



# Static and Wind Tunnel Aero-Performance Tests of NASA AST Separate Flow Nozzle Noise Reduction Configurations

Kevin L. Mikkelsen and Timothy J. McDonald  
Aero Systems Engineering, Inc., St. Paul, Minnesota

## The NASA STI Program Office . . . in Profile

Since its founding, NASA has been dedicated to the advancement of aeronautics and space science. The NASA Scientific and Technical Information (STI) Program Office plays a key part in helping NASA maintain this important role.

The NASA STI Program Office is operated by Langley Research Center, the Lead Center for NASA's scientific and technical information. The NASA STI Program Office provides access to the NASA STI Database, the largest collection of aeronautical and space science STI in the world. The Program Office is also NASA's institutional mechanism for disseminating the results of its research and development activities. These results are published by NASA in the NASA STI Report Series, which includes the following report types:

- **TECHNICAL PUBLICATION.** Reports of completed research or a major significant phase of research that present the results of NASA programs and include extensive data or theoretical analysis. Includes compilations of significant scientific and technical data and information deemed to be of continuing reference value. NASA's counterpart of peer-reviewed formal professional papers but has less stringent limitations on manuscript length and extent of graphic presentations.
- **TECHNICAL MEMORANDUM.** Scientific and technical findings that are preliminary or of specialized interest, e.g., quick release reports, working papers, and bibliographies that contain minimal annotation. Does not contain extensive analysis.
- **CONTRACTOR REPORT.** Scientific and technical findings by NASA-sponsored contractors and grantees.
- **CONFERENCE PUBLICATION.** Collected papers from scientific and technical conferences, symposia, seminars, or other meetings sponsored or cosponsored by NASA.
- **SPECIAL PUBLICATION.** Scientific, technical, or historical information from NASA programs, projects, and missions, often concerned with subjects having substantial public interest.
- **TECHNICAL TRANSLATION.** English-language translations of foreign scientific and technical material pertinent to NASA's mission.

Specialized services that complement the STI Program Office's diverse offerings include creating custom thesauri, building customized data bases, organizing and publishing research results . . . even providing videos.

For more information about the NASA STI Program Office, see the following:

- Access the NASA STI Program Home Page at <http://www.sti.nasa.gov>
- E-mail your question via the Internet to [help@sti.nasa.gov](mailto:help@sti.nasa.gov)
- Fax your question to the NASA Access Help Desk at 301-621-0134
- Telephone the NASA Access Help Desk at 301-621-0390
- Write to:  
NASA Access Help Desk  
NASA Center for AeroSpace Information  
7121 Standard Drive  
Hanover, MD 21076

NASA/CR—2001-210712



# Static and Wind Tunnel Aero-Performance Tests of NASA AST Separate Flow Nozzle Noise Reduction Configurations

Kevin L. Mikkelsen and Timothy J. McDonald  
Aero Systems Engineering, Inc., St. Paul, Minnesota

Prepared under Contract NAS3-98021

National Aeronautics and  
Space Administration

Glenn Research Center

Note that at the time of research, the NASA Lewis Research Center  
was undergoing a name change to the  
NASA John H. Glenn Research Center at Lewis Field.  
Both names may appear in this report.

Available from

NASA Center for Aerospace Information  
7121 Standard Drive  
Hanover, MD 21076  
Price Code: A14

Available electronically at <http://gltrs.grc.nasa.gov/CLTRS>

## TABLE OF CONTENTS

TABLE OF CONTENTS .....	iii
LIST OF FIGURES .....	iv
DEFINITION OF SYMBOLS .....	vi
1.0 INTRODUCTION.....	1
2.0 FACILITY DESCRIPTION.....	3
2.1 CHANNEL 14 STATIC THRUST STAND .....	3
2.2 WIND TUNNEL CHECKOUT FACILITY, CHANNEL 6 .....	4
2.3 TRANSONIC WIND TUNNEL, CHANNEL 10 .....	4
2.4 OPERATIONAL PROCEDURES.....	5
3.0 MODEL DESCRIPTION.....	7
3.1 MODEL ADAPTERS .....	7
3.2 MODEL COMPONENTS.....	8
3.3 MODEL INSTRUMENTATION.....	8
4.0 DATA ANALYSIS PROCEDURES.....	11
4.1 P <sub>i</sub> DEFINITIONS .....	11
4.2 T <sub>i</sub> DEFINITIONS .....	13
4.3 FLOW RATES .....	13
4.4 DISCHARGE COEFFICIENTS .....	17
4.5 THRUST MEASUREMENT .....	20
4.5.1 THRUST MEASUREMENT IN CHANNEL 14.....	20
4.5.2 THRUST MEASUREMENT IN CHANNEL.....	23
4.6 THRUST COEFFICIENT .....	25
4.6.1 CHANNEL14 STATIC THRUSTCOEFFICIENT .....	25
4.6.2 CHANNEL 10 WIND TUNNEL THRUST COEFFICIENT .....	27
4.7 PRESSURE AND TEMPERATURE DATA.....	28
4.8 FORCE BALANCE CALIBRATION.....	28
5.0 PRESENTATION OF RESULTS.....	31
5.1 ASME CHECKOUT NOZZLE TESTS .....	31
5.2 MODEL TESTS .....	32
6.0 REFERENCES .....	35
FIGURES	
ASE- FLUIDYNE PART DRAWINGS	
ASE- FLUIDYNE THRUST PARAMETERS	
DATA AND CALCULATIONS (under separate cover) .....	APPENDIX

## LIST OF FIGURES

<u>Figure</u>	<u>Description</u>	<u>Drawing</u>
1a	Channel 14 Static Thrust Stand	6051-0154
1b	Channel 14 Adapter Assembly	6051-0160
2a	Channel 10 Transonic Wind Tunnel	
2b	Channel 10 Aero-Lines	6229-021
3	Channel 10 Model Installation	
4	Channel 6 Static Thrust Stand	
5	Channel 14 Model Assembly	2212-001
6a	Channels 6 and 10 Model Assembly	2212-005
6b	Channels 6 and 10 Model Sting Assembly	2212-006
7	Station Notation, ASME Checkout Nozzle Tests, Channel 14	
8	Station Notation, ASME Checkout Nozzle Tests, Channel 6	
9	Station Notation, Channel 14 Model Tests	
10	Station Notation, Channels 6 and 10 Model Tests	
11	Tabulation of ASME Checkout Nozzle Test Results	
12a-c	Channel 14 ASME Checkout Nozzle Results- Plotted	
13a-b	Channel 6 ASME Checkout Nozzle Results - Plotted	
14	ASME Checkout Nozzle Photographs	
15a-n	Model Photographs	
16	Test Matrix and Model Configuration Definition	
17	Test Conditions and Major Test Results	
18	Channel 14 Static Test, Core Nozzle Discharge Coefficients	
19	Channel 14 Static Test, Fan Nozzle Discharge Coefficients	
20	Channel 14 Static Test, Thrust Coefficients	

- 21 Channel 6 Sting Checkout, Core Nozzle Discharge Coefficients
  - 22 Channel 6 Sting Checkout, Fan Nozzle Discharge Coefficients
  - 23 Channel 6 Sting Checkout, Thrust Coefficients
- 
- 24a-f Channel 10 Wind Tunnel, Core Nozzle Discharge Coefficients
  - 25a-f Channel 10 Wind Tunnel, Fan Nozzle Discharge Coefficients
  - 26a-f Channel 10 Wind Tunnel, Thrust Coefficients

Drawing List

Detailed Drawings

FluiDyne Thrust Parameter List

## DEFINITION OF SYMBOLS

A	Cross-section area, in <sup>2</sup>
AP	(Channel 10) Pitching moment at aft balance bridge, inlb <sub>f</sub>
A*	Sonic throat area, in <sup>2</sup>
b	Real-gas ideal thrust function correction, dimensionless
B <sub>j</sub>	Balance readout, millivolts
c	Real-gas A/A* correction factor, dimensionless
C <sub>D</sub>	Discharge coefficient, dimensionless
C <sub>DA</sub>	Effective area, in <sup>2</sup>
C <sub>T</sub>	Thrust coefficient, dimensionless
d	Diameter, inches
f	Exit stream thrust parameter, dimensionless
F	Stream thrust, $(1 + \gamma M^2)$ PA, lb <sub>f</sub>
FP	(Channel 10) Pitching moment at forward balance bridge, inlb <sub>f</sub>
g	Acceleration of gravity, 32.174 ft/sec <sup>2</sup>
G	Real gas stream thrust correction factor, dimensionless
H <sub>0</sub>	Axial balance force (unpressurized calibration), lb <sub>f</sub>
H <sub>2</sub>	Axial balance force corrected for seal tare, lb <sub>f</sub>
H <sub>r</sub>	Resultant thrust, lb <sub>f</sub>
H <sub>x</sub>	Axial thrust, lb <sub>f</sub>
H <sub>y</sub>	Vertical thrust, lb <sub>f</sub>
K	Real-gas mass flow function, °R <sup>1/2</sup> /sec
K <sub>ij</sub>	Balance force calibration factors, lb <sub>f</sub> /millivolt
L <sub>bal</sub>	Axial distance between vertical bridges V1 and V3, inches
L <sub>ref</sub>	(Channel 14) Axial distance from the balance center to the model reference plane at exit of fan nozzle : 2078-001 (for Ch14 L <sub>ref</sub> = 68.625 inches)
L <sub>ref</sub>	(Channel 10) Axial distance from the balance downstream pitching moment bridge (AP) to the model reference plane at exit of fan nozzle : 2078-001 (for Ch10 L <sub>ref</sub> =34.77 inches)

$L_x$	Axial distance to the intersection of the resultant thrust vector with the model centerline, measured from the model reference plane, positive downstream of the reference plane (also referred to as "Station Ly" on the Channel 14 output sheet), inches
$L_y$	(Channel 14): Axial distance from the balance center to the intersection of the resultant thrust vector with the facility lower centerline, inches
$L_y$	(Channel 10): Vertical displacement of resultant thrust vector at the reference plane, measured from nozzle centerline to the intersection of the thrust vector and the reference plane, positive upward, inches
$m$	Mass flow rate, slugs/second
$M$	Mach number, dimensionless
$M_o$	(Channel 14) Pitching moment about the intersection of the balance center and the model centerline, positive clockwise with flow left to right, ( $=L_y H_y$ ), inlb <sub>f</sub>
$M_o$	(Channel 10) Pitching moment about the intersection of the reference plane and the model centerline, positive clockwise with flow left to right, ( $=L_x H_y$ ), inlb <sub>f</sub>
$P$	Pressure, static unless otherwise specified by subscript, psia
$\Delta P$	Static pressure difference across seal, psid
$r$	Radius from centerline, inches
$\Delta r$	(Channel 14) Vertical displacement of resultant thrust vector at the reference plane, measured from nozzle centerline to the intersection of the thrust vector and the reference plane (equivalent centerline for dual-flow ASME nozzles) positive above centerline, inches
$R$	Gas constant, 1716.32 ft <sup>2</sup> /sec <sup>2</sup> °R
$R_N$	Reynolds number, dimensionless
$T$	Temperature, °R (unless stated as °F)
$V_1, V_3$	(Channel 14) Vertical balance forces, lb <sub>f</sub>
$v$	Velocity, ft/sec

$W$	Mass flow rate, $\text{lb}_m/\text{sec}$
$W_x, W_y$	Dead-weight calibration loads, $\text{lb}_f$
$y$	Distance from wall
$\alpha$	Thrust vector angle, degrees
$\gamma$	Ratio of specific heats, dimensionless
$\delta$	Boundary layer thickness
$\theta$	Meridian angle measured clockwise from top looking upstream, degrees
$\lambda$	Pressure ratio, $P_t/P_a$ , dimensionless
$\rho$	Density, slugs/ $\text{ft}^3$
$\Sigma$	Summation
$\Delta$	Incremental quantity
$\tau$	Temperature ratio, $T_{t_8}/T_{t_7}$ , dimensionless
$\eta$	Temperature difference ratio, $(T - T_{t_7})/(T_{t_8} - T_{t_7})$ , dimensionless

Subscripts

a	Ambient
e	Exit
i	Ideal
i,j	Counter for summations
mp	Mixing plane
r	Resultant
t	Total conditions
w	Wall
x	Axial component
y	Vertical component
$\infty$	Freestream
1,2,...	See Figures 7-10

Superscript

\* Sonic condition,  $M = 1$

## 1.0 INTRODUCTION

This cold-flow model study investigated the static and simulated in-flight performance of several NASA Advanced Subsonic Technology (AST) separate flow nozzle noise reduction configurations. The tests were conducted at ASE's FluiDyne Laboratory located in Plymouth, Minnesota. Tests were conducted in the Channel 14 static thrust stand, the Channel 6 wind tunnel sting checkout facility, and the Channel 10 transonic wind tunnel. In Channels 14 and 6 the model exhausts directly to atmosphere. Channel 6 is used to check-out the wind tunnel sting, force balance, and model prior to transporting the sting system into the 66x66 inch transonic wind tunnel.

The test program was defined by NASA test specifications with some changes as the test progressed. Technical liaison for NASA LeRC was performed by Mr. Naseem Saiyed. The model was designed and fabricated by ASE-FluiDyne using aerodynamic lines furnished by customers on prior jobs (Jobs 2078 & 2087) and tested previously at NASA LeRC for acoustics. Some new model-to-facility adapter hardware were fabricated for the present job. Existing adapters were used where possible to minimize the cost. Consequently, the charging station contours are different between the static and wind tunnel tests.

This report describes the test facility, test model, data acquisition and analysis procedures, and presents the test results. Test conditions and major test results are tabulated in Figure 17. Detailed data and calculations are contained in a separate Appendix. Detailed part drawings are included at the end of this report.



## **2.0 FACILITY DESCRIPTION**

The tests were performed at the FluiDyne Laboratory in the Channel 14 static thrust stand, the Channel 6 static stand for wind tunnel sting checkout, and the Channel 10 transonic wind tunnel.

### **2.1 Channel 14 Static Thrust Stand**

Channel 14 is a dual passage hot-cold flow static stand used to determine performance of exhaust nozzle models. Nozzle thrust is determined from force measurement with a strain-gage force balance. Model air is metered and ducted to the model through two separate passages; see Figure 1a. The general arrangement of Channel 14 is shown in Figures 1 and 9. While the current tests were with cold flow only, the general description of the facility below includes its hot flow capability.

The airflows for both the cold and hot passages of a test nozzle are obtained from the facility 500 psi dry air storage system. Air for the cold passage is throttled, metered through a long-radius ASME nozzle, ducted to the cold passage of the test nozzle, and finally exhausted to atmosphere. Air for the hot passage is throttled, passed through a regenerative storage heater, mixed with unheated bypass flow to achieve a desired temperature, metered through a long-radius ASME nozzle, ducted to the hot passage of the test nozzle, and finally exhausted to atmosphere.

The air heater used for the hot flow contains alumina pebbles which are preheated to approximately 1250°F with a combustion heater. The Channel 14 heater capacity is nominally 30 lbs/sec at 1400°F (1600°F if heater liner is changed to Inconel).

The model assembly is supported by a 3-component strain-gage force balance and is isolated from the facility piping by two elastic seals; see schematic in Figures 1 and 9. Calibration of the balance and seals is described in Section 4.8.

The ASME meter at Station 1 is water-cooled to protect the elastic seal from thermal effects. Since the cooling water is confined to the upstream (i.e., non-metric) hardware only, no tare forces are introduced by the water supply lines.

Facility instrumentation is provided to calculate mass flow rates at Stations 1 and 4, and to calculate the exit thrust produced by the test nozzle; details are described in Section 4.

## **2.2 Wind Tunnel Checkout Facility, Channel 6**

Channel 6 is the static ( $M=0$ ) wind tunnel setup and checkout facility used prior to the Channel 10 wind tunnel. Figure 4 shows the arrangement of Channel 6. Channel 6 consists of piping which supplies dried, heated air from the 2500 psi air storage system to the sting mounted flow-through force balance. This facility allows checkout of the model (exhausting to atmosphere), balance, instrumentation and data acquisition systems before the sting is installed in the wind tunnel(Channel 10). Proper performance of this facility was demonstrated by testing a standard 5.7 inch diameter ASME nozzle. In addition, the baseline model configuration 1 (3BB) was tested statically in both Channels 6 and 14 to confirm agreement. Channel 14 is the more accurate facility for measuring static performance.

## **2.3 Transonic Wind Tunnel, Channel 10**

Channel 10 is a transonic wind tunnel having a 66 inch x 66 inch test section with slotted upper and lower walls. Figures 2a and 2b show overall views of the

tunnel and Figure 3 shows a model installation for exhaust nozzle tests. This is an induction-type tunnel in which atmospheric air is drawn through the test section using air ejectors to reduce the downstream pressure. The required test section Mach number is obtained by controlling the mass flow to the ejectors. Tunnel Mach number for the present tests was controlled to  $M = 0.28$  and  $0.80$ . At Mach .8, water condensation in the test section is avoided by burning propane upstream of the inlet.

The exhaust nozzle model and the force balance system are supported in the test cell by a cantilevered tube (or sting) that projects through the contraction into the test section. This 10 inch diameter sting flares to 14.5 inch diameter to match the model diameter at the beginning of the slotted wall test section. The model support tube consists of two concentric pipes with the model air (obtained from the 2500 psi storage system) being supplied to the model through the inner pipe. Thinning of the boundary layer on the support tube was achieved by using the facility vacuum system( $33500 \text{ ft}^3$ ) to remove the low energy air adjacent to the tube through a perforated section upstream of the test model. This air is removed through the outer pipe in the sting. Figure 10 shows a schematic of this boundary layer removal system.

The boundary layer thickness on the support tube was measured with a total pressure rake located 1 inch upstream of the metric break at  $\theta = 0$  degrees (top). Boundary layer thicknesses are discussed in Section 3.3.

The performance data taken in Channel 10 were obtained by force measurement using a dual passage flow through strain gage force balance system. This system consists of two choked ASME metering nozzles, two flexible seals, and a five component force balance.

## **2.4 Operational Procedures**

Flow conditions for the Channel 14 static tests were set by independently regulating the airflow to the fan and core meters to obtain the desired  $P_{t7}/P_a$  and  $P_{t8}/P_a$ . The model air was preheated to room temperature for these tests.

Flow conditions in Channels 6 and 10 were set by regulating the total air flow to obtain the desired  $P_{t7}/P_a$ , while adjusting a motorized flow splitter to obtain the desired  $P_{t7}/P_{t8}$ . The motorized flow splitter utilizes a sliding choke plate arrangement to vary area and divide flow between the fan and core passages. (Splitter 6051-8115-2, Choke plates: C1= 6070-6158-4, F1=6070-6158-2) External flow Mach number in Channel 10 was set using the tunnel air ejectors. Model support tube boundary layer suction was adjusted with sting vacuum control to reduce the boundary layer thickness to better simulate freestream conditions. Upstream tunnel propane burners were ignited to produce a freestream air temperature rise to prevent test section water vapor condensation at higher Mach numbers. The test section freestream flow was monitored with a video camera to confirm there was no cloud of water vapor condensation in the test section. Test section total temperature was typically 120 F at M=0.8.

### **3.0 MODEL DESCRIPTION**

#### **3.1 Model Adapters**

The test model was attached to common adapting hardware in Channel 14 (Figures 1a-b) which supplied separately-metered flows to the fan and core nozzles. The fan and core air flow was nominally at 70°F temperature for all tests.

Figures 1b (6051-0160) and 5 (2212-001) illustrate major adapters for Channel 14 tests. Adapters for the core passage included an insulated duct, a choke plate, four screens, a centerbody with three struts, and a primary duct to which interchangeable mixers attached. The tailcone or plug was common to all configurations. Adapters for the annular fan passage included a choke plate, two screens, a bellmouth contraction, and a common outer bypass duct. Spacers were fabricated to position the hardware in axial locations corresponding to the cold aero-design lines per NASA specification. These design lines were defined to ASE-FluiDyne for fabrication Jobs 2078 and 2087 and are depicted on the drawings.

Figures 6a and 6b (2212-005, -006) illustrate major adapters for Channels 6 and 10 tests. Adapters for the core passage included two choke plates, four screens, a charging station, a centerbody with three struts, and a primary duct to which interchangeable mixers attached. Adapters for the annular fan passage included two choke plates, four screens, a charging station, and a common outer bypass duct to which interchangeable fan nozzles were attached. The hardware were positioned in axial locations corresponding to the cold aero-design lines per NASA specification.

### **3.2 Model Components**

The test model hardware adapters were designed and fabricated by the ASE FluiDyne Laboratory. The nozzle models were fabricated by ASE under previous jobs using aerodynamic lines and instrumentation locations specified by the customer. Aero-lines correspond to the cold aero-design lines from Jobs 2078 and 2087 per NASA specification. Figures 5, 6a, and 6b show assembly drawings of the test model. Detail drawings of the model hardware are contained in the last section of this report. Photographs of model assemblies and components are shown in Figure 15. Model configuration definitions are documented in Figure 16. The major interchangeable components were the core nozzle and the fan nozzle. The plug was common to all configurations.

The plug was designed with a vent hole. This was left open during all tests including wind tunnel tests with sub-barometric pressure in the test section. The plug tip was modified on a previous test program, and a screw was installed in the aft tip. This screw remained in the plug for the present test.

### **3.3 Model Instrumentation**

In Channel 14 charging station instrumentation for the fan passage consisted of four 12-probe area-weighted rakes ( $P_{t7}$ ) and three 5-probe thermocouple rakes ( $T_{t7}$ ). Associated with each total pressure rake was an inner and outer wall static pressure tap ( $P_{s7}$ ). Core nozzle charging instrumentation consisted of four 5-probe total pressure rakes ( $P_{t8}$ ), two 4-probe, and two 2-probe total temperature rakes ( $T_{t8}$ ). Also associated with each total pressure rake was an outer wall static pressure tap ( $P_{s8}$ ). An inner wall static pressure tap was not available.

In Channels 6 and 10 charging station instrumentation for the fan passage consisted of four 12-probe area-weighted rakes ( $P_{t7}$ ). Associated with each total pressure rake was an inner and outer wall static pressure tap ( $P_{s7}$ ). Core nozzle charging instrumentation consisted of four 5-probe total pressure rakes ( $P_{t8}$ ). Also associated with each total pressure rake was an inner and outer wall static pressure tap ( $P_{s8}$ ).

For the wind tunnel test, ten external static pressure taps were installed on the baseline fan nozzle (2078-001). These pressure taps were installed to provide information for the calculation of boat-tail drag of the fan nacelle.

The model support sting boundary layer total pressure profile was measured with an 11 probe boundary layer rake (6051-4281-1) located 1 inch upstream of the metric break. The boundary layer thicknesses were larger than usual because of the larger size model in combination with a fixed vacuum system capability. The model size was a result of previous test programs. In the tunnel, a sting boundary layer profile generated by vacuum suction is superimposed onto a larger boundary layer profile approaching the perforated section. Near the sting surface the vacuum dominates, and the velocity gradients are large. Farther from the sting surface the original velocity profile remains, and a small velocity gradient persists. Boundary layer thicknesses were calculated using two methods and are documented in the Data Appendix.

The first method calculates overall thicknesses from the combined vacuum-plus-original-profile and results in the following:

Data Point 58.02,  $\delta_1$  [99% $(V/V_{inf})$ ] = 0.92 inches ( $M=0.8$ )

Data Point 55.03,  $\delta_1$  [99% $(V/V_{inf})$ ] = 0.24 inches ( $M=0.28$ )

The second method considers only the boundary layer shape created by the vacuum which is superimposed onto the larger shape. Since the largest velocity gradients are

in this section of the profile, this definition may be useful. Thicknesses calculated using this method are listed below.

Data Point 58.02,  $\delta_2 [99\% (V/V_{inf})] = 0.63$  inches ( $M=0.8$ ).

Data Point 55.03,  $\delta_2 [99\% (V/V_{inf})] = 0.21$  inches ( $M=0.28$ )

During the program, experiments at  $M=0.8$  demonstrated that the boundary layer thickness could be decreased by about 45% by reducing the length of the perforated section of the covers by 1/3<sup>rd</sup> (eliminating the first third of the bleed section length).

However, this bleed configuration was never employed for the actual test data.

## 4.0 DATA ANALYSIS PROCEDURES

The following subsections describe the data analysis procedures used for the present tests. Station notations are defined in Figures 7-10. Computerized data reduction programs written in BASIC language are included in the Data Appendix.

### 4.1 $P_t$ Definitions

In Channel 14, charging station instrumentation for the fan passage consisted of four 12-probe area-weighted rakes ( $P_{t7}$ ). Each total pressure rake was associated with an inner and outer wall static pressure tap ( $P_{s7}$ ). Core nozzle charging station instrumentation consisted of four 5-probe total pressure rakes ( $P_{t8}$ ). Each total pressure rake was associated with an outer wall static pressure tap ( $P_{s8}$ ). For the core duct, the inner wall static pressure was assumed equal to the outer wall static pressure (part 0946-001-2 was used).

In Channels 6 and 10 charging station instrumentation for the fan passage consisted of four 12-probe area-weighted rakes ( $P_{t7}$ ). Each total pressure rake was associated with an inner and outer wall static pressure tap ( $P_{s7}$ ). Core nozzle charging instrumentation consisted of four 5-probe total pressure rakes ( $P_{t8}$ ). Each total pressure rake was associated with an inner and outer wall static pressure tap ( $P_{s8}$ ).

The mass-momentum method was used to determine total pressures in the ducts. A summary of the mass-momentum method is given below.

Mass-momentum average model charging station total pressures were determined as follows. For flows with nearly-uniform total pressure profiles, the average total pressure may be obtained by simply area-weighting individual probe

measurements. For flows with non-uniform total pressure profiles, however, a more accurate measure of the average total pressure is obtained from the mass-momentum method (Reference 5). This method represents a non-uniform flow by average properties that simultaneously satisfy both the mass flow and the momentum of the real flow.

From continuity:

$$PAM \sqrt{\frac{\gamma}{RT} \left(1 + \frac{\gamma - 1}{2} M^2\right)} = \sum P_j A_j M_j \sqrt{\frac{\gamma}{RT_j} \left(1 + \frac{\gamma - 1}{2} M_j^2\right)}$$

and from momentum:

$$PA (1 + \gamma M^2) = \sum P_j A_j (1 + \gamma M_j^2)$$

where the individual  $A_j$  were determined from the flow path and rake geometry,  $P_j$  is assumed to vary linearly between the inner and outer wall,  $P_t$  is measured directly, and

$$M_j = \sqrt{\frac{2}{\gamma - 1} \left[ \left( \frac{P_t}{P} \right)^{\frac{\gamma - 1}{\gamma}} - 1 \right]}$$

If total temperature is assumed constant in the passage, then:

$$\frac{M \sqrt{1 + \frac{\gamma - 1}{2} M^2}}{1 + \gamma M^2} = \frac{\sum P_j A_j M_j \sqrt{1 + \frac{\gamma - 1}{2} M_j^2}}{\sum P_j A_j (1 + \gamma M_j^2)}$$

The right side of the above equation is calculated by summation from the measured quantities. Squaring the above equation results in a quadratic (with variable  $M^2$ ),

which is readily solved for a unique value of the effective Mach number,  $M$ , satisfying the stated requirements. Knowing the effective Mach number, the effective static pressure,  $P$ , is determined from the preceding continuity equation, and finally, the effective total pressure is calculated from:

$$P_t = P \left( 1 + \frac{\gamma - 1}{2} M^2 \right)^{\frac{\gamma}{\gamma - 1}}$$

For the present test the total pressure profile at each of the charging station rakes was integrated using the mass-momentum technique. The average charging station total pressure was then defined as the average from the separate rake integrations.

#### 4.2 $T_t$ Definitions

$T_{t1}$  and  $T_{t4}$  were measured with facility thermocouples. For all model and ASME checkout nozzle tests,  $T_{t7}$  and  $T_{t8}$  were calculated from  $T_{t4}$  and  $T_{t1}$ , respectively, by subtracting the temperature drop due to adiabatic throttling of flow between the meter station and the nozzle charging station. The temperature drop was calculated from Joule-Thomson throttling values (Reference 4) and typically varied between 1° and 6°F. Measured values of  $T_{t7}$  were acquired but not used in the data reduction. Measured values of  $T_{t8}$  were acquired in Channel 14 only and were not used in the data reduction.

#### 4.3 Flow Rates

The mass flow rates through the test nozzles were determined using choked ASME long-radius metering nozzles. The core nozzle flow rate was calculated at

Station 1 and the fan nozzle flow rate was calculated at Station 4 using the following equations.

$$W_1 = W_8 = \frac{K_1 C_{D_1} A_1 P_{t_1}}{\sqrt{T_{t_1}}}$$

$$W_4 = W_7 = \frac{K_4 C_{D_4} A_4 P_{t_4}}{\sqrt{T_{t_4}}}$$

The critical flow factor, K, was calculated as a function of total pressure and total temperature.

Channel 14:

$$K = 0.52820 + a T_t + b T_t^2 + c T_t^3 + 0.186 \times 10^{-4} P_t e^{-0.0067(T_t - 500)}$$

where

$$a = 0.1654 \times 10^{-4}$$

$$b = -0.2119 \times 10^{-7}$$

$$c = 0.6008 \times 10^{-11}$$

$T_t$  is in °R and  $P_t$  is in psia.

This equation was obtained by curve-fitting tabulated values in References 1 and 4; the curve-fit is accurate to within  $\pm 0.03\%$  for  $0 < P_t < 30$  atmospheres and  $460 < T_t < 700$ °R, and is accurate to within  $\pm 0.1\%$  for  $0 < P_t < 40$  atmospheres and  $460 < T_t < 1800$ °R.

In Channels 6 and 10, K was calculated using a different equation. K was calculated as a function of total pressure and temperature from a different curve fit of Reference 1 data.

Channel 6 & 10:

$$K = 0.776615 [ (0.68166 + 1.36243E-5 T_t - 1.43545E-8 T_t^2) \\ + (2.14835E-4 - 6.06496E-7 T_t + 4.49456E-10 T_t^2) P_t \\ + (5.4424E-8 - 1.90568E-10 T_t + 1.64438E-13 T_t^2) P_t^2 ]$$

where  $P_t$  (psia) = 0 to 1100 psia

$T_t(R)$  = 460 to 600 R

Throat Reynolds numbers at Stations 1 and 4 were calculated using the following equation from Reference 3.

$$R_N = 1.50994 \times 10^7 \frac{P_t M d \left[ T_t \left( 1 + .2 M^2 \right)^{-1} + 198.6 \right]}{T_t^2 \left( 1 + .2 M^2 \right)^{1.5}}$$

where all parameters pertain to the desired station.

$C_{D_4}$  was calculated using a semi-empirical equation

$$C_{D_4} = 1 - 0.184 R_{N_4}^{-0.2} .$$

For cold flow,  $C_{D_1}$  can be calculated with an equation of the same form as above. For hot flow, the  $C_{D_1}$  equation is modified to account for a thermal boundary layer. This thermal boundary layer results from water-cooling of the Station 1 meter.

$$C_{D_1} = 1 - \left( 0.184 R_{N_1}^{-0.2} \right) \left( 1.574 - 0.574 T_{t_1} / T_w \right)$$

For some hot tests at low flow rates, the above equation (for turbulent flow) can be modified slightly (corresponding to transitional boundary layer flow). The above equation was derived assuming: constant static pressure in the boundary layer, a 1/7<sup>th</sup> power velocity profile, thermal boundary layer thickness equal to velocity boundary layer thickness, and a density distribution in the boundary layer defined by

$$\frac{\rho}{\rho_{\infty}} = \frac{T_{\infty}}{T_w} \cdot \left( \frac{T_{\infty}}{T_w} - 1 \right) \left( \frac{y}{\delta} \right)^{1/7} .$$

$T_w$ , the wall temperature at the nozzle throat, is estimated for hot flow tests from heat-balance calculations of heat transfer from the air stream to the cooling water.  $T_w$  values calculated are typically 95° to 165°F.  $R_{N_1}$  is calculated using a mean temperature,  $(T_w + T_{t_1})/2$ . Given sufficient wall cooling,  $C_{D_1}$  may exceed unity (Reference 2).

The above equation for "hot"  $C_{D_1}$  is believed to be correct within ±0.0025, on the basis of results from facility demonstration tests. These demonstration tests included test series with either a 2.5-inch or a 4-inch diameter ASME nozzle located downstream of the water-cooled Station 1 meter. The downstream nozzle was essentially at adiabatic conditions (thin-wall construction, backside insulated). Flow rates calculated at Station 1 (using the above  $C_{D_1}$  equation) agreed within ±0.25% with flow rates calculated at the downstream nozzle (using adiabatic wall  $C_D$ ).

In Channel 14,  $A_4$ , the geometric throat area of the Station 4 meter, was 4.9029 in<sup>2</sup>. The geometric throat area of the Station 1 meter was 1.3507 in<sup>2</sup>. For hot core flow tests,  $A_1$  is calculated assuming thermal expansion from 70°F to  $T_w$ . In Channels 6 and 10,  $A_1=1.3283$  in<sup>2</sup> and  $A_4=1.3304$  in<sup>2</sup>.

In Channel 14, core meter pressure,  $P_{t1}$ , was measured using total pressure probes. Fan meter total pressure,  $P_{t4}$ , was calculated using the measured static pressure and the isentropic pressure ratio for the A/A\* at the meter charging station duct location, i.e.  $P_{t4}=1.0023 P_{s4}$ .

In Channels 6 and 10, both core and fan meter pressures were calculated using the measured static pressures and the isentropic pressure ratios for the A/A\* at the meter charging station duct locations, i.e.  $P_{t1}=1.0262 P_{s1}$  and  $P_{t4}=1.0262 P_{s4}$ .

$T_{t1}$  and  $T_{t4}$  were measured with shielded thermocouple probes and were recorded on the facility data acquisition system.

Flow rates (lbm/sec) calculated for the present tests were in the ranges:

For Channel 14:       $2.94 < W_8 < 7.18$        $12.88 < W_7 < 20.23$

For Channel 6:       $4.13 < W_8 < 6.05$        $15.49 < W_7 < 18.79$

For Channel 10:       $4.31 < W_8 < 5.94$        $15.0 < W_7 < 18.0$

#### 4.4 Discharge Coefficients

Discharge coefficient is defined as the ratio of the actual flow rate through a nozzle to the ideal isentropic flow rate at the overall nozzle pressure ratio. Overall nozzle pressure ratios are defined as  $\lambda_7 = P_{t7}/P_a$  and  $\lambda_8 = P_{t8}/P_a$ . In a static thrust stand,  $P_a$  is atmospheric pressure. In the wind tunnel,  $P_a$  is the test section static pressure. Fan and core nozzle discharge coefficients are then

$$C_{D7} = W_7/W_{7i} \text{ and } C_{D8} = W_8/W_{8i}$$

where

$$W_{7_i} = P_{t_7} A_7 K_7 (A^* / A) / \sqrt{T_{t_7}}$$

$$W_{8_i} = P_{t_8} A_8 K_8 (A^* / A) / \sqrt{T_{t_8}}.$$

$P_{t_7}$ ,  $P_{t_8}$ ,  $T_{t_7}$ , and  $T_{t_8}$  were defined in Sections 4.1 and 4.2.  $K_7$  and  $K_8$  were evaluated using previous equations, as functions of  $P_{t_7}$ ,  $T_{t_7}$ ,  $P_{t_8}$  and  $T_{t_8}$ .

Actual reference areas  $A_7$  and  $A_8$  were not defined for noise reduction configurations. Therefore fan and core nozzle discharge coefficients were calculated using the baseline areas. Baseline areas were calculated using design contours adjusted for assembled “tip to tip” inspections defining the relative axial locations of the fan, core, and centerbody parts. Calculated areas are listed in the following table.

NOZZLE	DRAWING	CH14 AREA (in <sup>2</sup> )	CH10 AREA (in <sup>2</sup> )
Baseline Fan (3BB)	2078-001	30.2491	30.2944
Baseline Core (3BB)	2078-405	10.5553	10.5553

For Channel 14 ASME checkout nozzle tests, the throat area of the 7.1-inch nozzle was  $A_7 = 39.5897$  in<sup>2</sup>. The throat area of the 4-inch nozzle was  $A_8 = 12.5613$  in<sup>2</sup> for cold tests. In Channel 6, the throat area of the 5.7 inch ASME checkout nozzle was 25.4994 in<sup>2</sup>.

$A^*/A$ , the isentropic area ratio, is used to correct the ideal flow rate when the nozzle is unchoked.  $A^*/A$  for cold flow was calculated using equations valid for  $\gamma = 1.4$ , obtained from Reference 3.

$$A^*/A = 3.86393 \lambda^{0.71429} \sqrt{1-\lambda^{-0.28571}} \text{ for } \lambda < 1.8929$$

and

$$A^*/A = 1 \text{ for } \lambda \geq 1.8929.$$

$A^*/A$  for hot core nozzle tests are obtained by correcting the  $\gamma = 1.4$  value for "real gas effects," to account for  $\gamma_8$  being significantly less than 1.4. The correction was derived by curve-fitting tabulated values from Reference 4; no corrections are indicated for  $T_t < 900^\circ R$ . First, the critical pressure ratio was expressed as a function of total temperature:

$$1/\lambda^* = 9.667 \times 10^{-6} T_t (^\circ R) + 0.5196$$

If  $\lambda > \lambda^*$ , then  $A^*/A = 1$ . If  $\lambda < \lambda^*$  and  $900 < T_t < 1260^\circ R$ ,

$$c = 1 + \left( \frac{1}{\lambda} - \frac{1}{\lambda^*} \right) 5.728 \times 10^{-5} (T_t - 900)$$

If  $\lambda < \lambda^*$  and  $1260 < T_t \leq 1800^\circ R$ ,

$$c = 1 + \left( \frac{1}{\lambda} - \frac{1}{\lambda^*} \right) [2.615 \times 10^{-5} (T_t - 1260) + 0.020621].$$

Finally,

$$A^*/A = c \times (A^*/A)_{\gamma=1.4} .$$

For the present cold flow tests,  $c$  is 1.000.

## **4.5 Thrust Measurement**

Model thrust is measured by a highly accurate force balance system with a control volume approach to account for entering stream thrusts and other pressure-area terms. Forces caused by the elastic seals which separate the balance system from the facility piping are also accounted for. The measurement of thrust is described below for Channels 14 and 10 separately.

### **4.5.1 Thrust Measurement in Channel 14**

The net static axial thrust of an exhaust nozzle is defined as the axial exit momentum of the exhaust flow, plus the excess of exit pressure over ambient pressure times the projected exit area.

$$H_x = mv_{ex} + (P_e - P_a) A_{ex}$$

The net static thrust of an exhaust nozzle model was determined in the present test program by applying the momentum equation to the control volume shown in Figures 7 and 9. The analysis of axial forces applied to the control volume includes entering stream thrusts ( $F_1$  and  $F_4$ ), a balance force ( $H_2$ ), various pressure-area terms and the axial exit stream thrust, ( $H_x + P_a A_{ex}$ ). The axial balance force,  $H_2$ , as used here, includes seal tare forces. Summing axial forces,

$$H_x = F_1 + F_4 + P_2(A_2 - A_1) + P_5(A_5 - A_4) - P_a(A_2 + A_5) - H_2 .$$

The stream thrust at Station 4 is the exit stream thrust of a choked long-radius ASME nozzle, and was calculated as:

$$F_4 = G_4 (1 + 1.4 C_{D_4} C_{T_4}) .52828 P_{t_4} A_4 .$$

Use of  $\gamma = 1.4$  and  $P^*/P_t = .52828$  in the above equation implies an ideal gas. The factor  $G$ , derived from tabulated values in References 1 and 4, corrects the stream thrust from that of an ideal gas to that of a real gas.

$$\text{If } T_t < 560^\circ\text{R}, G = 1.00012 + 6.8338 \times 10^{-6} P_t (\text{psia})$$

$$\text{If } T_t > 560^\circ\text{R}, G = 1.0044 - (4.196 - .0059 P_t) (T_t + 460) \times 10^{-6}$$

$C_{D_4}$  has already been discussed;  $C_{T_4}$  was calculated in an analogous manner,

$$C_{T_4} = 1 - 0.109 R_{N_4}^{0.2} .$$

This equation is a semi-empirical expression of the thrust coefficient of an ASME nozzle at a pressure ratio of  $\lambda = 1.8929$  (corresponding to  $P^*/P_t = .52828$ ). For the present tests,  $G_1$  typically varied from 1.000 to 1.002,  $G_4$  from 1.000 to 1.004, and  $C_{T_4}$  from 0.9954 to 0.9962.

The stream thrust at Station 1 was calculated as:

$$F_1 = G_1 (1 + 1.4 C_{D_1} C_{T_1}) .52828 P_{t_1} A_1 .$$

Each variable in this equation has been previously described, except  $C_{T_1}$ .  $C_{T_1}$  was calculated in a similar manner as  $C_{T_4}$ , but is modified for hot flow tests to account for the thermal boundary layer described in the discussion of  $C_{D_1}$  in Section 4.3:

$$C_{T_1} = 1 - \left(0.109 R_{N_1}^{-0.2}\right) \left(0.828 + 0.172 T_{t_1} / T_w\right).$$

The above equation was derived using the same assumptions as in the derivation of  $C_{D_1}$ .  $C_{T_1}$  for the present cold flow tests varied from 0.9946 to 0.9955.

$P_2$  and  $P_5$  are seal cavity static pressures which act over areas determined by the seal area ( $A_2-A_1$ ) or ( $A_5-A_4$ ). Static pressures  $P_2$  and  $P_5$ , and test area ambient pressure ( $P_a$ ), were measured with PSI pressure transducers.  $A_2$  and  $A_5$ , the geometric reference areas for the seals, were 3.500 and 7.0686 in<sup>2</sup>, respectively. The balance force and seal tare calibrations are described in Section 4.8.

The vertical thrust,  $H_y$ , was obtained from the vertical force balances:

$$H_y = V_1 + V_3.$$

The resultant thrust,  $H_r$ , was calculated as the vector sum of the axial thrust,  $H_x$ , and the vertical thrust,  $H_y$ . Resultant thrust vector angle,  $\alpha$ , was determined as:

$$\alpha = \tan^{-1}(H_y/H_x).$$

The sign convention for positive values of thrust components and vector angle is defined in Figures 8 and 10. **At ASE-FluiDyne, positive vertical thrust is defined as pointing downward as a result of historical balance calibration procedures.** The location of the resultant thrust vector was determined by summation of moments and is described by the axial distance between the

intersection of the thrust vector and the facility centerline to the intersection of the reference plane and the facility centerline ( $L_x$ ). The reference plane for all configurations is the baseline fan nozzle exit plane.

$$\begin{aligned}
 L_{ref} &= \text{distance from balance center to model reference plane (fan exit)} \\
 L_x &= L_y - L_{ref} \quad (\text{see above, positive downstream from ref. plane}) \\
 L_y &= -(V_1 - V_3)(L_{bal}/2) / H_y \quad (\text{distance from balance center to vector intersection} \\
 &\qquad \qquad \qquad \text{with model centerline}) \\
 M_o &= L_y H_y \quad (\text{moment about balance center}) \\
 \Delta r &= (L_{ref} - L_y) \tan \alpha \quad (\text{vertical distance from model centerline to inter-} \\
 &\qquad \qquad \qquad \text{section of vector with ref. plane, positive upward})
 \end{aligned}$$

#### 4.5.2 Thrust Measurement in Channel 10

The thrust coefficient (in-flight) of an exhaust nozzle is defined as the ratio of the measured nozzle thrust-minus-drag, to the ideal thrust of the actual mass flow expanded to ambient pressure. The actual thrust-minus-drag of an exhaust nozzle can be determined indirectly by applying the momentum equation to the control volume shown in Figure 10. The analysis of forces applied to the boundaries of the control volume includes entering and exit stream thrust, the balance force ( $H_2$ ) and various pressure area terms. Thus, the actual thrust equation can be written from the summation of forces as:

$$H_x = F_1 + F_4 + P_2 (A_2 - A_1) + P_5 (A_5 - A_4) + P_3 (A_3 - A_2 - A_5) - P_a A_3 - H_2$$

where  $P_3$  is the pressure inside the cavity surrounding the seal and load cell, and  $A_3$  is the sting support tube cross sectional area ( $A_3 = 164.675 \text{ in}^2$  or 14.48 inch diameter). The 10 inch diameter upstream tube has a cross sectional area of 78.54

$\text{in}^2$ . The nozzle exit thrust term,  $H_x$ , includes form and friction drags due to the external flow.

$F_1$  and  $F_4$  were calculated as described in Section 4.4, except that the real-gas correction  $G$  was calculated from

$$G = 1.00011 + AP_t + BP_t^2 - C(T_t - 560)P_t^{1.9477}$$

$$\text{where } A = 0.601347 \times 10^{-5}$$

$$B = 1.50556 \times 10^{-9}$$

$$C = 2.2751 \times 10^{-11}$$

This equation was obtained by curve fitting tabulated data from Reference 1, and applies for  $460 < T_t < 560$  R and  $0 < P_t < 1000$  psia.

$P_2$  and  $P_5$  are seal cavity static pressures which act over the seal areas  $A_2$  and  $A_5$ .  $A_2$  and  $A_5$  (each  $1.9956 \text{ in}^2$ ) are the geometric areas of the seals.  $P_a$  is the ambient pressure surrounding the model.  $P_2$ ,  $P_5$  and  $P_3$  were measured on the PSI System.

The vertical thrust,  $H_y$ , was obtained from the sting balance pitching moments.

$$H_y = (FP - AP) / L_{bal}$$

where  $L_{bal}$  is the distance between the two balance bridges (5.962 inches). FP and AP are the moments at the forward and aft pitching moment bridges (referred to in the computer program as V1 and V3 for convenience).

The resultant thrust,  $H_r$ , was calculated as the vector sum of the axial thrust,  $H_x$ , and the vertical thrust,  $H_y$ . Resultant thrust vector angle,  $\alpha$ , was determined as:

$$\alpha = \tan^{-1}(H_y/H_x)$$

Referring to Figure 10, the axial location of the thrust vector is defined by  $L_x$ , the axial distance from the reference plane (fan cowl exit for all configurations) to the intersection of the resultant thrust vector with the model centerline.  $L_x$  is defined as positive downstream of the reference plane.  $L_x$  is found by a moment equation at the balance center.

$$L_x = (FP + AP)/(2H_y) - (L_{bal}/2 + L_{ref})$$

where  $L_{ref}$  is the distance from the downstream bridge (AP) to the model reference plane.  $L_y$  is the vertical distance to the intersection of the resultant thrust vector with the reference plane, measured positive upward from the model centerline, and is calculated from  $L_x$  and  $\alpha$ .

$$L_y = -L_x \tan \alpha$$

$$Mo = H_y L_x \text{ (moment about intersection of ref. plane and model centerline)}$$

Static pressure measurements were made for the baseline fan nozzle external surface (2078-001). These pressure measurements can be used to calculate the boat-tail drag of the fan nacelle external flow. The instrumentation locations are defined on the drawing.

#### 4.6 Thrust Coefficient

Thrust coefficient calculations are described below for the static and wind tunnel tests.

##### 4.6.1 Channel 14 Static Thrust Coefficient

Thrust coefficient is defined as the ratio of the measured nozzle thrust, to the ideal thrust of the actual fan flow (expanded isentropically from  $P_{t7}$  to  $P_a$ ) plus the

ideal thrust of the core flow (expanded isentropically from  $P_{t8}$  to  $P_a$ ). For the present tests, thrust coefficients were calculated for the axial and vertical thrust components, and for the resultant (in vertical plane) thrust vector:

$$C_{T_x} = \frac{H_x}{\sum m v_i}$$

$$C_{T_y} = \frac{H_y}{\sum m v_i}$$

$$C_{T_r} = \sqrt{C_{T_x}^2 + C_{T_y}^2}$$

where  $\sum m v_i = m_7 v_{i7} + m_8 v_{i8}$ .

Ideal thrust was calculated using a dimensionless ideal thrust function,  $(m_i v_i / P_t A^*)$ , which is a function of both  $\lambda$  and  $\gamma$ .

$$m_7 v_{i7} = (A^*/A)_7 C_{D7} A_7 P_{t7} (m_i v_i / P_t A^*)_7$$

$$m_8 v_{i8} = (A^*/A)_8 C_{D8} A_8 P_{t8} (m_i v_i / P_t A^*)_8$$

where

$$(m_i v_i / P_t A^*) = \gamma \left[ \frac{2}{\gamma + 1} \right]^{\frac{\gamma}{\gamma - 1}} \sqrt{\frac{\gamma + 1}{\gamma - 1}} \sqrt{1 - \lambda^{\frac{1-\gamma}{\gamma}}} \\ = 1.81162 \sqrt{1 - \lambda^{0.28571}} \quad \text{for } \gamma = 1.4$$

For the present test,  $\gamma_7$  and  $\gamma_8$  were taken to be 1.4. However,  $\gamma_8 \neq 1.4$  for hot tests, and therefore,  $(m_i v_i / P_t A^*)_8$  obtained from the above equation can be corrected to account for "real gas effects" by multiplying by the ratio

$$b = \frac{\left(m_i v_i / P_t A^*\right) \text{ for real gas}}{\left(m_i v_i / P_t A^*\right) \text{ for } \gamma = 1.4}$$

This ratio is calculated from tabulated values in Reference 4; this factor can be obtained by interpolating between the following equations:

$$b = .99707 + .00228 \log \lambda, \text{ at } T_{t8} = 440^\circ\text{F}$$

$$b = .99393 + .00377 \log \lambda, \text{ at } T_{t8} = 800^\circ\text{F}.$$

$b$  typically varies between 0.994 and 1.000 for hot tests.

#### 4.6.2 Channel 10 Wind Tunnel Thrust Coefficient

Thrust coefficient,  $C_{Tr}$ , is identical to that defined in Section 4.6.1. For in-flight tests, however, the measured net thrust includes form and friction drag on the external model surfaces and thus may also be referred to as "thrust-minus-drag". Similarly, the thrust coefficient for in-flight tests may be referred to as "thrust-minus-drag coefficient".

The wind tunnel sting was tested statically ( $M=0$ ) in Channel 6 and compared to Channel 14 static results. In Channels 6 and 10 the shorter distance between the model charging station and the nozzle exit could result in a slightly higher  $C_{Tr}$  in Channels 6 and 10 than Channel 14. Calculations of lower frictional losses were estimated to increase  $C_{Tr}$  in Channels 6 and 10 by roughly 0.1% above Channel 14 results ( $M=0$ ). This difference is within the data scatter band for Channel 10.

Static pressure data were measured on the baseline fan nozzle external nacelle (2078-001) such that one could perform a calculation of boat-tail drag. The reported  $C_{Tr}$  has not been adjusted or increased in any way to remove boat-tail or nacelle friction drag.

#### **4.7 Pressure and Temperature Data**

Pressure instrumentation for facility pressures and charging station pressures were described previously. All other pressures in the model were measured using a Pressure Systems Incorporated Model 780B pressure scanning unit. In the wind tunnel, all of the model pressures were measured with Pressure Systems Incorporated ESP remote modules mounted on the model under the sting tube covers. This reduced the amount of tubing crossing the force balance to the support sting and increased force measurement accuracy. Miscellaneous other pressures were measured with the standard PSI system and transducers outside the tunnel (wind tunnel plenum, wall pressures and other facility pressures). The model pressure data were reduced to absolute pressures (psia) and dimensionless ratios ( $P/P_{t_7}$ ,  $P/P_{t_8}$ ,  $P/P_a$ ).

Temperature measurements were obtained using chromel/alumel or iron/constantan thermocouples. Temperatures were expressed in °F and °R. Temperatures from hot model tests are often normalized using a dimensionless temperature difference ratio,

$$\eta = (T - T_{t_7}) / (T_{t_8} - T_{t_7}) .$$

#### **4.8 Force Balance Calibration**

The Channel 14 force balance calibration determined the output characteristics of the three force balance flexures and the two elastic seals between the metric model assembly and the non-metric facility structure. The elastic seals produce a small tare force, largely due to radial seal deflections necessary to support

the static pressure differential across the seal. The seal and balance assembly are calibrated under simulated operating conditions of loads and seal differential pressures.

The balance assembly was first calibrated with the internal seals unpressurized. Known loads were applied in the axial and vertical directions to obtain a matrix of balance equations, including force interactions, of the form:

$$V_1 = K_{11}B_1 + K_{12}B_2 + K_{13}B_3$$

$$H_o = K_{21}B_1 + K_{22}B_2 + K_{23}B_3$$

$$V_3 = K_{31}B_1 + K_{32}B_2 + K_{33}B_3$$

In the above equations,  $B_j$  is the balance output in millivolts for the axial and vertical bridges.  $K_{ij}$  terms are the calibration coefficients obtained during the calibration process, where the off-diagonal terms ( $i \neq j$ ) are the interaction correction terms, which numerically have the effect of canceling any interactive load along one axis of the system due to an applied load along an orthogonal axis. The reference coordinate system is defined along the facility centerline and all forces and moments are defined with respect to this coordinate system.

Calibration of the elastic seals was accomplished as follows. Blank-off plates were installed downstream of the seals, and the seals were pressurized (independently) to selected values of pressure differentials,  $\Delta P$ . This pressure loading produces a downstream force on the balance. Additional axial loads,  $W_x$ , were then applied to increase or decrease the net load to simulate test conditions of axial load and  $\Delta P$ . The balance force calculated from the balance output and unpressurized calibration is greater than the apparent applied load ( $W_x + \Delta P_2 A_2 + \Delta P_5 A_5$ ), due to the

seal tare force. The ratio of applied to calculated loads is then curve-fit as a function of  $\Delta P$  and  $H_2$  and included as a correction term in the balance force calculation. The Channel 14 vertical balance force calculations also include similar corrections to adjust for a seal  $\Delta P$  effect on the balance vertical bridge outputs.

In Channels 6 and 10 the procedures are the same except the seal calibrations are simplified by applying the average of the differential pressures ( $\Delta P_2$  and  $\Delta P_5$ ) to simulate a condition. Not simulating exact individual seal pressures is desirable because of the difficult access for installing internal blank off plates in the wind tunnel balance system. Also, the meter-diffusers are designed to create similar seal pressures. Another difference is that the vertical balance force correction determined from seal calibrations was not employed for the wind tunnel balance.

## 5.0 PRESENTATION OF RESULTS

### 5.1 ASME Checkout Nozzle Tests

Standard ASME long-radius flow nozzles were tested before this test program to demonstrate proper facility operation and accuracy in determining  $C_D$  and  $C_T$  of static test nozzles. The test results were compared with predicted (target) values. The target-value curves are based on semi-empirical equations consistent with those described for the ASME meter in Sections 4.3 and 4.5.

In Channel 14, a 7.1-inch diameter nozzle was tested to simulate the fan nozzle, and a 4.0-inch diameter nozzle was tested to simulate the core nozzle, as shown in Figure 7. The two nozzles were tested simultaneously, both with room temperature air flow ( $T_{t_8}/T_{t_7} = 1$ ). Major results are tabulated in Figure 11 and plotted in Figure 12. Detailed data are contained in the Data Appendix.

In Channel 6, a single 5.7-inch diameter nozzle was tested statically as shown in Figure 8. The air flow was at room temperature. Both fan and core facility meters were flowing and the fan to core mass flow split was roughly 3 to 1. The two flows were mixed and exhausted through a single 5.7 inch diameter ASME nozzle. Major results are tabulated in Figure 11 and plotted in Figure 13. Detailed data are contained in the Data Appendix.

The test results were statistically analyzed for bias (average difference between actual and predicted values) and scatter (standard deviation of the individual differences from their average). Standard procedure is to perform the analysis for the nozzle pressure ratio range from 1.6 and greater. This analysis is summarized in the following table.

### Static Checkout Results with ASME Nozzles

			Bias			Standard Deviation ( $\pm$ ):		
Static Test Series	$\lambda$ Range	N	$C_T$	$C_{D_7}$	$C_{D_8}$	$C_T$	$C_{D_7}$	$C_{D_8}$
Channel 14 4 " ASME Core 7.1 " ASME Fan								
Pretest, cold	1.6-2.4	10	.0005	-.0001	-.0002	.0007	.0003	.0003
Channel 6 5.7 " ASME Nozzle								
Pretest, cold	1.6-2.6	10	.0007	n/a	-.0010	.0003	n/a	.0013

## 5.2 Model Tests

The test matrix and model configuration definition are provided in Figure 16. Test conditions and major test results are tabulated in Figure 17. The tabulation includes: facility, configuration, noise reduction device, data point number, actual values of independent test variables ( $\lambda_7$  and  $\lambda_8$ ), pressure ratio split ( $\lambda_7/\lambda_8$ ), mass flow split ( $W_7/W_8$ ), and major test results ( $C_{D_7}$ ,  $C_{D_8}$ ,  $C_{T_r}$ , and  $\alpha$ ).

Channel 14 static thrust rig results are plotted in Figures 18, 19, and 20. The wind tunnel sting is checked out statically in Channel 6 prior to actual wind tunnel tests. Channels 6 and 14 static results are compared for the baseline configuration #1 (3BB) in Figures 21, 22, and 23. In this comparison, Channel 14 results are the most accurate. The comparison is very good demonstrating the correct operation of the wind tunnel sting balance system. Different charging station locations between the two sets of adapter hardware are expected to result in about 0.1% greater static  $C_{T_r}$  in

Channel 6 above Channel 14. This level of difference is within the scatter band of the Channel 6 data.

Results from the Channel 10 wind tunnel are shown in Figures 24, 25, and 26. Since all the data could not be fit on a single plot, the data are plotted in several groups. The first group presents all configurations that were tested at Mach=0.28 and 0.8. The second group presents all configurations with the baseline fan nozzle at the M=0.8 cruise point "A". The third group presents all configurations with the chevron or T48 fan nozzle at the M=0.8 cruise point "A". The next 3 groups present data at M=0.8 with an expanded cruise pressure ratio matrix for the baseline (3BB) and 2 other selected configurations (3T24C and 3AC).

Detailed data and calculations are contained in a separate Data Appendix and include: computer programs, instrumentation lists, inspections, thrust calculations, tabulations of pressures, charging station pressure plots, and boat-tail pressure distribution plots.



## 6.0 REFERENCES

1. Johnson, R.C., "Real-Gas Effects in Critical-Flow-Through Nozzles and Tabulated Thermodynamic Properties." NASA TN D-2565. 1965.
2. Massier, P.F., Back, L.H., Noel, M.B., and Saheli, F., "Viscous Effects on the Flow Coefficient for a Supersonic Nozzle." AIAA Journal, Volume 8, No. 3, March 1970, pp. 605-607.
3. Ames Research Staff, "Equations, Tables and Charts for Compressible Flow." NACA Report 1135. 1953.
4. Jordan, D.P., and Mintz, M.D., "Air Tables." McGraw-Hill Book Company, New York. 1965.
5. Wyatt, DeMarquis D., "Analysis of Errors Introduced by Several Methods of Weighting Non-Uniform Duct Flows." NACA TN 3400. March 1955.




FIGURE 1a. CHANNEL 14 STATIC THRUST STAND




FIGURE 1b. CHANNEL 14 ADAPTER ASSEMBLY




FIGURE 2a. CHANNEL 10 TRANSONIC WIND TUNNEL.




FIGURE 2b. CHANNEL 10 AERO-LINES




FIGURE 3. CHANNEL 10 MODEL INSTALLATION




FIGURE 4. CHANNEL 6 STATIC THRUST STAND




FIGURE 5. CHANNEL 14 MODEL ASSEMBLY




FIGURE 6a. CHANNELS 6 AND 10 MODEL ASSEMBLY






FIGURE 7. STATION NOTATION, ASME CHECKOUT NOZZLE TESTS, CHANNEL 14




FIGURE 8. STATION NOTATION, ASME CHECKOUT NOZZLE, CHANNEL 6




FIGURE 9. STATION NOTATION, CHANNEL 14 MODEL TESTS




FIGURE 10. STATION NOTATION, CHANNEL 6 AND 10 MODEL TESTS

JOB 2212, NASA AST

Data Point	$\lambda_7$	$\lambda_8$	T <sub>8</sub> /T <sub>07</sub>	C <sub>D7</sub>	C <sub>D8</sub>	C <sub>Tr</sub>	$\alpha$ (deg.)
Channel 14, Pretest, Cold							
7.1 inch Diameter ASME Fan Nozzle, 4.0 inch Diameter ASME Core Nozzle							
701.01	2.400	2.393	0.985	0.9922	0.9906	0.9971	0.00
701.02	2.405	2.401	0.980	0.9923	0.9905	0.9964	-0.04
701.03	2.406	2.396	0.994	0.9921	0.9903	0.9967	-0.13
702.01	2.203	2.199	0.985	0.9919	0.9903	0.9974	-0.04
702.02	2.204	2.196	0.986	0.9922	0.9903	0.9971	-0.01
702.03	2.205	2.198	0.989	0.9922	0.9906	0.9970	-0.13
703.01	1.998	1.997	0.988	0.9916	0.9905	0.9961	0.00
703.02	2.002	2.003	0.984	0.9917	0.9904	0.9957	-0.03
703.03	2.003	1.998	0.995	0.9915	0.9903	0.9956	-0.11
704.02	1.801	1.806	0.989	0.9912	0.9907	0.9952	0.04
704.03	1.801	1.795	0.990	0.9912	0.9905	0.9948	0.03
704.04	1.804	1.799	0.990	0.9915	0.9906	0.9949	-0.09
705.01	1.595	1.602	0.990	0.9906	0.9903	0.9937	0.06
705.03	1.601	1.600	1.000	0.9907	0.9902	0.9935	-0.06
705.04	1.601	1.598	0.992	0.9909	0.9905	0.9934	-0.05
706.01	1.391	1.399	0.989	0.9902	0.9895	0.9934	0.08
706.02	1.400	1.399	0.990	0.9901	0.9897	0.9924	0.14
706.03	1.401	1.397	0.994	0.9902	0.9898	0.9925	-0.02
707.01	1.294	1.300	0.991	0.9892	0.9894	0.9909	0.19
707.02	1.297	1.300	0.984	0.9899	0.9895	0.9911	0.15
707.03	1.300	1.297	1.004	0.9899	0.9894	0.9908	0.01
Channel 6, Pretest, Cold							
Single 5.7 Inch Diameter ASME Nozzle for Combined Fan and Core Flow							
610.01		1.598		0.9922	0.9950	-0.05	
610.02		1.600		0.9915	0.9946	-0.07	
611.01		1.799		0.9910	0.9951	-0.07	
611.02		1.799		0.9909	0.9953	-0.07	
612.01		1.999		0.9903	0.9962	-0.01	
612.02		2.000		0.9897	0.9958	-0.02	
613.01		2.202		0.9904	0.9966	-0.01	
613.02		2.207		0.9893	0.9960	-0.01	
614.01		2.403		0.9897	0.9962	0.04	
614.03		2.408		0.9894	0.9960	-0.01	
615.01		2.612		0.9892	0.9956	-0.02	
615.02		2.609		0.9901	0.9960	-0.01	

**FIGURE 11. TABULATION OF ASME NOZZLE TEST RESULTS**

ASME Checkout Nozzle Tests  
7.1 inch ASME Nozzle (6051-0196)




FIGURE 12a. CHANNEL 14 FAN DISCHARGE COEFFICIENTS, 7.1 INCH ASME NOZZLE,  $T_{t8}/T_{t7}=1.0$



ASME Checkout Nozzle Tests

7.1 inch ASME Nozzle (6051-0196)  
4.0 inch ASME Nozzle (6051-4232)




FIGURE 12c. CHANNEL 14 THRUST COEFFICIENTS, 7.1 AND 4.0 INCH ASME NOZZLES,  $T_{ts}/T_{t7}=1.0$




FIGURE 13a. CHANNEL 6 DISCHARGE COEFFICIENTS, 5.7 INCH ASME NOZZLE,  $T_{t8}/T_{t7}=1.0$

Channel 6  
ASME Checkout Nozzle Tests






FIGURE 13b. CHANNEL 6 THRUST COEFFICIENTS, 5.7 INCH ASME NOZZLE,  $T_e/T_{t7}=1.0$




Channel 14 ASME Checkout Nozzle Tests (7.1 " Dia. Fan, 4.0" Dia. Core)




Channel 6 ASME Checkout Nozzle (5.7" Diameter, Mixed Fan and Core Flow)

**FIGURE 14. ASME CHECKOUT NOZZLE PHOTOGRAPHS**




Configuration 1 (3BB) in Channel 14



Configuration 1 (3BB) in Channel 14

**FIGURE 15a. MODEL PHOTOGRAPHS**




Configuration 2 (3C12B) in Channel 14




Configuration 3 (3IB) in Channel 14

#### FIGURE 15b. MODEL PHOTOGRAPHS




Configuration 4 (3T24B) in Channel 14




Configuration 5 (3T48B) in Channel 14

### FIGURE 15c. MODEL PHOTOGRAPHS




Configuration 6 (3FmB) in Channel 14




Configuration 7 (3HmB) in Channel 14

**FIGURE 15d. MODEL PHOTOGRAPHS**




Wind Tunnel Sting Checkout in Channel 6 Facility, Configuration 1 (3BB)




Configuration 1 (3BB) in Channel 10 Wind Tunnel

**FIGURE 15e. MODEL PHOTOGRAPHS**




Wind Tunnel Sting Boundary Layer Probe




Configuration 2 (3C12B)

**FIGURE 15f. MODEL PHOTOGRAPHS**




Configuration 3 (3IB)




Configuration 4 (3T24B)

**FIGURE 15g. MODEL PHOTOGRAPHS**




Configuration 5 (3T48B)




Configuration 6 (3FmB)

**FIGURE 15h. MODEL PHOTOGRAPHS**




Configuration 7 (3HmB)




Configuration 8 (3BC)

**FIGURE 15i. MODEL PHOTOGRAPHS**




Configuration 9 (3IC)




Configuration 10 (3BT48)

**FIGURE 15j. MODEL PHOTOGRAPHS**




Configuration 11 (3T24T48)




Configuration 12 (3T24C with core clocked 90 degrees clockwise looking upstream)

**FIGURE 15k. MODEL PHOTOGRAPHS**




Configuration 13 (3T24C with fan clocked 22.5 degrees clockwise looking upstream)




Configuration 14 (3AB)

#### FIGURE 15I. MODEL PHOTOGRAPHS




Configuration 15 (3AC)




Configuration 16 (3T24C)

**FIGURE 15m. MODEL PHOTOGRAPHS**



Configuration 17 (3T48C)



Configuration 18 (3T48T48)

**FIGURE 15n. MODEL PHOTOGRAPHS**

TEST MATRIX AND MODEL CONFIGURATIONS						
		Data Points:				
Configuration	Device	Static	M = 0.28	Point A	Best 2 Configurations,	
		5-pt cycle	3-pt cycle	Cruise	4-Point Cruise	Matrix M=0.8
1	3BB(baseline)	5	3	1	4	2078-405
2	3C12B	5		1		2078-422
3	3IB	5		1		2078-427
4	3T24B	5		1		2087-406
5	3T48B	5		1		2087-405
6	3FmB	5		1		2087-407
7	3HmB	5		1		2087-404
8	3BC		3	1		2078-405
9	3IC		3	1		2078-427
10	3BT48		3	1		2078-405
11	3T24T48		3	1		2087-406
12	clock config. 16 core 90 deg.			1		2087-406
13	clock config. 16 fan 22.5 deg.			1		2087-406
14	3AB			1		2078-429
15	3AC			1	4	2078-429
16	3T24C			1	4	2087-406
17	3T48C			1		2087-405
18	3T48T48			1		2087-405
<b>Definition of Conditions:</b>						
	Pt7/Pa	Pt8/Pa	Pt7/Pt8	M	<b>Common Parts:</b>	
5 Point Static Matrix						
1	1.89	1.79	1.056	0	Forward core nozzle: 2078-404	
2	1.83	1.68	1.089	0	Forward plug: 2078-402	
3	1.73	1.51	1.146	0	Aft plug: 2078-411	
4	1.60	1.35	1.185	0	Core nozzle cover: 2078-605	
5	1.51	1.27	1.189	0		
3 Point Takeoff Matrix						
1	1.89	1.79	1.056	0.28		
2	1.83	1.68	1.089	0.28		
3	1.73	1.51	1.146	0.28		
Cruise Point A						
A	2.60	2.40	1.083	0.8		
4 Point Cruise Matrix						
1	2.80	2.40	1.167	0.8		
2	2.60	2.60	1.000	0.8		
3	2.60	2.20	1.182	0.8		
4	2.40	2.40	1.000	0.8		

FIGURE 16. TEST MATRIX AND MODEL CONFIGURATION DEFINITION.

Facility Config.	Device	Run #	Mach #	$\lambda_7$	$\lambda_t$	$\lambda_{7t}$	$W_7/W_8$	$C_{D7}$	$C_{Ds}$	$C_{Tr}$	$\alpha$ (deg.)
Ch. 14 1	3BB	*1.01	0	2.004	1.996	1.004	2.892	0.9923	0.9855	0.9908	0.05
		2.01	0	1.892	1.785	1.060	3.093	0.9919	0.9745	0.9903	0.06
		*2.02	0	1.892	1.787	1.058	3.087	0.9918	0.9750	0.9901	0.02
		*2.03	0	1.891	1.786	1.059	3.089	0.9919	0.9750	0.9900	0.04
		3.01	0	1.831	1.676	1.093	3.232	0.9913	0.9675	0.9901	0.08
		4.01	0	1.733	1.503	1.153	3.562	0.9902	0.9512	0.9893	0.07
		*4.02	0	1.732	1.504	1.151	3.556	0.9900	0.9517	0.9890	0.05
		5.01	0	1.599	1.346	1.189	3.951	0.9897	0.9333	0.9891	0.13
		6.01	0	1.507	1.265	1.192	4.206	0.9886	0.9208	0.9882	0.12
		*6.02	0	1.511	1.266	1.194	4.212	0.9887	0.9208	0.9877	0.10
		*7.01	0	1.399	1.196	1.169	4.380	0.9881	0.9110	0.9875	0.20
2	3C12B	*8.03	0	2.001	2.000	1.000	2.799	0.9924	1.0136	0.9902	0.03
		9.02	0	1.888	1.788	1.056	2.978	0.9918	1.0067	0.9896	0.04
		10.01	0	1.829	1.679	1.090	3.117	0.9911	0.9998	0.9898	0.13
		11.01	0	1.728	1.507	1.147	3.419	0.9899	0.9845	0.9889	0.18
		12.01	0	1.595	1.344	1.187	3.813	0.9895	0.9658	0.9888	0.22
		13.01	0	1.506	1.266	1.190	4.050	0.9887	0.9536	0.9878	0.28
3	3IB	*14.01	0	1.998	2.001	0.998	2.857	0.9921	0.9907	0.9888	0.06
		15.01	0	1.893	1.788	1.059	3.082	0.9917	0.9751	0.9884	0.08
		16.01	0	1.831	1.675	1.093	3.243	0.9911	0.9639	0.9883	0.10
		17.01	0	1.730	1.509	1.146	3.555	0.9901	0.9453	0.9876	0.12
		18.01	0	1.600	1.345	1.190	4.005	0.9897	0.9224	0.9873	0.15
		19.01	0	1.512	1.268	1.193	4.258	0.9886	0.9094	0.9866	0.19
4	3T24B	*20.02	0	2.004	2.005	1.000	2.966	0.9922	0.9545	0.9854	0.02
		21.01	0	1.888	1.791	1.055	3.161	0.9917	0.9470	0.9849	0.05
		22.01	0	1.830	1.679	1.090	3.306	0.9911	0.9417	0.9846	0.05
		23.01	0	1.728	1.507	1.147	3.601	0.9899	0.9328	0.9838	0.07
		24.01	0	1.597	1.343	1.189	3.998	0.9892	0.9227	0.9832	0.11
		25.01	0	1.508	1.266	1.191	4.212	0.9884	0.9171	0.9826	0.10

\* no charge

FIGURE 17. TEST CONDITIONS AND MAJOR TEST RESULTS, (Sheet 1 of 4)

Facility Config.	Device	Run #	Mach #	$\lambda_7$	$\lambda_t$	$\lambda_7/\lambda_t$	$W_7/W_6$	$C_{D7}$	$C_{D8}$	$C_{Tr}$	$\alpha$ (deg.)
Ch. 14	5	3T48B	*26.01	0	2.005	2.004	1.001	2.931	0.9919	0.9674	0.9875
		27.01	0	1.888	1.790	1.055	3.128	0.9916	0.9573	0.9871	0.08
		28.01	0	1.830	1.679	1.090	3.276	0.9912	0.9509	0.9867	0.08
		29.01	0	1.729	1.510	1.145	3.570	0.9903	0.9400	0.9864	0.09
		30.01	0	1.598	1.346	1.187	3.967	0.9895	0.9272	0.9859	0.15
		31.01	0	1.508	1.270	1.187	4.170	0.9888	0.9198	0.9850	0.17
6	3FmB	*32.01	0	2.003	2.002	1.000	2.924	0.9925	0.9663	0.9759	-0.02
		*32.02	0	2.002	2.004	0.999	2.929	0.9924	0.9668	0.9763	0.01
		33.01	0	1.891	1.791	1.056	3.109	0.9919	0.9637	0.9757	0.06
		34.01	0	1.828	1.678	1.089	3.243	0.9911	0.9595	0.9765	0.06
		35.01	0	1.729	1.511	1.144	3.530	0.9903	0.9495	0.9776	0.06
		36.01	0	1.598	1.350	1.184	3.898	0.9896	0.9395	0.9786	0.11
		37.01	0	1.509	1.271	1.187	4.111	0.9886	0.9329	0.9783	0.14
7	3HmB	*38.01	0	2.002	2.006	0.999	2.911	0.9919	0.9724	0.9825	-0.06
		*38.03	0	2.001	2.002	1.000	2.919	0.9921	0.9722	0.9823	-0.08
		39.01	0	1.889	1.793	1.054	3.099	0.9918	0.9653	0.9820	-0.02
		40.01	0	1.829	1.681	1.088	3.240	0.9908	0.9595	0.9823	-0.01
		41.01	0	1.730	1.512	1.144	3.539	0.9901	0.9473	0.9826	0.06
		42.01	0	1.596	1.353	1.179	3.902	0.9887	0.9336	0.9827	0.06
		*42.03	0	1.599	1.350	1.184	3.920	0.9895	0.9337	0.9831	0.05
		43.03	0	1.510	1.272	1.187	4.150	0.9886	0.9248	0.9825	0.04
1	3BB	*44.01	0	2.019	2.005	1.007	2.896	0.9927	0.9858	0.9904	0.01
	Post Test	*44.03	0	2.000	2.003	0.999	2.876	0.9924	0.9858	0.9904	0.05
	Repeat	*45.01	0	1.894	1.795	1.055	3.069	0.9921	0.9762	0.9897	0.05
		*46.01	0	1.828	1.682	1.087	3.207	0.9912	0.9684	0.9895	0.06
		*47.01	0	1.731	1.512	1.144	3.521	0.9899	0.9532	0.9891	0.07
		*48.01	0	1.595	1.354	1.178	3.889	0.9886	0.9359	0.9888	0.10
		*49.03	0	1.509	1.270	1.188	4.154	0.9886	0.9234	0.9882	0.13

\* no charge

FIGURE 17. TEST CONDITIONS AND MAJOR TEST RESULTS, (Sheet 2 of 4)

Facility Config.	Device	Run #	Mach #	$\lambda_7$	$\lambda_8$	$\lambda_7/\lambda_8$	$W_7/W_8$	$C_{D7}$	$C_{D8}$	$C_{Tr}$	$\alpha$ (deg.)	
Ch. 6 1	3BB sting checkout	++50.01	0	1.891	1.792	1.055	3.086	0.9927	0.9755	0.9903	-0.13	
		++50.02	0	1.887	1.782	1.059	3.104	0.9922	0.9740	0.9910	-0.12	
		++51.01	0	1.829	1.687	1.084	3.209	0.9898	0.9678	0.9896	-0.13	
		++51.02	0	1.837	1.696	1.083	3.204	0.9903	0.9682	0.9893	-0.13	
		++51.04	0	1.838	1.694	1.086	3.210	0.9910	0.9687	0.9891	-0.15	
		++52.02	0	1.731	1.503	1.152	3.575	0.9917	0.9522	0.9899	-0.16	
		++53.01	0	1.601	1.383	1.158	3.749	0.9898	0.9420	0.9888	-0.14	
Ch. 10	1	3BB	55.03	0.277	1.889	1.804	1.047	3.062	0.9908	0.9731	0.9792	-0.01
		56.02	0.295	1.846	1.681	1.098	3.265	0.9908	0.9639	0.9787	-0.04	
		57.01	0.273	1.730	1.509	1.147	3.556	0.9886	0.9474	0.9774	-0.05	
1	3BB	58.02	0.795	2.604	2.392	1.089	3.150	0.9936	0.9846	0.9374	0.59	
3	3IB	60.01	0.797	2.606	2.397	1.087	3.102	0.9938	0.9985	0.9342	0.62	
4	3T24B	61.01	0.803	2.630	2.434	1.081	3.229	0.9938	0.9538	0.9275	0.50	
5	3T48B	62.01	0.799	2.592	2.407	1.077	3.172	0.9934	0.9666	0.9297	0.68	
3BB	+63.01	0.8	1.1	Background noise acquired by NASA.								
3BB	+64.01	0.8	2.600	2.400	Baseline noise acquired by NASA.							
14	3AB	65.04	0.801	2.603	2.444	1.065	2.942	0.9929	1.0311	0.9340	0.63	
7	3HmB	66.01	0.803	2.620	2.412	1.086	3.183	0.9933	0.9719	0.9280	0.39	
6	3FmB	67.02	0.804	2.616	2.419	1.082	3.190	0.9931	0.9651	0.9210	0.47	
10	3BT48	68.01	0.792	2.595	2.392	1.085	3.057	0.9670	0.9839	0.9317	0.40	
10	3BT48	69.01	0.281	1.899	1.777	1.069	3.016	0.9550	0.9735	0.9760	-0.11	
		70.01	0.282	1.837	1.669	1.101	3.141	0.9518	0.9662	0.9750	-0.10	
		71.01	0.280	1.733	1.501	1.155	3.420	0.9463	0.9514	0.9718	-0.07	
11	3T24T48	72.01	0.795	2.608	2.391	1.091	3.166	0.9663	0.9542	0.9260	0.33	
11	3T24T48	73.02	0.282	1.896	1.789	1.060	3.072	0.9546	0.9462	0.9721	-0.13	
		74.01	0.274	1.827	1.675	1.091	3.194	0.9512	0.9409	0.9684	-0.16	
		75.01	0.280	1.732	1.494	1.159	3.511	0.9460	0.9318	0.9670	-0.08	
18	3T48T48	76.05	0.800	2.614	2.434	1.074	3.078	0.9661	0.9664	0.9264	0.44	

+ Runs 63.01 and 64.01 for NASA acoustic data and charged together as one run.


++ Sting Checkout runs considered part of setup charge.

FIGURE 17. TEST CONDITIONS AND MAJOR TEST RESULTS, (Sheet 3 of 4)

Facility Config.	Device	Run #	Mach #	$\lambda_7$	$\lambda_s$	$\lambda_7/\lambda_s$	$W_7/W_s$	$C_{D7}$	$C_{Ns}$	$C_{Tr}$	$\alpha$ (deg.)
Ch10	8	3BC	77.01	0.801	2.629	2.407	1.092	3.195	1.0039	0.9843	0.9356
8	8	3BC	78.01	0.285	1.900	1.804	1.053	3.104	0.9991	0.9736	0.9785
			79.01	0.279	1.835	1.681	1.091	3.271	0.9991	0.9645	0.9776
			80.01	0.284	1.732	1.506	1.150	3.608	0.9977	0.9462	0.9767
16	3T24C	81.01	0.793	2.594	2.400	1.081	3.266	1.0034	0.9523	0.9331	0.35
12	3T24C core@90deg.	82.01	0.791	2.588	2.391	1.083	3.274	1.0032	0.9516	0.9331	0.33
15	3AC	83.02	0.786	2.565	2.385	1.076	3.008	1.0030	1.0284	0.9325	0.22
17	3T48C	84.02	0.796	2.609	2.391	1.091	3.256	1.0025	0.9633	0.9323	0.43
9	3IC	85.01	0.790	2.586	2.387	1.083	3.138	1.0036	0.9941	0.9368	0.29
9	3IC	86.01	0.279	1.891	1.794	1.054	3.110	0.9989	0.9725	0.9780	0.00
		87.02	0.290	1.843	1.697	1.087	3.258	0.9982	0.9620	0.9761	0.01
		88.01	0.282	1.733	1.510	1.148	3.627	0.9971	0.9384	0.9767	-0.02
1	3BB expanded cruise matrix	89.02	0.798	2.811	2.390	1.176	3.400	0.9925	0.9845	0.9394	0.36
		90.01	0.797	2.608	2.639	0.988	2.863	0.9946	0.9847	0.9415	0.37
		91.02	0.798	2.607	2.192	1.189	3.444	0.9934	0.9838	0.9317	0.47
		92.01	0.793	2.397	2.379	1.008	2.918	0.9938	0.9844	0.9395	0.50
2	3C12B	95.02	0.804	2.615	2.394	1.092	3.055	0.9932	1.0186	0.9319	0.24
16	3T24C expanded cruise matrix	96.020	0.799	2.612	2.589	1.009	3.041	1.0026	0.9537	0.9338	0.40
		98.020	0.786	2.379	2.368	1.005	3.024	1.0023	0.9549	0.9280	0.43
		99.010	0.788	2.795	2.415	1.157	3.493	1.0041	0.9544	0.9364	0.40
		97.010	0.794	2.600	2.169	1.198	3.645	1.0027	0.9455	0.9320	0.38
15	3AC expanded cruise matrix	103.010	0.797	2.406	2.366	1.017	2.841	1.0026	1.0291	0.9251	0.58
		101.010	0.790	2.593	2.581	1.005	2.799	1.0035	1.0326	0.9351	0.51
		100.020	0.799	2.821	2.406	1.173	3.272	1.0041	1.0322	0.9347	0.32
		102.010	0.796	2.595	2.184	1.188	3.342	1.0031	1.0233	0.9234	0.50
13	3T24C	104.030	0.799	2.612	2.430	1.075	3.247	1.0032	0.9524	0.9290	0.38
		fan rotated 22.5 degrees									

FIGURE 17. TEST CONDITIONS AND MAJOR TEST RESULTS, (Sheet 4 of 4)

**FIGURE 18. CHANNEL 14 STATIC TEST, CORE NOZZLE DISCHARGE COEFFICIENTS**






FIGURE 19. CHANNEL 14 STATIC TEST, FAN NOZZLE DISCHARGE COEFFICIENTS




FIGURE 20. CHANNEL 14 STATIC TEST, THRUST COEFFICIENTS





FIGURE 21. CHANNEL 6 STING CHECKOUT, CORE NOZZLE DISCHARGE COEFFICIENTS



**FIGURE 22. CHANNEL 6 STING CHECKOUT, FAN NOZZLE DISCHARGE COEFFICIENTS**

Job 2212, NASA AST, Channel 6




FIGURE 23. CHANNEL 6 STING CHECKOUT, THRUST COEFFICIENTS




FIGURE 24a. CHANNEL 10 WIND TUNNEL, CORE NOZZLE DISCHARGE COEFFICIENTS

Job 2212, NASA AST, Channel 10, Cruise Point A with Baseline Fan




FIGURE 24b. CHANNEL 10 WIND TUNNEL, CORE NOZZLE DISCHARGE COEFFICIENTS,  
CRUISE POINT A WITH BASELINE FAN

Job 2212, NASA AST, Channel 10, Cruise Point A with Chevron or T48 Fan






FIGURE 24c. CHANNEL 10 WIND TUNNEL, CORE NOZZLE DISCHARGE COEFFICIENTS,  
CRUISE POINT A WITH CHEVRON OR T48 FAN

**Job 2212, NASA AST, Channel 10, Cruise Matrix**




**FIGURE 24d. CHANNEL 10 WIND TUNNEL, CORE NOZZLE DISCHARGE COEFFICIENTS,  
CRUISE MATRIX FOR CONFIGURATION 1 (3BB)**

**Job 2212, NASA AST, Channel 10, Cruise Matrix**




**FIGURE 24e. CHANNEL 10 WIND TUNNEL, CORE NOZZLE DISCHARGE COEFFICIENTS,  
CRUISE MATRIX FOR CONFIGURATION 16 (3T24C)**

**Job 2212, NASA AST, Channel 10, Cruise Matrix**



**FIGURE 24f. CHANNEL 10 WIND TUNNEL, CORE NOZZLE DISCHARGE COEFFICIENTS,  
CRUISE MATRIX FOR CONFIGURATION 15 (3AC)**



**FIGURE 25a. CHANNEL 10 WIND TUNNEL, FAN NOZZLE DISCHARGE COEFFICIENTS**

Job 2212, NASA AST, Channel 10, Cruise Point A with Baseline Fan






FIGURE 25b. CHANNEL 10 WIND TUNNEL, FAN NOZZLE DISCHARGE COEFFICIENTS,  
CRUISE POINT A WITH BASELINE FAN

**Job 2212, NASA AST, Channel 10, Cruise Point A with Chevron or T48 Fan**




**FIGURE 25c. CHANNEL 10 WIND TUNNEL, FAN NOZZLE DISCHARGE COEFFICIENTS,  
CRUISE POINT A WITH CHEVRON OR T48 FAN**




**FIGURE 25d. CHANNEL 10 WIND TUNNEL, FAN NOZZLE DISCHARGE COEFFICIENTS,  
CRUISE MATRIX FOR CONFIGURATION 1 (3BB)**

**Job 2212, NASA AST, Channel 10, Cruise Matrix**



**FIGURE 25e. CHANNEL 10 WIND TUNNEL, FAN NOZZLE DISCHARGE COEFFICIENTS,  
CONFIGURATION 16 (3T24C)**

**Job 2212, NASA AST, Channel 10, Cruise Matrix**



Job 2212, NASA AST, Channel 10




FIGURE 26a. CHANNEL 10 WIND TUNNEL, THRUST COEFFICIENTS

Job 2212, NASA AST, Channel 10, Cruise Point A with Baseline Fan




FIGURE 26b. CHANNEL 10 WIND TUNNEL, THRUST COEFFICIENTS,  
CRUISE POINT A WITH BASELINE FAN

Job 2212, NASA AST, Channel 10 , Cruise Point A with Chevron or T48 Fan





FIGURE 26c. CHANNEL 10 WIND TUNNEL, THRUST COEFFICIENTS,  
CRUISE POINT A WITH CHEVRON OR T48 FAN

**Job 2212, NASA AST, Channel 10, Cruise Matrix**



**FIGURE 26d. CHANNEL 10 WIND TUNNEL, THRUST COEFFICIENTS,  
CRUISE MATRIX FOR CONFIGURATION 1 (3BB)**

Job 2212, NASA AST, Channel 10, Cruise Matrix







FIGURE 26e. CHANNEL 10 WIND TUNNEL, THRUST COEFFICIENTS,  
CRUISE MATRIX FOR CONFIGURATION 16 (3T24C)


**Job 2212, NASA AST, Channel 10, Cruise Matrix**





ASE FluiDyne Laboratory Detail Drawings		
Part Number	Rev	Description
2212-001	B	Channel 11 Assembly
2212-002	B	Fan Adapter
2212-003	B	Fan Adapter - Channel 10
2212-004	A	Fan Charging Station
2212-005	-	Channel 10 Assembly
2212-006	-	Sting Assembly
2212-401	C	Core Adapter
2212-403	D	Core Flow Conditioning Duct
2212-601	B	Plug Adapter
2212-602	A	Plug Adapter
2212-603		Fan Spacer
2212-604	A	Fan Choke Plate
2212-605	A	Fan Screen
2212-606	A	Core Charging Station Adapter
2212-607	B	Core Charging Station
2212-608	A	Core OD Spacer
2212-609	A	Core Screen
2212-610	A	Core Choke Plate
2212-611	-	Split Cover
2212-612	B	Fan Pt Rake
2212-613	A	Fan Tt Rake
2212-801	A	Fan Spacer ID
2212-802	A	Core ID Spacer
2212-803	A	Plug Spacer
2212-804	A	Fan Duct Plug
2212-805	-	Fan Key
2212-806	-	Core Key
Other Drawings Provided:		
2078-001	D	Fan Nozzle - Configurations #2 Through #5
2078.003	B	Chevron Fan Nozzle, Configuration 7A
2078.402	B	Tail Cone Adapter Configuration 3
2078.404	C	Core Nozzle Forward Section, Configuration 2 and 3
2078.405	A	Core Nozzle, Configuration #3
2078.411	A	Tail Cone, Configuration #3
2078.422	A	Core Nozzle 9a, Configuration #3
2078.427	A	Core Nozzle 9c, Configuration #3
2078.429	B	Core Nozzle 9d, Configuration #3
2078.605	A	Core Nozzle Cover Ring, Configurations 2 and 3
2078.606	-	Split Ring -Core
2078.610	B	Core Nozzle/Strut Assembly
2087.001	A	48 Flipper Tab, Fan Nozzle Model #3
2087.404	A	Half Mixer
2087.405	A	Core Nozzle Config #3, 48 Alternating Tabs
2087.406	A	Core Nozzle Config #3, 24 Alternating Tabs
2087.407	A	20 Lobe Mixer
946.001	J	Core Shroud Adapter (see also 0946-416)
946.407	C	Instrumentation Plug Pt (Ch14 Fan)
946.410	C	Fan Bellmouth ( Ch14)
946.415	C	Instrumentation Plug - Tt
946.416	B	Total Temperature & Total Pressure Rake Locations for 946-001
946.603.1	B	Core Choke Plate
946.606	-	Spacer -Choke Plate
1195.001		Not available on CAD
1195.401		Not available on CAD
1865-005	D	Adapter/Mixer
6051.0160	B	Assembly Model Adapters
6051-0209	C	14.5 Diameter Sting Adapter
6051-4280	-	Perforated Split Cover
6051-4281	D	Split Cover- Boundary Layer Rake
6051-4282	A	Support Ring
6051-6428.1	A	Spacer
6051-8115	A	Variable Choke Plate
6051-8167	C	Plug adapter Channel 11 & 14
6051-8172	-	Split Cover Block
6070-441	G	Fan Spacers-Outer
6070-6158	B	Choke Plate - C1 and F1





























REVISIONS					
ITEM	REV.	DESCRIPTION	DATE APPROVED	RE-USE	
-	A	-	-	-	




SECTION A-A













**REV. S**

DATE	REV.	DESCRIPTION	DATE	AEROTEST R.L.W.
2/15/88	S	ADDED CERT #S	2/15/88	R.L.W.

0.188

0.094

1.900

0.35 x 45°  
CHAMFER (4)

DO NOT BREAK  
THRU EDGE

STAMP  
PART NO.

SECTION A-A

SECTION B-B

**ASE** AERO SYSTEMS ENGINEERING, INC.  
568 EAST FILMORIC AVENUE, ST. PAUL, MINNESOTA 55107 - USA

**Fundyne** AEROTEST GROUP  
NASS COMET INC., NO. 10, NASS, 3333 3RD AVENUE, ST. PAUL, MN 55107 - USA


**CORE CHOCK PLATE** THERMITE -

**NASA ADAPTER HARDWARE** THERMITE -

DASH NO	THICKNESS	DRILL & REAM	*A*	NO OF HOLES	OPEN CERT NO	OPEN AREA
1	1"	3/32	257	441	3022	6.09
2	3/8	3/32	257	441	3022	6.09
3	1/4	1/16	0.121	1.385	2023	0.30
4	-	-	-	-	-	-
5	-	-	-	-	-	-



REV SIONS		DATE	APPROVED	PAGE
ITEM	REV NUMBER	DESCRIPTION		
- A	1	MAP NUMBERS	23-JUL-93	1LM
- B	2	ADDED INSPECTED VALUES	CINMAY93	2LM




Pt PROBE LOCATIONS

12	2	INSTR	3265 DIA X LGHT REOD. ST STL LUBING
CIR	ITEM	FAN DUCT PLUG	-
1	1	2212-804-1	
		PLATE NO.	DESCRIPTION

DETAIL B  
SCALE: 5/1

① LEAK CHECKED, ID NUMBER 01, VISUAL  
CONFIRMATION OF LAB LOCATION

## NOTES.



REVISI		DESCRIPTION		DATE	APPROVED BY
LINE	REV	"	A	ADDOO CERT #	28 JANGE RM -
<p><b>ASE</b> AERO SYSTEMS ENGINEERING, INC. 358 EAST FILLMORE AVENUE, ST. PAUL, MINNESOTA 55107 • USA</p> <p><b>FLUIDYNE</b> AEROTEST GROUP 13825 SCHMIDT LAKE RD., PLACID, MINNESOTA 55446 • USA</p> <p>FACILITY SHI NO</p> <p>DOC TITLE FAN SPACER ID</p> <p>NASA ADAPTER HARDWARE</p>					
<p>UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES</p> <p>TOLERANCES ARE</p> <p>DECIMALS      0-.1-.40-.78 INCHES      .001      .005      .010      .016 .125 - .250      .001      .005      .010      .016 .375 - .500      .001      .006      .010      .016 .501 - .750      .001      .005      .010      .016 .751 - 1.000      .001      .006      .010      .016</p> <p>MATERIAL      416 ST STL      M16 CERT # (112)      PART NO.      - FINISH      -      PE-FILE      -</p> <p>SIZE      TSD NO      DMC NO      DMC NO W/ CALC      54933      2212801      2212801 STAS      -      SCALE      1/1      SHEET      -</p>					

REVISONS


ZONE	REV	DESCRIPTION	DATE	APPROVED	RELE
-	A	ADDED CERT #	05FEB98	RLM	-


STAMP NO. A

SECT I (U) A-A

A


DRILLED HOLE TOLERANCE		UNLESS OTHERWISE SPECIFIED UNLESS OTHERWISE SPECIFIED (TOLERANCES ARE		STOCK RES		DATA SHEET	
Ø .125 DIA	.004	DECIMALS	3/16 INCHES	DRAWS	3AS	23JAN98	<b>A-SE</b>
.000		MAX. .005	FRACTIONS	CRK	-	-	<b>ERGON SYSTEMS ENGINEERING, INC.</b>
.010		MIN. -.010	1/16	ENGR	RLM	27JAN98	356 EAST FILLMORE AVENUE SUITE 101 PARK MINNESOTA 55007 • USA
.030			MACHINED ANGLES				<b>FLUIDYNE</b>
			1/2, 1/4,				13025 SCOMBI LAKE RD. PLAINFIELD, MINNESOTA 55446 • USA
			1/8, 1/16,				<b>ERGOTEST GROUP</b>
			1/32, 1/64,				ONE TIME
			1/128, 1/256,				FACTORY SHIPPING
			1/512, 1/1024,				SHIPPING
			1/2048, 1/4096,				NO. 1
			1/8192, 1/16384,				NO. 2
			1/167772, 1/335544,				NO. 3
			1/671088, 1/1342176,				NO. 4
			1/3355440, 1/6710880,				NO. 5
			1/167108800, 1/33554400,				NO. 6
			1/835544000, 1/1671088000,				NO. 7
			1/4170440000, 1/8355440000,				NO. 8
			1/20852200000, 1/41704400000,				NO. 9
			1/104261000000, 1/208522000000,				NO. 10
			1/521305000000, 1/1042610000000,				NO. 11
			1/2606525000000, 1/5213050000000,				NO. 12
			1/13032625000000, 1/26065250000000,				NO. 13
			1/65163125000000, 1/130326250000000,				NO. 14
			1/325815625000000, 1/651631250000000,				NO. 15
			1/1629078125000000, 1/3258156250000000,				NO. 16
			1/8145390625000000, 1/16290781250000000,				NO. 17
			1/40727453125000000, 1/81453906250000000,				NO. 18
			1/203637265625000000, 1/407274531250000000,				NO. 19
			1/1018186328125000000, 1/2036372656250000000,				NO. 20
			1/5090931640625000000, 1/10181863281250000000,				NO. 21
			1/25454658203125000000, 1/50909316406250000000,				NO. 22
			1/127273291015625000000, 1/254546582031250000000,				NO. 23
			1/636366445078125000000, 1/1272732910156250000000,				NO. 24
			1/3181832225390625000000, 1/6363664450781250000000,				NO. 25
			1/15909161126953125000000, 1/31818322253906250000000,				NO. 26
			1/79545805634775625000000, 1/159091611269531250000000,				NO. 27
			1/397729028173878125000000, 1/795458056347756250000000,				NO. 28
			1/1988645140869390625000000, 1/3977290281738781250000000,				NO. 29
			1/9943225670434953125000000, 1/1988645140869390625000000,				NO. 30
			1/49716128502174765625000000, 1/9943225670434953125000000,				NO. 31
			1/248580642510873781250000000, 1/497161285021747656250000000,				NO. 32
			1/124290321255436875000000000, 1/248580642510873781250000000,				NO. 33
			1/621451606277218437500000000, 1/124290321255436875000000000,				NO. 34
			1/310725803138609218750000000, 1/621451606277218437500000000,				NO. 35
			1/1553629015693046093750000000, 1/3107258031386092187500000000,				NO. 36
			1/7768145008465223048750000000, 1/15536290156930460937500000000,				NO. 37
			1/38840725042326115243750000000, 1/77681450084652230487500000000,				NO. 38
			1/194203625211630576218750000000, 1/388407250423261152437500000000,				NO. 39
			1/971018126058152881093750000000, 1/1942036252116305762187500000000,				NO. 40
			1/4855090630290764405437500000000, 1/9710181260581528810937500000000,				NO. 41
			1/24275453151453822027187500000000, 1/48550906302907644054375000000000,				NO. 42
			1/121377265757269110136875000000000, 1/242754531514538220271875000000000,				NO. 43
			1/606886328786345550068750000000000, 1/121377265757269110136875000000000,				NO. 44
			1/3034431643891727750343750000000000, 1/606886328786345550068750000000000,				NO. 45
			1/1517215821945863875171875000000000, 1/3034431643891727750343750000000000,				NO. 46
			1/7586079110729419437587500000000000, 1/1517215821945863875171875000000000,				NO. 47
			1/3793039555364709718793750000000000, 1/7586079110729419437587500000000000,				NO. 48
			1/1896519777682354854393750000000000, 1/3793039555364709718793750000000000,				NO. 49
			1/9482598888411774272193750000000000, 1/1896519777682354854393750000000000,				NO. 50
			1/4741299444205882136093750000000000, 1/9482598888411774272193750000000000,				NO. 51
			1/2370649722102941068043750000000000, 1/4741299444205882136093750000000000,				NO. 52
			1/1185324861051470534021875000000000, 1/2370649722102941068043750000000000,				NO. 53
			1/5926624305257352670109375000000000, 1/1185324861051470534021875000000000,				NO. 54
			1/2963312152628676335051875000000000, 1/5926624305257352670109375000000000,				NO. 55
			1/1481656076314336667525875000000000, 1/2963312152628676335051875000000000,				NO. 56
			1/7408280381572183337512875000000000, 1/1481656076314336667525875000000000,				NO. 57
			1/3704140190786091668756875000000000, 1/7408280381572183337512875000000000,				NO. 58
			1/1852070095393045834378875000000000, 1/3704140190786091668756875000000000,				NO. 59
			1/9260350476965229171894375000000000, 1/1852070095393045834378875000000000,				NO. 60
			1/4630175238482614585947187500000000, 1/9260350476965229171894375000000000,				NO. 61
			1/2315087619241307292923750000000000, 1/4630175238482614585947187500000000,				NO. 62
			1/1157543809620653646461875000000000, 1/2315087619241307292923750000000000,				NO. 63
			1/5787719048103268322231875000000000, 1/1157543809620653646461875000000000,				NO. 64
			1/2893859524051634161115875000000000, 1/5787719048103268322231875000000000,				NO. 65
			1/1446929762025819580557875000000000, 1/2893859524051634161115875000000000,				NO. 66
			1/7234648810129097902789375000000000, 1/1446929762025819580557875000000000,				NO. 67
			1/3617324405064548951394875000000000, 1/7234648810129097902789375000000000,				NO. 68
			1/18086622025322744756974375000000000, 1/3617324405064548951394875000000000,				NO. 69
			1/90433111016613722383874375000000000, 1/18086622025322744756974375000000000,				NO. 70
			1/45216555508306861191937500000000000, 1/90433111016613722383874375000000000,				NO. 71
			1/22608277754153430595937500000000000, 1/45216555508306861191937500000000000,				NO. 72
			1/11304138877076715297937500000000000, 1/22608277754153430595937500000000000,				NO. 73
			1/56520694385383577489687500000000000, 1/11304138877076715297937500000000000,				NO. 74
			1/28260347192691788744843750000000000, 1/56520694385383577489687500000000000,				NO. 75
			1/14130173596345894372421875000000000, 1/28260347192691788744843750000000000,				NO. 76
			1/70650867981729472161218750000000000, 1/14130173596345894372421875000000000,				NO. 77
			1/35325433990864736080609375000000000, 1/70650867981729472161218750000000000,				NO. 78
			1/17662716995432368040304375000000000, 1/35325433990864736080609375000000000,				NO. 79
			1/88313584977211840200152187500000000, 1/17662716995432368040304375000000000,				NO. 80
			1/44156792488605920100076093750000000, 1/88313584977211840200152187500000000,				NO. 81
			1/22078396244302960050038093750000000, 1/44156792488605920100076093750000000,				NO. 82
			1/11039198122151480025001909375000000, 1/22078396244302960050038093750000000,				NO. 83
			1/55195990611057400125000909375000000, 1/11039198122151480025001909375000000,				NO. 84
			1/27597995305528700062500453750000000, 1/55195990611057400125000909375000000,				NO. 85
			1/13798997652764350031250225375000000, 1/27597995305528700062500453750000000,				NO. 86
			1/68994998263821800156250115375000000, 1/13798997652764350031250225375000000,				NO. 87
			1/34497499131910900078125057375000000, 1/68994998263821800156250115375000000,				NO. 88
			1/172472995659514500390625028375000000, 1/34497499131910900078125057375000000,				NO. 89
			1/862364978297572500195312501437500000, 1/17247299565951450039062502837500000,				NO. 90
			1/4311824891487862500097656250073750000, 1/86236497829757250019531250143750000,				NO. 91
			1/21559124457389125000488281250036375000, 1/431182489148786250009765625007375000,				NO. 92
			1/1077956222869456250002441406250018187500, 1/21559124457389125000488281250036375000,				NO. 93
			1/538978111433928125000122070312500090937500, 1/1077956222869456250002441406250018187500,				NO. 94
			1/2694890557169640625000061035156250045375000, 1/538978111433928125000122070312500090937500,				NO. 95
			1/13474452785848206250000305275312500226562500, 1/2694890557169640625000061035156250045375000,				NO. 96
			1/6737226392924100312500015256875000113187500, 1/13474452785848206250000305275312500226562500,				NO. 97
			1/3368613196462050156250000762812500056562500, 1/6737226392924100312500015256875000113187500,				NO. 98
			1/1684306598231025007812500038125000028125000, 1/3368613196462050156250000762812500056562500,				NO. 99
			1/84215329911551250039062500190312500014062500, 1/1684306598231025007812500038125000028125000,				NO. 100
			1/42107664955775625001953125000951562500014062500, 1/84215329911551250039062500190312500014062500,				NO. 101
			1/2105383247788781250009765625000475312500014062500, 1/42107664955775625001953125000951562500014062500,				NO. 102
			1/1052691623894390625000488281250002375312500014062500, 1/2105383247788781250009765625000475312500014062500,				NO. 103
			1/52634581194724750024414062500024414062500014062500, 1/1052691623894390625000488281250002375312500014062500,				NO. 104
			1/26317290				











REVISED			
ZONE	REV	DESCRIPTION	DATE APPROVED R.S.E.
-	A	-	-
0.185 <sup>+0.000</sup> 0.005 <sup>-0.005</sup>			
0.10			
FULL R			
2.360			
STAMP — PART NO			
<b>ASE</b> AERO SYSTEMS ENGINEERING, INC. 558 EAST FILLMORE AVENUE, ST. PAUL, MINNESOTA 55107 • USA 29 JAN 93 DRAWN: BIAS CHECKED: - DESIGNER: RLM DATE: 01/26/98 <b>Fluidyne</b> AEROTEST GROUP 13225 SCHMID LANE RD., PLAINFIELD, MINNESOTA 55446 • USA DRAWN: RLM CHECKED: - DESIGNER: RLM DATE: 01/26/98 <b>NASA ADAPTER HARDWARE</b> DRAWN: RLM CHECKED: - DESIGNER: RLM DATE: 01/26/98 REV: - SHEET: 4-1 SCALE: 1:1 Dwg No: 2212-806 FSU No: 54933 Wt. in lbs: - Proj. No: -08 NO: -9 2212 170021			


























**COLD MOD STA 15G 596**

STAMP P/N. STONE LETTERS FLUSH TO SURFACE. ALL PIECES

0 .03 x 45° CHAMFER (2)

6 607 +0 .001 DIA -C .001

6 358 +0 .000 DIA -C .000

1 540 +0 .000 DIA -C .001

40°

20°

40° (8)

SPLIT LINES AT THETA = 40°, 160° & 280°. 010 GAP PERMISSIBLE

**SECTION A-A**

TYP HOLE LOCATIONS AT THETA = 35°, 45°, 55°, 165°, 275°, & 285°.

3/8 DIA x 3 DEEP (8)

#5 DRILL (0.2055 DIA) THRU CSINK ICC TO O 375 DIA

(12) HOLES (6) PLACES (12) HOLES TOTAL

Φ C 307

**Aero Systems Engineering Inc.**  
154 EAST FAIRVIEW AVENUE  
ST. PAUL, MINNESOTA 55101 • USA

**Fluidyne Aerotest Group**  
3212 3RD AVENUE, APT #100, ST. PAUL, MN 55101 • USA

DATA SHEET NO.	UNITS	DESCRIPTION	DATA SHEET NO.	UNITS	DESCRIPTION
DATA SHEET	INCHES	INCHES	DATA SHEET	INCHES	INCHES
0 - 123 Dia	.064	2 INCHES	0 - 124 Dia	.064	2 INCHES
	.020			.020	
126 - 135 Dia	.303	WALL ANGLES	126 - 135 Dia	.303	WALL ANGLES
	.021	1/16"		.021	1/16"
131 - 300 Dia	.724	INNER 1/4 IN SEC STD OUT	131 - 300 Dia	.724	INNER 1/4 IN SEC STD OUT
	.031	MACHINED SURFACE RAD 1/8"		.031	MACHINED SURFACE RAD 1/8"
301 - 356 Dia	.608	WATERLINE	304 SST (CERTS)	.608	WATERLINE
	.021			.021	
751 - 1 000 DIA	1.00	PIPE	751 - 1 000 DIA	1.00	PIPE
	.021			.021	
140 -	-	WALL	140 -	-	WALL
140 -	-	CD	140 -	-	CD
NO. -	-	CD	NO. -	-	CD
NO. -	-	CD	NO. -	-	CD

**SECTION B-B**

APPROVED BY:

DATE:

REVISION:

1.000

54933

2078-606

**REVISIONS**

Line	Rev	Description	Date	APPROVED BY
-	A	PICTORIAL CHANGE	2 JUN 97	WMM
-	B	ADDED INSPECTION	14 FEB 97	WMM

Part	Ref	Part No.	Description	Matl
1	3	2078-428	CORE STRUTS	131 OR
6	2	-	DOVET PIN	DAY-DRIVE
1	1	2078-403	CORE NOZZLE ADAPTER	SH-1000
Ort			Core Pin Hole	MATERIALS


Detail No.	Dimensions	Material	Drawn By	Date Drawn
12-101	Outer Diam 1.000 Inner Diam .991 Wall .009 Welded Angles A1 Q20	Stainless Steel	WMM	2 JUN 97
12-1450	Dia .450 Wall .031 Lug .034 Welded Diameter No. 110 Part Attached Surface Roughness 1/8 Max. Error	Stainless Steel	RLM	2 JUN 97
12-1500	Dia .500 Wall .031 Lug .034 Welded Diameter No. 110 Part Attached Surface Roughness 1/8 Max. Error	Stainless Steel	RLM	2 JUN 97
12-1-1000	Dia .100 Wall .001 Lug .031 Welded	Stainless Steel	RLM	2 JUN 97
12-1-1400	Dia .1400 Wall .031 Lug .034 Welded	Stainless Steel	RLM	2 JUN 97
12-1-1500	Dia .1500 Wall .031 Lug .034 Welded	Stainless Steel	RLM	2 JUN 97


**ASE** AFRO SYSTEMS  
ENGINEERING INC  
200 EAST FAIRBINE AVENUE ST. PAUL MINNESOTA 55107 USA


**FLUID DYNNE** AEROTEST GROUP  
3335 SCHMIDT LANE NO. 1 P.O. BOX 33494 ST. PAUL MN 55131 USA


**CORE NOZZLE / STRUT ASSEMBLY GE HIGH BYPASS RATIO EXHAUST NOZZLE MODEL**


Part	Ref	Part No.	Matl
1	3	2078-428	DAY-DRIVE
6	2	-	SH-1000
1	1	2078-403	SH-1000
Ort			MATERIALS























RAKE LOCATIONS FOR 0946-001-1

PTI PRESSURE RANKS ( $X = 2$ 1/2)			
PTI	PAT NO.	THEIR X	Y [REF.]
1	60*	1.27*	2.15
2	60*	.93	2.49
3	60*	.63	2.76
4	63*	.76	3.00
5	60	.11	3.31
6	150*	2.17	2.15
7	150*	.93	2.49
8	150	.63	2.79
9	150	.36	3.06
10	150	.1	3.31
11	240	.127	2.15
12	240	.93	2.49
13	240	.63	2.79
14	240	.36	3.06
15	240	.1	3.31
16	330	.127	2.15
17	330	.93	2.49
18	330	.63	2.79
19	330	.36	3.06
20	330	.11	3.31

P1 PRESSURE RAKES FOR 0946-001-2

TAP NO	THETA	Y	R	TAP NO	THETA	Y	R
1	60°	2.12	1.30	11	240°	2.12	1.30
2	60°	1.44	1.98	12	210°	1.44	1.98
3	60°	2.94	2.48	13	210°	0.93	2.48
4	60°	0.53	2.09	14	240°	0.53	2.09
5	60°	0.16	3.26	15	240°	0.16	3.26
6	150°	2.12	1.30	16	310°	2.12	1.30
7	150°	1.44	1.98	17	330°	1.44	1.98
8	150°	0.94	2.48	18	330°	0.94	2.48
9	150°	0.53	2.09	19	330°	0.53	2.09
10	150°	0.16	3.26	20	330°	0.16	3.26


THERMOCOUPLE T1 BAKES EOB 0946-001-2

T/C NO	THETA	Y	R	T/C NO	THETA	Y	R
1	3°	2.02	1.40	6	270°	1.24	2.18
2	0°	1.24	2.16	8	270°	0.21	3.21
3	0°	0.68	2.74	9	180°	-0.24	4.0
4	0°	0.21	3.21	10	180°	1.24	2.18
5	30°	2.02	1.40	12	90°	0.68	2.74
7	90°	0.68	2.74	13	180°	0.21	3.21


THERMOCOUPLE TI RAKES FOR 0946-001-1


THERMOCOUPLE T1 RAKES FOR 0946-001-1


T/C NO	Y	R	T/C NO	Y	R
1	0.	2.02	1	4C	6
2	0*	1.24	2	1.8	9
3	0*	0.68	2	7.4	9
4	0*	0.21	3	2.1	10
5	36*	2.02	4	1.4C	11
6	36*	0.68	2	7.4	12
7	36*	0.68	1	4C	13




















REVISIONS		Description	DATE APPROVED	RELEASER
CASE	REV			
-	A	ADDEC CERT # FOR DASH -1	25 JAN 98	RJM

STAMP PART NO →  
STONE LETTERS  
FLUSH TO SURFACE

φ1.256 ± 0.002

φ1.256 ± 0.002

0.05 x 45° CHAMFER (2)

6.5

FLOW

DASH NO	"L"	QTY	DATE	CERT #
	5.2	1	JAN 98	55182
		1		
		1		
		1		
		1		
		1		
		1		
		1		

NOTES:  
1 DO NOT BREAK CORNERS UNLESS OTHERWISE SPECIFIED  
NOTES:

ITEM	DESCRIPTION	QTY	SIZE	DATE	RELEASER
1	SPACER	1	φ1.256 ± 0.002	25 JAN 98	RJM
2	NASA ADAPTER HARDWARE	1	φ1.256 ± 0.002	25 JAN 98	RJM

157

**REVISIONS**

ZONE	REV	DESCRIPTION	DATE	APPROVED BY
-	A	ADDED DASH TABLE	RLM	03-EB98 -

**DASH TABLE**

DASH NO	HOLE DIA	STAGGERED CENTERS	* OPEN	MATCH PART NO
-1	0 .070	1/4	7 1	6070-6158-1
-2	0 .098	1/4	13 .9	6070-6158-4
-3	0 .0935	3/16	22 .0	6070-6158-6

**4 715 (REF)**

**DRILL HOLES WITHIN THIS AREA SEE TABLE FOR PART TO MATCH**

**FULL R**

**REV A**

**AERO SYSTEMS ENGINEERING, INC.**  
328 EAST FILLMORE AVENUE SI PAUL, MINNESOTA 55137 • USA

**Fluidyne Aerotest Group**  
1425 SCHMIDT LAKE RD PLYMOUTH, MINNESOTA 55446 • USA

**FACILITY SHT NO**

**VARIABLE CHOKE PLATE**

**SIZE** FSOM NO DWG NO 6051-8 115 REV

L/O	SPR	PROJ	WT ACTUAL	WT CALC	SCALE	SHEET
-	-	-	-	-	1/1	-

**REVISIONS**

LINE	PREV	DESCRIPTION	DATE	APPROVED	REUSE
-	A	-	-	-	-

1.00 = 2.00

0.25

1.00

2.00

5.0

#6-32 UNC THRU  
S' STAIN 8 1/2 AS REQ'D  
TO BURN HEADS IN  
ASSEMBLY WITH COVERS

R7.19

STAMP PART NO

**ASE** AERO SYSTEMS ENGINEER INC., INC.  
356 EAST FILLMORE AVENUE, ST. PAUL, MINNESOTA 55107 • USA

**FLUIDYNE** FLUIDYNE TEST GROUP  
1525 SOMMERTIME DR., P.O. BOX 104, MINNEAPOLIS 55446 • USA

SPLIT COVER BLOCK

14.5 DIAMETER STING

LINE	ITEM	DESCRIPTION	QTY	PCN NO.	WT EACH	SCALE	SHFT NO.
1	1	1.000 DIA - .001	1	B154933	.000221	1/16	—
2	1	.500 DIA - .001	1	B154933	.000221	1/16	—
3	1	.250 DIA - .001	1	B154933	.000221	1/16	—
4	1	.125 DIA - .001	1	B154933	.000221	1/16	—
5	1	.062 DIA - .001	1	B154933	.000221	1/16	—
6	1	.031 DIA - .001	1	B154933	.000221	1/16	—
7	1	.015 DIA - .001	1	B154933	.000221	1/16	—





ID. #	NAME	FLUIDYNE THRUST PARAMETERS
1	CTR	Resultant thrust coefficient dimensionless
2	HR	Resultant thrust lbf
3	CTX	Axial thrust coefficient dimensionless
4	HX	Axial thrust lbf
5	CTY	Normal thrust coefficient dimensionless
6	HY	Normal thrust lbf
7	ALPHA	Angle of the resultant thrust
8	MACH	"Tunnel mach number, dimensionless"
9	Q	"Tunnel freestream dynamic pressure, psi"
10	LAM7	"Pressure ratio, Pt/Pa, dimensionless (Fan)"
11	LAM8	"Pressure ratio, Pt/Pa, dimensionless (Core)"
12	LAM9	"Pressure ratio, Pt/Pa, dimensionless (Final nozzle)"
13	W1	"Mass flow rate, lbm/sec (Core meter)"
14	W1COR	W1 corrected to std. pressure and temp.
15	W4	"Mass flow rate, lbm/sec (Fan meter)"
16	W4COR	W4 corrected to std. pressure and temp.
17	W7	"Mass flow rate, lbm/sec (Fan)"
18	W8	"Mass flow rate, lbm/sec (Core)"
19	MAVI7	Ideal thrust (Fan)
20	MAVI8	Ideal thrust (Core)
21	CD1	Meter discharge coefficient (Core)
22	CD4	Meter discharge coefficient (Fan)
23	CD6	Discharge coefficient (Venturi)
24	CD7	Discharge coefficient (Fan)
25	CD8	Discharge coefficient (Core)
26	CD9	Discharge coefficient (Final nozzle)
27	CT1	Meter thrust coefficient (Core)
28	CT4	Meter thrust coefficient (Fan)
29	PRATIO	Pt7/Pt8
30	TRATIO	Nozzle temperature ratio (TT8/TT7)
31	WRATIO	W7/W8
32	CWRATIO	SQR(Tt7/Tt8)*W7/W8
33	WCRATIO	W7/W8 corrected
34	CSTAR	Real gas A/A* correction factor
35	MSTAR	Gamma correction factor
36	ASTARA8	A* for core duct
37	F9	Exit stream thrust parameter dimensionless
38	F9X	Exit stream thrust parameter dimensionless X-plane
39	F9Y	Exit stream thrust parameter dimensionless Y-plane
40	K1	Real gas critical mass flow function (Meter)
41	K4	Real gas critical mass flow function (Meter)
42	K6	Real gas critical mass flow function (Venturi)
43	K7	Real gas critical mass flow function (Fan)
44	K8	Real gas critical mass flow function (Core)
45	RN1/1000	Reynolds number dimensionless
46	RN4/1000	Reynolds number dimensionless (Fan)
47	RN6/1000	Reynolds number dimensionless (Venturi)
48	RNWT/1000	Reynolds number dimensionless (Tunnel)
49	F1	Stream thrust (Core)
50	F4	Stream thrust (Fan)
51	G1	Real gas stream thrust correction factor (Core)
52	G4	Real gas stream thrust correction factor (Fan)

53	P2PT1	-	Pseal/Pmeter (Core)
54	P5PT4	-	Pseal/Pmeter (Fan)
55	PSPT6	-	Ps(venturi)/Pt(venturi)
56	A1	-	"Cross-section area, in^2 (Meter)"
57	A1COLD	-	"Cross-section area, in^2 (Meter @ room temp)
58	A2	-	"Cross-section area, in^2 (Seal)"
59	A3	-	"Cross-section area, in^2 (Sting cavity)"
60	A4	-	"Meter cross-section area, in^2 (Fan)"
61	A5	-	"Seal cross-section area, in^2 (Fan)"
62	A6	-	"Cross-section area, in^2 (Venturi)"
63	A7	-	"Cross-section area, in^2 (Fan)"
64	A8	-	"Cross-section area, in^2 (Core)"
65	A8COLD	-	"Cross-section area, in^2 (Core @ room temp.)"
66	A9	-	"Cross-section area, in^2 (Final nozzle)"
67	A9X	-	"Cross-section area, in^2 (Final nozzle X-plane)"
68	A9Y	-	"Cross-section area, in^2 (Final nozzle Y-plane)"
69	P2-PA	-	"Static pressure difference across core seal, (Psid)"
70	P3-PA	-	"Static pressure in sting cavity, psi"
71	P5-PA	-	"Static pressure difference across fan seal, (Psid)"
72	PBAR	-	Barometric pressure (Psia)
73	P	-	Measured tunnel static pressure (Psia)
74	PT0	-	Measured tunnel total pressure (Psia)
75	PA	-	Ambient pressure model sees (Psia)
76	PT1	-	Meter total pressure (Psia)
77	P2	-	Seal static pressure (Psia)
78	P3	-	Cavity static pressure (Psia)
79	PT4	-	Fan meter total pressure (Psia)
80	P5	-	Fan seal static pressure (Psia)
81	PT6	-	Venturi total pressure (Psia)
82	PSV	-	Venturi throat static (Psia)
83	PT7	-	Fan charging station total pressure (Psia)
84	PT8	-	Core charging station total pressure (Psia)
85	TT0	-	Tunnel total temperature (Deg. F.)
86	TT1	-	Meter total temperature (Deg. F.)
87	T1WALL	-	Meter wall temp. (Deg. F.)
88	T1BAR	-	Average temp. between meter wall and TT1 (Deg. F.)
89	TT4	-	Fan meter total temperature (Deg. F.)
90	TT6	-	Venturi total temperature (Deg. F.)
91	TT7	-	Fan charging station total temperature (Deg. F.)
92	TT8	-	Core charging station total temperature (Deg. F.)
93	TT8RATIO	-	Tt8/Twall
94	TTW	-	Hot asme exit wall temp.
95	DELTAT	-	Tt1-Tt8
96	H0	-	"Iterated axial balance force, lbf"
97	V1	-	"Vertical balance force (upstream strap), lbs"
98	V3	-	"Vertical balance force (downstream strap), lbs"
99	H2	-	"Axial balance force corrected for seal tare, lbs"
100	HOI	-	"Axial balance force @ 26.983, lbf"
101	K0P	-	Correction for vertical location of thrust
102	B9	-	Vertical location of axial thrust vector
103	LBAL	-	Length of balance from V1 to V3 (Inches)
104	LREF	-	Length: bal. center(ch11,14)orV3(ch12) to ref. point (Inch)
105	LX	-	Axial distance of pitching moment
106	LY	-	Vertical distance of pitching moment

107	L3	-	Vertical location of thrust vector
108	WTLO	-	Weight balance sees @ 26.983
109	WTUP	-	Weight balance sees @ 6.783
110	M0	-	Pitching moment
111	DA2	-	Seal delta area (Core)
112	DA5	-	Seal delta area (Fan)
113	DELCTI	-	Ct ideal with 100% mix on channel 11 hot runs
114	DELR	-	Vertical displacement of vector @ model ref. point

## **ADDENDUM**

# **PRESSURE DISTRIBUTION TEST FOR NASA AST SEPARATE FLOW NOZZLE NOISE REDUCTION CONFIGURATIONS**

## **INTRODUCTION**



PRESSURE DISTRIBUTION TEST FOR  
NASA AST  
SEPARATE FLOW NOZZLE  
NOISE REDUCTION CONFIGURATIONS

ADDENDUM TO REPORT 2212 DATA APPENDIX

29 Oct 98

Introduction:

This is an addendum to the Report 2212 Data Appendix to document pressure distribution tests for selected NASA AST separate flow nozzle noise reduction configurations. These tests were added to the contract after the final report was completed for the performance tests. This Appendix Addendum contains drawing revisions, tables of run conditions, model photographs, tables of pressure measurements, and plots of charging station profiles and model pressure distributions.

New Instrumentation

Instrumentation was added to the model for measuring static pressure distributions on the core cowl outer flow surface downstream of the fan throat. The purpose was to measure the pressure distributions and interactions between the base, chevron, and tab nozzle trailing edge devices. Three axial rows of 10 pressure taps each were added at circumferential angles of 300, 330, and 345 degrees. Model stations for these pressure taps are documented on the following pages and on the detail drawings.

This instrumentation was not present in the original model design. Therefore the tubing was routed out of the core hardware and onto the inner fan duct air flow surface in a low Mach number region. It was covered with metallic tape. The tubing crossed the fan duct flow at 315 degrees. A sheet metal shield was used to form a strut for the 30 instrumentation tubes in an inline fashion. A total temperature rake/plug was modified by removing the temperature rake and slotting the plug to route the instrumentation out of the model. The sheet metal strut and tubes were all soldered to this plug. Existing PSI system ESP modules mounted in the sting were reconfigured to measure the new instrumentation.

One new T24 core nozzle was fabricated with static pressure instrumentation (2212-404). Tests were first done with the core tabs in place. Then half the tabs were cut off to locally simulate a baseline core nozzle. The tabs were cut off by hand with a Dremel tool parting disk.

Test Matrix and Conditions

The table below presents the test matrix. The chevron fan nozzle was first tested at the normal position with part top at top dead center(3T24Co). This positioned the fan chevron sharp point tip in line with a core tab protruding into the fan flow at the top dead center position. Next the fan chevron nozzle was rotated 22.5 degrees to position the fan chevron valley directly in line with the core tab at top dead center(3T24C<sub>22.5</sub>). Target test conditions were cruise point "A" (Pt7/Pa=2.6, Pt7/Pt8=1.083, Mach # =0.8).

Test Sequence	Description 3 (core)(fan)	Data Point	Core Drawing #	Fan Drawing #	Pt7/Pa	Pt7/Pt8	Mach
1	3T24B	201.02	2212-404RevB	2078-001	2.598	1.094	.796
2		201.03	2212-404RevB	2078-001	2.601	1.064	.794
3	3T24C <sub>0</sub>	202.02	2212-404RevB	2078-003 (@ 0 deg.)	2.607	1.087	.800
4	3T24C <sub>22.5</sub>	203.01	2212-404RevB	2078-003 (@ 22.5 deg.)	2.581	1.082	.787
5	3B'C <sub>22.5</sub>	204.01	2212-404RevC	2078-003 (@ 22.5 deg.)	2.591	1.085	.789
6	3B'C <sub>0</sub>	205.01	2212-404RevC	2078-003 (@ 0 deg.)	2.626	1.091	.803
7	3B'B	206.01	2212-404RevC	2078-001	2.621	1.080	.801



Job 2212: NASA AST NOZZLE TESTS							
Instrumentation Locations							
<b>Channel 6&amp;10 Core Charging Station</b>							
Pressure Tap no.	theta	R	(R-Ri)/(Ro-Ri)	T/C Probe no.	theta	R	(R-Ri)/(Ro-Ri)
Pt8	0	1.253	0.1376	Tt8			
Pt8	2	1.629	0.3549	Tt8			
Pt8	3	1.934	0.5312	Tt8			
Pt8	4	2.196	0.6827	Tt8			
Pt8	5	2.43	0.8179	Tt8	(none provided, use J.T. temp drop)		
Pt8	6	2.644	0.9416	Tt8			
Pt8	7	1.253	0.1376	Tt8			
Pt8	8	1.629	0.3549	Tt8			
Pt8	9	1.934	0.5312	Tt8			
Pt8	10	2.196	0.6827	Tt8			
Pt8	11	2.43	0.8179	Tt8			
Pt8	12	2.644	0.9416	Tt8			
Pt8	13	1.253	0.1376				
Pt8	14	1.629	0.3549				
Pt8	15	1.934	0.5312				
Pt8	16	2.196	0.6827				
Pt8	17	2.43	0.8179	Core Charging Station Drawing			
Pt8	18	2.644	0.9416	Ri= inch	1.015 2212-607		
Pt8	19	270	0.1376	Ro= inch	2.745 2212-403		
Pt8	20	270	1.629				
Pt8	21	270	1.934				
Pt8	22	270	2.196				
Pt8	23	270	2.43				
Pt8	24	270	2.644				
Tap	theta (deg)						
Ps8_inner	25	15					
Ps8_inner	26	105					
Ps8_inner	27	195					
Ps8_inner	28	285					
Ps8_outer	29	15					
Ps8_outer	30	105					
Ps8_outer	31	195					
Ps8_outer	32	285					


Channel 6&10 Fan Charging Station						
Pressure Tap no.	theta	R	(R-Ri)/(Ro-Ri)	T/C Probe no.	theta	
Pt7	50	0	3.486	0.0594	Tt7	1
Pt7	51	0	3.824	0.1696	Tt7	2
Pt7	52	0	4.134	0.2707	Tt7	3
Pt7	53	0	4.423	0.3650	Tt7	4
Pt7	54	0	4.634	0.4534	Tt7	5
Pt7	55	0	4.850	0.5369	Tt7	6
Pt7	56	0	5.194	0.6164	Tt7	7
Pt7	57	0	5.427	0.6924	Tt7	8
Pt7	58	0	5.850	0.7652	Tt7	9
Pt7	59	0	5.864	0.8350	Tt7	10
Pt7	60	0	6.072	0.9028		
Pt7	61	0	6.272	0.9680		
Pt7	62	90	3.486	0.0594		
Pt7	63	90	3.824	0.1696		
Pt7	64	90	4.134	0.2707		
Pt7	65	90	4.423	0.3650		
Pt7	66	90	4.694	0.4534		
Pt7	67	90	4.95	0.5369	Fan Charging Station Duct drawings	
Pt7	68	90	5.194	0.6164	Ri= inch	3.304 2212-403
Pt7	69	90	5.427	0.6924	Ro= inch	6.370 2212-004
Pt7	70	90	5.65	0.7652		
Pt7	71	90	5.864	0.8350	Pt rake	2212-612
Pt7	72	90	6.072	0.9028	Tt rake	2212-613
Pt7	73	90	6.272	0.9680		
Pt7	74	180	3.486	0.0594		
Pt7	75	180	3.824	0.1696		
Pt7	76	180	4.134	0.2707		
Pt7	77	180	4.423	0.3650		
Pt7	78	180	4.694	0.4534		
Pt7	79	180	4.95	0.5369		
Pt7	80	180	5.194	0.6164		
Pt7	81	180	5.427	0.6924		
Pt7	82	180	5.65	0.7652		
Pt7	83	180	5.864	0.8350		
Pt7	84	180	6.072	0.9028		
Pt7	85	180	6.272	0.9680		
Pt7	86	270	3.486	0.0594		
Pt7	87	270	3.824	0.1696		
Pt7	88	270	4.134	0.2707		
Pt7	89	270	4.423	0.3650		
Pt7	90	270	4.694	0.4534		
Pt7	91	270	4.95	0.5369		
Pt7	92	270	5.194	0.6164		
Pt7	93	270	5.427	0.6924		
Pt7	94	270	5.65	0.7652		
Pt7	95	270	5.864	0.8350		
Pt7	96	270	6.072	0.9028		
Pt7	97	270	6.272	0.9680		
Tap		Theta (deg)				
Ps7_in	98	15	2212-403			
Ps7_in	99	85				
Ps7_in	100	205				
Ps7_in	101	275				
Ps7_out	102	15	2212-004			
Ps7_out	103	85				
Ps7_out	104	205				
Ps7_out	105	275				

<b>Channel 10 Sting Boundary Layer Rake</b>			
PtBL	Tap	Y(inch)	theta , deg
	121	0.025	0
	122	0.070	
	123	0.115	
	124	0.160	
	125	0.205	
	126	0.300	
	127	0.400	
	128	0.500	
	129	0.600	
	130	0.800	
	131	1.000	
<b>Channel 6&amp;10 Fan External Nacelle</b>			
	Tap	X1, inches	theta, deg
	111	0.1	3
	112	0.75	357
	113	1.5	354
	114	2.25	351
	115	3.25	348
	116	4.5	345
	117	6	342
	118	7.5	340
	119	9	335
	120 base tap	10.371	333
<b>Channel 10 Phase 2 Additional Pressures for Core Cowls Outer Surface Downstream of Fan Throat</b>			
	Tap	Model	Theta
		Station (inches)	(deg)
Phase 2	151	156.489	300
	152	156.989	
	153	157.489	
	154	157.739	
	155	157.989	
	156	158.239	
	157	158.489	
	158	158.989	
	159	159.489	
	160	159.989	
	161	156.489	330
	162	156.989	
	163	157.489	
	164	157.739	
	165	157.989	
	166	158.239	
	167	158.489	
	168	158.989	
	169	159.489	
	170	159.989	
	171	156.489	345
	172	156.989	
	173	157.489	
	174	157.739	
	175	157.989	
	176	158.239	
	177	158.489	
	178	158.989	
	179	159.489	
	180	159.989	

Channel 10 Wall Static Pressures		
	Tap	X2(inches) from beginning of wall slots
Floor	701	2.5
	702	9.5
	703	16.5
	704	23.5
	705	30.5
	706	37.5
	707	44.5
	708	51.5
	709	58.5
	710	62.5
	711	65 Baseline fan exit plane is 64.5 inches downstream of beginning of wall slots.
	712	69
	713	72.5
	714	79.5
	715	86.5
Ceiling	720	2.25
	721	9.25
	722	16.25
	723	23.25
	724	30.25
	725	37.25
	726	44.25
	727	51.25
	728	58.25
	729	65.25
	730	72.25
	731	79.25
	732	86.25
West Wall	760	2.25
	761	9.25
	762	16.25
	763	30.25
	764	37.25
	765	65.25
	766	72.25
East Wall	790	2.25
	791	30.25
	792	37.25
	793	65.25
	794	72.25
Plenum	5 on plenum side of East wall, spread from upstream to downstream over entire length	
	5 on plenum side of West wall, spread from upstream to downstream over entire length	
Pa	is plenum pressure corrected to centerline pressure based on original tunnel calibration	
Pto	measured barometer with screen loss correction	

4.552 DIA  
 4.593 DIA

FAX 612-559-6667  
 To: Kevin Mikkelsen  
 cc: Hansen Saitch



P-01


NASA/BLDG 77, RM 337

216 433 3918

27

10-19-1998 17:47





REVISED  
DRAWINGS





## **REVISED DRAWINGS**


This section contains drawing revisions for the Phase 2 Pressure Distribution Test. For all other drawings refer to the Report for Job 2212 Phase 1 Test. The revised drawings are:

- 2078-404 Core Nozzle Forward Section
- 2212-404 Instrumented Core Nozzle
- 2212-613 Fan Tt Rake (modified for Ps instrumentation lead through )











3T24B



Data Point = 201.02  
Nozzle Description = 3T24B  
Pt7/Pa = 2.598  
Pt7/Pt8 = 1.094  
Mach Number = 0.796



## FLUIDYNE AEROTEST LABORATORY

3T24B

Run Day/Time= 20-OCT-98 10:37:43  
 Job Number= 2212  
 Pt0= 14.341  
 Mach number= 0.796  
 Tunnel Rn= 3.599E+06

Run Number= 201.02  
 File Id= 06293103743  
 Bar. (Psia)= 14.379  
 Ptunnel (Psia)= 9.444  
 Tunnel Q= 4.1903

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
<b>TUNNEL FLOOR STATICS</b>						
701	9.448				0.0010	0.7957
702	9.451				0.0017	0.7954
703	9.578				0.0321	0.7818
704	9.428				-0.0037	0.7978
705	9.406				-0.0090	0.8002
706	9.404				-0.0095	0.8004
707	9.466				0.0053	0.7938
708	9.343				-0.0240	0.8069
709	9.271				-0.0412	0.8147
710	9.163				-0.0670	0.8262
711	9.283				-0.0383	0.8134
712	9.380				-0.0152	0.8030
713	9.424				-0.0047	0.7983
714	9.466				0.0053	0.7938
715	9.427				-0.0040	0.7980
<b>TUNNEL CEILING STATICS</b>						
720	9.458				0.0034	0.7946
721	9.430				-0.0033	0.7976
722	9.428				-0.0037	0.7978
723	9.452				0.0020	0.7953
724	9.375				-0.0164	0.8035
725	9.342				-0.0243	0.8071
726	9.329				-0.0274	0.8084
727	9.252				-0.0457	0.8167
728	9.248				-0.0467	0.8171
729	9.392				-0.0123	0.8017
730	9.451				0.0017	0.7954
731	9.489				0.0108	0.7913
732	9.494				0.0120	0.7908
<b>TUNNEL WEST WALL STATICS</b>						
760	9.519				0.0180	0.7881
761	9.405				-0.0092	0.8003
762	9.428				-0.0037	0.7978
763	9.288				-0.0372	0.8128
764	9.360				-0.0200	0.8051
765	9.454				0.0025	0.7951
766	9.595				0.0361	0.7800
<b>TUNNEL EAST WALL STATICS</b>						
790	9.549				0.0251	0.7849

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 10:37:43  
 Job Number= 2212  
 Pt0= 14.341  
 Mach number= 0.796  
 Tunnel Rn= 3.599E+06

Run Number= 201.02  
 File Id= 06293103743  
 Bar. (Psia)= 14.379  
 Ptunnel (Psia)= 9.444  
 Tunnel Q= 4.1903

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
TUNNEL EAST WALL STATICS						
791	9.430				-0.0033	0.7976
792	9.338				-0.0252	0.8075
793	9.258				-0.0443	0.8160
794	9.415				-0.0068	0.7992
PT8 - RAKE @60 DEGREES						
1	22.442	1.0010				
2	22.455	1.0016				
3	22.436	1.0007				
4	22.407	0.9994				
5	22.365	0.9975				
6	22.311	0.9951				
AVERAGE=	22.403	Distortion .0064				
PSS - STATICS						
25	21.165	0.9440				
29	21.017	0.9374				
AVERAGE=	21.091	Distortion .0070				
PT8 - RAKE @150 DEGREES						
7	22.431	1.0005				
8	22.390	0.9987				
9	22.398	0.9990				
10	22.420	1.0000				
11	22.452	1.0014				
12	22.407	0.9994				
AVERAGE=	22.416	Distortion .0028				
PSS - STATICS						
26	21.041	0.9385				
30	21.007	0.9370				
AVERAGE=	21.024	Distortion .0016				
PT8 - RAKE @240 DEGREES						
Fixed 13	22.444	1.0010				
14	22.391	0.9987				
15	22.438	1.0008				
16	22.431	1.0005				
17	22.483	1.0028				
18	22.428	1.0004				
AVERAGE=	22.436	Distortion .0041				
PSS - STATICS						
27	21.033	0.9381				
31	20.994	0.9364				
AVERAGE=	21.013	Distortion .0019				

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 10:37:43  
 Job Number= 2212  
 Pt0= 14.341  
 Mach number= 0.796  
 Tunnel Rn= 3.599E+06

Run Number= 201.02  
 File Id= 06293103743  
 Bar. (Psia)= 14.379  
 Ptunnel (Psia)= 9.444  
 Tunnel Q= 4.1903

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PT8 - RAKE @30 DEGREES						
19	22.458	1.0017				
20	22.442	1.0010				
Fixed 21	22.424	1.0002				
22	22.433	1.0006				
23	22.486	1.0029				
24	22.308	0.9950				
AVERAGE=	22.425	Distortion .0079				
PS8 - STATICS						
28	20.971	0.9354				
32	20.901	0.9322				
AVERAGE=	20.936	Distortion .0033				
PT7 - RAKE @0 DEGREES						
50	24.506		0.9988			
51	24.494		0.9983			
52	24.504		0.9987			
53	24.501		0.9986			
54	24.500		0.9985			
55	24.496		0.9984			
56	24.528		0.9997			
57	24.554		1.0007			
58	24.589		1.0022			
59	24.598		1.0025			
60	24.541		1.0002			
61	24.407		0.9948			
AVERAGE=	24.518	Distortion .0078				
PS7 - STATICS @30 DEGREES						
98	23.842		0.9717			
102	23.915		0.9747			
AVERAGE=	23.878	Distortion .0031				
PT7 - RAKE @90 DEGREES						
62	24.489		0.9981			
63	24.587		1.0021			
64	24.601		1.0027			
65	24.597		1.0025			
66	24.594		1.0024			
67	24.569		1.0014			
68	24.536		1.0000			
69	24.529		0.9997			
70	24.513		0.9991			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 10:37:43  
 Job Number= 2212  
 Pt0= 14.341  
 Mach number= 0.796  
 Tunnel Rn= 3.599E+06

Run Number= 201.02  
 File Id= 06293103743  
 Bar. (Psia)= 14.379  
 Ptunnel (Psia)= 9.444  
 Tunnel Q= 4.1903

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PT8 -	RAKE @330 DEGREES					
19	22.458	1.0017				
20	22.442	1.0010				
Fixed 21	22.424	1.0002				
22	22.433	1.0006				
23	22.496	1.0029				
24	22.308	0.9950				
AVERAGE=	22.425	Distortion .0079				
PS8 -	STATICS					
28	20.971	0.9354				
32	20.901	0.9322				
AVERAGE=	20.936	Distortion .0033				
PT7 -	RAKE @0 DEGREES					
50	24.506		0.9988			
51	24.494		0.9983			
52	24.504		0.9987			
53	24.501		0.9986			
54	24.500		0.9985			
55	24.496		0.9984			
56	24.528		0.9997			
57	24.554		1.0007			
58	24.589		1.0022			
59	24.598		1.0025			
60	24.541		1.0002			
61	24.407		0.9948			
AVERAGE=	24.518	Distortion .0078				
PS7 -	STATICS @30 DEGREES					
98	23.842		0.9717			
102	23.915		0.9747			
AVERAGE=	23.878	Distortion .0031				
PT7 -	RAKE @90 DEGREES					
62	24.489		0.9981			
63	24.587		1.0021			
64	24.601		1.0027			
65	24.597		1.0025			
66	24.594		1.0024			
67	24.569		1.0014			
68	24.536		1.0000			
69	24.529		0.9997			
70	24.513		0.9991			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 10:37:43  
 Job Number= 2212  
 Pt0= 14.341  
 Mach number= 0.796  
 Tunnel Rn= 3.599E+06

Run Number= 201.02  
 File Id= 06293103743  
 Bar. (Psia)= 14.379  
 Ptunnel (Psia)= 9.444  
 Tunnel Q= 4.1903

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PT7 - RAKE @90 DEGREES						
71	24.514		0.9991			
72	24.510		0.9990			
73	24.540		1.0002			
AVERAGE=	24.548	Distortion .0046				
PS7 - STATICS @120 DEGREES						
99	23.874		0.9730			
103	23.920		0.9749			
AVERAGE=	23.897	Distortion .0019				
PT7 - RAKE @180 DEGREES						
74	24.518		0.9993			
75	24.513		0.9991			
76	24.526		0.9996			
77	24.498		0.9985			
78	24.451		0.9966			
79	24.442		0.9962			
80	24.456		0.9968			
81	24.509		0.9989			
82	24.538		1.0001			
83	24.550		1.0006			
84	24.552		1.0007			
85	24.555		1.0008			
AVERAGE=	24.509	Distortion .0046				
PS7 - STATICS @210 DEGREES						
100	23.860		0.9725			
104	23.919		0.9749			
AVERAGE=	23.889	Distortion .0025				
PT7 - RAKE @270 DEGREES						
86	24.534		0.9999			
87	24.651		1.0047			
88	24.649		1.0046			
89	24.636		1.0041			
90	24.603		1.0027			
91	24.554		1.0007			
92	24.529		0.9997			
Fixed	93	24.531	0.9998			
	94	24.525	0.9996			
	95	24.514	0.9991			
	96	24.524	0.9995			
	97	24.511	0.9990			
AVERAGE=	24.563	Distortion .0057				

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 10:37:43  
 Job Number= 2212  
 Pt0= 14.341  
 Mach number= 0.796  
 Tunnel Rn= 3.599E+06

Run Number= 201.02  
 File Id= 06293103743  
 Bar. (Psia)= 14.379  
 Ptunnel (Psia)= 9.444  
 Tunnel Q= 4.1903

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PS7 - STATICS @300 DEGREES						
Fixed 101	23.859		0.9724			
105	23.915		0.9747			
AVERAGE=	23.887	Distortion	.0024			
EXTERNAL FAN NACELLE						
111	7.611			-0.4374		0.9960
112	5.843			-0.8593		1.2092
115	8.804			-0.1527		0.8648
120	9.863			0.1001		0.7513
B. L. PT RAKE						
122	12.202			1.2921		
125	13.000			1.3766		
PHASE 2 FAN INNER SURFACE PS @ 300 DEG						
151	12.563		0.5120			
152	9.628		0.3924			
153	8.901		0.3628			
154	8.919		0.3635			
155	9.066		0.3695			
156	9.400		0.3831			
157	10.701		0.4361			
158	12.238		0.4988			
159	11.347		0.4625			
160	9.645		0.3931			
PHASE 2 FAN INNER SURFACE PS @ 330 DEG						
161	12.585		0.5129			
162	9.598		0.3912			
163	8.876		0.3618			
164	8.936		0.3642			
165	8.980		0.3660			
166	9.143		0.3726			
167	10.482		0.4272			
168	12.320		0.5021			
169	11.447		0.4665			
170	9.674		0.3943			
PHASE 2 FAN INNER SURFACE PS @ 345 DEG						
171	12.672		0.5165			
172	9.683		0.3946			
173	8.951		0.3648			
174	8.889		0.3622			
175	9.083		0.3702			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 10:37:43 Run Number= 201.02  
 Job Number= 2212 File Id= 06293103743  
 Pt0= 14.341 Bar. (Psia)= 14.379  
 Mach number= 0.796 Ptunnel (Psia)= 9.444  
 Tunnel Rn= 3.599E+06 Tunnel Q= 4.1903

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PHASE 2 FAN INNER SURFACE PS @ 345 DEG						


176	9.200		0.3750			
177	10.441		0.4255			
178	12.300		0.5013			
179	11.493		0.4684			
180	9.723		0.3963			

STAB	PT	PS	MACH
STA8	22.403	21.080	0.2962
	22.416	21.021	0.3043
	22.436	21.011	0.3074
	22.425	20.931	0.3154
STA7	24.519	23.884	0.1939
	24.549	23.901	0.1959
	24.509	23.894	0.1910
	24.565	23.893	0.1994

STAB	AVERAGE		Pt Dist	Ps Dist
STA8	22.420	21.011	0.3059	0.0079
STA7	24.536	23.893	0.1951	0.0099

USR1:[CH06.SET]PRCONF11.SET;7  
 USR1:[CH06.SET]PZCONF12.SET;2  
 USR1:[CH06.SET]PPCONF12.SET;2


USR1:[CH06.SET]PBCONF11.SET;4  
 DATA REDUCED WITH A DELTA FILE



PTS PROFILE (PL21)  
Job 2212 Phase 2

RUN = 231.02

- (+) PTB @ 0 deg taps (1-6)
- (X) P5B @ 15 deg taps (25 & 29)
- (D) PTB @ 30 deg taps (7-12)
- (Y) P5B @ 100 deg taps (26 & 30)
- (\*) PTB @ 100 deg taps (13-18)
- (#) P5B @ 100 deg taps (27 & 31)
- (2) PTB @ 270 deg taps (19-24)
- (\\$) P5B @ 260 deg taps (28 & 32)



NACELLE EXTERNAL FS/FTB (PL23)

Job 2212 Phase 2

RUN = 231.02


(+) TAP 111

(X) TAP 112

(O) TAP 113

(Y) TAP 120

LINE - PHASE 1 RUN 61.01 31248 (111-120)




FAN STATIC PRESSURE DISTRIBUTION (PLZ4)

Job 2212 Phase 2


RUN = 231.02

- (+) PS/PIT 0300deg (TAPS 151-158)
- (X) PS/PIT 0330deg (TAPS 161-178)
- (D) PS/PIT 0345deg (TAPS 171-188)

3T24B



Data Point = 201.03  
Nozzle Description = 3T24B  
Pt7/Pa = 2.601  
Pt7/Pt8 = 1.064  
Mach Number = 0.794



## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 14:58:21  
 Job Number= 2212  
 Pt0= 14.309  
 Mach number= 0.794  
 Tunnel Rn= 3.845E+06

Run Number= 201.03  
 File Id= 06293145821  
 Bar. (Psia)= 14.347  
 Ptunnel (Psia)= 9.443  
 Tunnel Q= 4.1665

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
<b>TUNNEL FLOOR STATICS</b>						
701	9.459				0.0039	0.7922
702	9.446				0.0007	0.7936
703	9.568				0.0300	0.7805
704	9.423				-0.0048	0.7961
705	9.402				-0.0098	0.7983
706	9.399				-0.0105	0.7986
707	9.462				0.0046	0.7919
708	9.332				-0.0266	0.8058
709	9.264				-0.0429	0.8131
710	9.157				-0.0686	0.8246
711	9.279				-0.0393	0.8115
712	9.387				-0.0134	0.7999
713	9.428				-0.0036	0.7955
714	9.465				0.0053	0.7916
715	9.420				-0.0055	0.7964
<b>TUNNEL CEILING STATICS</b>						
720	9.447				0.0010	0.7935
721	9.425				-0.0043	0.7958
722	9.415				-0.0067	0.7969
723	9.444				0.0003	0.7938
724	9.370				-0.0175	0.8017
725	9.338				-0.0252	0.8052
726	9.329				-0.0273	0.8061
727	9.255				-0.0451	0.8141
728	9.251				-0.0461	0.8145
729	9.389				-0.0132	0.7998
730	9.447				0.0010	0.7935
731	9.490				0.0113	0.7889
732	9.496				0.0127	0.7882
<b>TUNNEL WEST WALL STATICS</b>						
760	9.512				0.0166	0.7865
761	9.402				-0.0098	0.7983
762	9.427				-0.0038	0.7956
763	9.289				-0.0369	0.8104
764	9.359				-0.0201	0.8029
765	9.446				0.0007	0.7936
766	9.589				0.0351	0.7782
<b>TUNNEL EAST WALL STATICS</b>						
790	9.540				0.0233	0.7835

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 14:59:21  
 Job Number= 2212  
 Pt0= 14.309  
 Mach number= 0.794  
 Tunnel Rn= 3.845E+06

Run Number= 201.03  
 File Id= 06293145821  
 Bar. (Psia)= 14.347  
 Ptunnel (Psia)= 9.443  
 Tunnel Q= 4.1665

TAP	P(PSIA)	P/Pt0	P/Pt7	P/Pa	Cp	Mach #
TUNNEL EAST WALL STATICS						
791	9.427				-0.0038	0.7956
792	9.335				-0.0259	0.8055
793	9.257				-0.0446	0.8139
794	9.411				-0.0077	0.7973
PT8 - RAKE @60 DEGREES						
1	23.108	1.0009				
2	23.118	1.0013				
3	23.108	1.0009				
4	23.073	0.9993				
5	23.028	0.9974				
6	22.977	0.9952				
AVERAGE=	23.069	Distortion .0061				
PS8 - STATICS						
25	21.789	0.9437				
29	21.640	0.9373				
AVERAGE=	21.715	Distortion .0069				
PT8 - RAKE @150 DEGREES						
7	23.108	1.0009				
8	23.065	0.9990				
9	23.064	0.9989				
10	23.088	1.0000				
11	23.122	1.0015				
12	23.074	0.9994				
AVERAGE=	23.087	Distortion .0025				
PS8 - STATICS						
26	21.665	0.9384				
30	21.628	0.9368				
AVERAGE=	21.647	Distortion .0017				
PT8 - RAKE @240 DEGREES						
Fixed 13	23.115	1.0012				
14	23.057	0.9986				
15	23.103	1.0006				
16	23.100	1.0005				
17	23.153	1.0028				
18	23.102	1.0006				
AVERAGE=	23.105	Distortion .0042				
PS8 - STATICS						
27	21.658	0.9381				
31	21.612	0.9361				
AVERAGE=	21.635	Distortion .0021				

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 14:58:21  
 Job Number= 2212  
 Pt0= 14.309  
 Mach number= 0.794  
 Tunnel Rn= 3.845E+06

Run Number= 201.03  
 File Id= 06293145821  
 Bar. (Psia)= 14.347  
 Ptunnel (Psia)= 9.443  
 Tunnel Q= 4.1665

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PT8 - RAKE @330 DEGREES						
19	23.129	1.0018				
20	23.109	1.0009				
Fixed 21	23.092	1.0001				
22	23.095	1.0003				
23	23.161	1.0032				
24	22.965	0.9947				
AVERAGE=	23.092	Distortion .0085				
PS8 - STATICS						
28	21.580	0.9347				
32	21.529	0.9325				
AVERAGE=	21.555	Distortion .0024				
PT7 - RAKE @0 DEGREES						
50	24.536		0.9989			
51	24.522		0.9983			
52	24.532		0.9987			
53	24.524		0.9984			
54	24.530		0.9986			
55	24.527		0.9985			
56	24.556		0.9997			
57	24.580		1.0007			
58	24.613		1.0020			
59	24.621		1.0023			
60	24.562		0.9999			
61	24.443		0.9951			
AVERAGE=	24.546	Distortion .0073				
PS7 - STATICS @30 DEGREES						
98	23.868		0.9717			
102	23.950		0.9750			
AVERAGE=	23.909	Distortion .0034				
PT7 - RAKE @90 DEGREES						
62	24.530		0.9986			
63	24.615		1.0021			
64	24.634		1.0029			
65	24.631		1.0028			
66	24.622		1.0024			
67	24.600		1.0015			
68	24.558		0.9998			
69	24.553		0.9996			
70	24.537		0.9989			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 14:58:21  
 Job Number= 2212  
 Pt0= 14.309  
 Mach number= 0.794  
 Tunnel Rn= 3.845E+06

Run Number= 201.03  
 File Id= 06293145821  
 Bar. (Psia)= 14.347  
 Ptunnel (Psia)= 9.443  
 Tunnel Q= 4.1665

TAP	P(PSIA)	P/Pt0	P/Pt7	P/Pa	Cp	Mach #
PT7 - RAKE @90 DEGREES						
71	24.535		0.9988			
72	24.538		0.9990			
73	24.570		1.0003			
AVERAGE=	24.577	Distortion	.0042			
PS7 - STATICS @120 DEGREES						
99	23.901		0.9730			
103	23.944		0.9748			
AVERAGE=	23.923	Distortion	.0018			
PT7 - RAKE @180 DEGREES						
74	24.551		0.9995			
75	24.539		0.9990			
76	24.556		0.9997			
77	24.523		0.9984			
78	24.481		0.9966			
79	24.469		0.9962			
80	24.494		0.9968			
81	24.527		0.9985			
82	24.567		1.0001			
83	24.585		1.0009			
84	24.585		1.0009			
85	24.583		1.0008			
AVERAGE=	24.538	Distortion	.0047			
PS7 - STATICS @210 DEGREES						
100	23.899		0.9730			
104	23.945		0.9748			
AVERAGE=	23.922	Distortion	.0019			
PT7 - RAKE @270 DEGREES						
86	24.559		0.9998			
87	24.676		1.0046			
88	24.687		1.0050			
89	24.665		1.0041			
90	24.629		1.0027			
91	24.585		1.0009			
92	24.556		0.9997			
Fixed 93	24.554		0.9996			
94	24.548		0.9994			
95	24.542		0.9991			
96	24.547		0.9993			
97	24.533		0.9988			
AVERAGE=	24.590	Distortion	.0063			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 14:58:21  
 Job Number= 2212  
 Pt0= 14.309  
 Mach number= 0.794  
 Tunnel Rn= 3.845E+06

Run Number= 201.03  
 File Id= 06293145821  
 Bar. (Psia)= 14.347  
 Ptunnel (Psia)= 9.443  
 Tunnel Q= 4.1665

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PS7 - STATICS @300 DEGREES						
Fixed 101	23. 890		0. 9726			
105	23. 939		0. 9746			
AVERAGE=	23. 915	Distortion .0021				
EXTERNAL FAN NACELLE						
111	7. 602			-0. 4418		0. 9951
112	5. 837			-0. 8654		1. 2082
115	8. 781			-0. 1589		0. 8651
120	9. 847			0. 0970		0. 7505
B. L. PT RAKE						
122	12. 176			1. 2894		
125	12. 915			1. 3677		
PHASE 2 FAN INNER SURFACE PS @ 300 DEG						
151	12. 615		0. 5136			
152	9. 641		0. 3925			
153	8. 862		0. 3608			
154	8. 876		0. 3614			
155	9. 029		0. 3676			
156	9. 350		0. 3807			
157	10. 585		0. 4309			
158	12. 275		0. 4998			
159	11. 417		0. 4648			
160	9. 670		0. 3937			
PHASE 2 FAN INNER SURFACE PS @ 330 DEG						
161	12. 640		0. 5146			
162	9. 603		0. 3910			
163	8. 833		0. 3596			
164	8. 900		0. 3623			
165	8. 955		0. 3646			
166	9. 094		0. 3702			
167	10. 395		0. 4232			
168	12. 339		0. 5023			
169	11. 515		0. 4688			
170	9. 704		0. 3951			
PHASE 2 FAN INNER SURFACE PS @ 345 DEG						
171	12. 694		0. 5168			
172	9. 712		0. 3954			
173	8. 905		0. 3625			
174	8. 849		0. 3603			
175	9. 042		0. 3681			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 20-OCT-98 14:58:21	Run Number= 201.03
Job Number= 2212	File Id= 06293145821
Pt0= 14.309	Bar. (Psia)= 14.347
Mach number= 0.794	Ptunnel (Psia)= 9.443
Tunnel Rn= 3.845E+06	Tunnel Q= 4.1665

TAP	P(PSIA)	P/Pt0	P/Pt7	P/Pa	Cp	Mach #
PHASE 2 FAN INNER SURFACE	PS @ 345 DEG					
176	9.170		0.3733			
177	10.342		0.4210			
178	12.316		0.5014			
179	11.550		0.4702			
180	9.747		0.3968			

STA8	PT	PS	MACH
	23.067	21.703	0.2965
	23.087	21.644	0.3051
	23.106	21.632	0.3083
	23.093	21.552	0.3156
STA7			
	24.547	23.916	0.1933
	24.573	23.927	0.1962
	24.538	23.926	0.1904
	24.592	23.920	0.1993

	AVERAGE			Pt Dist	Ps Dist
STA8	23.089	21.633	0.3064	0.0085	0.0120
STA7	24.564	23.922	0.1948	0.0099	0.0034


USR1: [CH06, SET]PRCONF11, SET; 7  
 USR1: [CH06, SET]PZCONF12, SET; 2  
 USR1: [CH06, SET]PFCONF12, SET; 2

USR1: [CH06, SET]PBCONF11, SET; 4  
 DATA REDUCED WITH A DELTA FILE

FT7 PROFILE (PR22)

۱۷۰

NAME	SEX	AGE	DATE OF BIRTH	DEATH DATE	CAUSE OF DEATH	REGISTRATION NO.	REGISTRATION DATE	REGISTRATION PLACE	REGISTRATION OFFICE
SHAH, SABU	M	50	1901-09-15	1951-09-05	CHF	P57	1951-09-05	1951-09-05	(2)
SHAH, SABU	M	50	1901-09-15	1951-09-05	CHF	P57	1951-09-05	1951-09-05	(4)
SHAH, SABU	M	50	1901-09-15	1951-09-05	CHF	P57	1951-09-05	1951-09-05	(74-283)
SHAH, SABU	M	50	1901-09-15	1951-09-05	CHF	P57	1951-09-05	1951-09-05	(85-57)




PTB PROFILE <PL21>

Job 2212 Phase 2

RUN = Z31.03

- (+) PTB @ 0 deg 10PS (1-6)
- (X) PSB @ 15 deg 10PS (23 & 29)
- (0) PTB @ 30 deg 10PS (7-12)
- (Y) PSB @ 180 deg 10PS (25 & 30)
- (\*) PTB @ 180 deg 10PS (13-18)
- (#) PSB @ 195 deg 10PS (27 & 31)
- (2) PTB @ 270 deg 10PS (19-24)
- (3) PSB @ 265 deg 10PS (28 & 32)



NACELLE EXTERNAL FS/F16 (PL23)

Job 2212 Phase 2

RUN = 231.03


(+) TAF 111

(X) TAF 112

(D) TAF 113

(Y) TAF 120

LINE - PHASE 1 RUN 61.01 3T24B (111-120)




## FAN STATIC PRESSURE DISTRIBUTION (FL24)

Job 2212 Phase 2

RUN = 2211.03

- (+) Ps/Pt7 6300deg (11deg 151-160)
- (X) Ps/Pt7 6336deg (11deg 161-170)
- (O) Ps/Pt7 6345deg (11deg 171-180)

3T24B



3T24C<sub>0</sub><sup>0</sup>



Data Point = 202.02  
Nozzle Description = 3T24C<sub>0</sub>  
Pt7/Pa = 2.607  
Pt7/Pt8 = 1.087  
Mach Number = 0.800



## FLUIDYNE AEROTEST LABORATORY

3T24 C<sub>0</sub>

Run Day/Time= 21-OCT-98 10:59:25  
 Job Number= 2212  
 Pt0= 14.371  
 Mach number= 0.800  
 Tunnel Rn= 3.726E+06

Run Number= 202.02  
 File Id= 06294105925  
 Bar. (Psia)= 14.410  
 Ptunnel (Psia)= 9.427  
 Tunnel Q= 4.2242

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
<b>TUNNEL FLOOR STATICS</b>						
701	9.433				0.0016	0.7994
702	9.416				-0.0024	0.8012
703	9.540				0.0269	0.7879
704	9.397				-0.0069	0.8032
705	9.371				-0.0131	0.8060
706	9.368				-0.0138	0.8063
707	9.429				0.0007	0.7998
708	9.295				-0.0311	0.8141
709	9.240				-0.0441	0.8200
710	9.135				-0.0689	0.8312
711	9.259				-0.0396	0.8180
712	9.379				-0.0112	0.8051
713	9.403				-0.0055	0.8026
714	9.442				0.0037	0.7984
715	9.404				-0.0052	0.8025
<b>TUNNEL CEILING STATICS</b>						
720	9.428				0.0004	0.7999
721	9.400				-0.0062	0.8029
722	9.395				-0.0074	0.8034
723	9.408				-0.0043	0.8020
724	9.341				-0.0202	0.8092
725	9.309				-0.0277	0.8126
726	9.299				-0.0301	0.8137
727	9.226				-0.0474	0.8215
728	9.224				-0.0479	0.8217
729	9.365				-0.0145	0.8066
730	9.424				-0.0005	0.8003
731	9.468				0.0099	0.7956
732	9.474				0.0113	0.7950
<b>TUNNEL WEST WALL STATICS</b>						
760	9.495				0.0163	0.7928
761	9.380				-0.0109	0.8050
762	9.404				-0.0052	0.8025
763	9.264				-0.0384	0.8174
764	9.335				-0.0216	0.8098
765	9.428				0.0004	0.7999
766	9.574				0.0350	0.7843
<b>TUNNEL EAST WALL STATICS</b>						
790	9.517				0.0215	0.7904

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 21-OCT-98 10:59:25  
 Job Number= 2212  
 Pt0= 14.371  
 Mach number= 0.800  
 Tunnel Rn= 3.726E+06

Run Number= 202.02  
 File Id= 06294105925  
 Bar. (Psia)= 14.410  
 Ptunnel (Psia)= 9.427  
 Tunnel Q= 4.2242

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
TUNNEL EAST WALL STATICS						
791	9.403				-0.0055	0.8026
792	9.308				-0.0280	0.8127
793	9.238				-0.0445	0.8202
794	9.393				-0.0079	0.8036
PT8 - RAKE @60 DEGREES						
1	22.624	1.0009				
2	22.637	1.0014				
3	22.617	1.0006				
4	22.582	0.9990				
5	22.547	0.9975				
6	22.492	0.9950				
AVERAGE=	22.584	Distortion .0064				
PS8 - STATICS						
25	21.330	0.9436				
29	21.196	0.9377				
AVERAGE=	21.263	Distortion .0063				
PT8 - RAKE @150 DEGREES						
7	22.618	1.0006				
8	22.577	0.9988				
9	22.581	0.9990				
10	22.608	1.0002				
11	22.640	1.0016				
12	22.592	0.9994				
AVERAGE=	22.603	Distortion .0028				
PS8 - STATICS						
26	21.215	0.9385				
30	21.179	0.9369				
AVERAGE=	21.197	Distortion .0017				
PT8 - RAKE @240 DEGREES						
Fixed 13	22.630	1.0011				
14	22.576	0.9987				
15	22.624	1.0009				
16	22.617	1.0006				
17	22.667	1.0028				
18	22.612	1.0003				
AVERAGE=	22.621	Distortion .0040				
PS8 - STATICS						
27	21.202	0.9380				
31	21.160	0.9361				
AVERAGE=	21.181	Distortion .0020				

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 21-OCT-98 10:59:25  
 Job Number= 2212  
 Pt0= 14.371  
 Mach number= 0.800  
 Tunnel Rn= 3.726E+06

Run Number= 202.02  
 File Id= 06294105925  
 Bar. (Psia)= 14.410  
 Ptunnel (Psia)= 9.427  
 Tunnel Q= 4.2242

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PT8 - RAKE @30 DEGREES						
19	22.647	1.0019				
20	22.620	1.0007				
Fixed 21	22.608	1.0001				
22	22.613	1.0004				
23	22.679	1.0033				
24	22.497	0.9952				
AVERAGE=	22.611	Distortion .0080				
PSB - STATICS						
28	21.160	0.9361				
32	21.080	0.9326				
AVERAGE=	21.120	Distortion .0038				
PT7 - RAKE @0 DEGREES						
50	24.540		0.9987			
51	24.527		0.9982			
Fixed 52	24.532		0.9984			
53	24.537		0.9986			
54	24.532		0.9984			
55	24.537		0.9986			
56	24.563		0.9996			
57	24.592		1.0008			
58	24.629		1.0023			
59	24.636		1.0026			
60	24.582		1.0004			
61	24.455		0.9952			
AVERAGE=	24.556	Distortion .0074				
PS7 - STATICS @30 DEGREES						
98	23.870		0.9714			
102	23.942		0.9743			
AVERAGE=	23.906	Distortion .0030				
PT7 - RAKE @90 DEGREES						
62	24.538		0.9986			
63	24.627		1.0022			
64	24.644		1.0029			
65	24.639		1.0027			
66	24.636		1.0026			
67	24.613		1.0017			
68	24.573		1.0000			
69	24.570		0.9999			
70	24.548		0.9990			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 21-OCT-98 10:59:25  
Job Number= 2212  
Pt0= 14.371  
Mach number= 0.800  
Tunnel Rn= 3.726E+06

Run Number= 202.02  
File Id= 06294105925  
Bar. (Psia)= 14.410  
Ptunnel (Psia)= 9.427  
Tunnel Q= 4.2242

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PT7 - RAKE @90 DEGREES						
71	24.543		0.9988			
72	24.547		0.9990			
73	24.577		1.0002			
AVERAGE=	24.588	Distortion	.0043			
PS7 - STATICS @120 DEGREES						
99	23.909		0.9730			
103	23.938		0.9742			
AVERAGE=	23.924	Distortion	.0012			
PT7 - RAKE @180 DEGREES						
74	24.558		0.9994			
75	24.547		0.9990			
76	24.558		0.9994			
77	24.525		0.9981			
78	24.484		0.9964			
79	24.476		0.9961			
80	24.490		0.9966			
91	24.543		0.9988			
82	24.574		1.0001			
83	24.595		1.0009			
84	24.590		1.0007			
85	24.587		1.0006			
AVERAGE=	24.544	Distortion	.0048			
PS7 - STATICS @210 DEGREES						
100	23.910		0.9730			
104	23.939		0.9742			
AVERAGE=	23.925	Distortion	.0012			
PT7 - RAKE @270 DEGREES						
86	24.600		1.0011			
87	24.687		1.0047			
88	24.692		1.0049			
89	24.667		1.0038			
90	24.636		1.0026			
91	24.582		1.0004			
92	24.557		0.9994			
Fixed 93	24.569		0.9998			
94	24.555		0.9993			
95	24.544		0.9988			
96	24.555		0.9993			
97	24.545		0.9989			
AVERAGE=	24.599	Distortion	.0060			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 21-OCT-98 10:59:25  
 Job Number= 2212  
 Pt0= 14.371  
 Mach number= 0.800  
 Tunnel Rn= 3.726E+06

Run Number= 202.02  
 File Id= 06294105925  
 Bar. (Psia)= 14.410  
 Ptunnel (Psia)= 9.427  
 Tunnel Q= 4.2242

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PS7 - STATICS @300 DEGREES						
Fixed 101	23.897		0.9725			
105	23.935		0.9741			
AVERAGE=	23.916	Distortion .0016				
EXTERNAL FAN NACELLE						
111						
112						
115						
120						
B. L. PT RAKE						
122	12.311			1.3060		
125	13.191			1.3994		
PHASE 2 FAN INNER SURFACE PS @ 300 DEG						
151	10.977		0.4467			
152	9.440		0.3842			
153	8.697		0.3539			
154	10.067		0.4097			
155	9.742		0.3965			
156	10.529		0.4285			
157	11.590		0.4717			
158	11.222		0.4567			
159	10.280		0.4184			
160	9.182		0.3737			
PHASE 2 FAN INNER SURFACE PS @ 330 DEG						
161	10.946		0.4455			
162	9.446		0.3844			
163	8.591		0.3496			
164	10.185		0.4145			
165	9.719		0.3955			
166	10.396		0.4231			
167	11.343		0.4616			
168	11.296		0.4597			
169	10.352		0.4213			
170	9.180		0.3736			
PHASE 2 FAN INNER SURFACE PS @ 345 DEG						
171	11.008		0.4480			
172	9.503		0.3867			
173	8.938		0.3638			
174	10.140		0.4127			
175	9.685		0.3942			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 21-OCT-98 10:59:25  
 Job Number= 2212  
 Pt0= 14.371  
 Mach number= 0.800  
 Tunnel Rn= 3.726E+06

Run Number= 202.02  
 File Id= 06294105925  
 Bar. (Psia)= 14.410  
 Ptunnel (Psia)= 9.427  
 Tunnel Q= 4.2242

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PHASE 2 FAN INNER SURFACE	PS @ 345 DEG					
176	10.436		0.4247			
177	11.263		0.4584			
178	11.179		0.4550			
179	10.495		0.4271			
180	9.246		0.3763			

STAB	PT	PS	MACH
22.584	21.253	0.2958	
22.603	21.195	0.3046	
22.622	21.179	0.3083	
22.611	21.115	0.3143	
STA7			
24.556	23.912	0.1953	
24.589	23.927	0.1979	
24.545	23.928	0.1911	
24.601	23.921	0.2005	

	AVERAGE			Pt Dist	Ps Dist
STAB	22.605	21.185	0.3057	0.0083	0.0118
STA7	24.573	23.922	0.1962	0.0096	0.0030


USR1: [CH06, SET]PRCONF11, SET; 7


USR1: [CH06, SET]PBCONF12, SET; 1

USR1: [CH06, SET]PZCONF12, SET; 2

DATA REDUCED WITH A DELTA FILE

USR1: [CH06, SET]PFCONF15, SET; 2






FHN STATIC PRESSURE DISTRIBUTION (FL24)

Job 2212 Phase 2

RUN = 202.02

- (+) PS/Pt7 (300deg) (16PS 151-160)
- (X) PS/Pt7 (330deg) (16PS 161-170)
- (O) PS/Pt7 (345deg) (16PS 171-180)

3T24 C<sub>o</sub>





3T24C<sub>22.5</sub><sup>0</sup>



Data Point = 203.01  
Nozzle Description = 3T24C<sub>22.5</sub>  
Pt7/Pa = 2.581  
Pt7/Pt8 = 1.082  
Mach Number = 0.787



## FLUIDYNE AEROTEST LABORATORY

3T24C<sub>12.5</sub>

Run Day/Time= 21-OCT-98 14:07:33  
 Job Number= 2212  
 Pt0= 14.379  
 Mach number= 0.787  
 Tunnel Rn= 3.995E+06

Run Number= 203.01  
 File Id= 06294140733  
 Bar. (Psia)= 14.417  
 Ptunnel (Psia)= 9.558  
 Tunnel Q= 4.1401

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
<b>TUNNEL FLOOR STATICS</b>						
701	9.573				0.0035	0.7851
702	9.560				0.0004	0.7865
703	9.678				0.0289	0.7739
704	9.535				-0.0056	0.7891
705	9.515				-0.0105	0.7913
706	9.510				-0.0117	0.7918
707	9.569				0.0026	0.7855
708	9.458				-0.0242	0.7973
709	9.391				-0.0404	0.8045
710	9.298				-0.0629	0.8144
711	9.410				-0.0358	0.8025
712	9.512				-0.0112	0.7916
713	9.540				-0.0044	0.7886
714	9.590				0.0076	0.7833
715	9.547				-0.0027	0.7878
<b>TUNNEL CEILING STATICS</b>						
720	9.567				0.0021	0.7857
721	9.545				-0.0032	0.7881
722	9.541				-0.0042	0.7885
723	9.560				0.0004	0.7865
724	9.490				-0.0165	0.7939
725	9.454				-0.0252	0.7978
726	9.448				-0.0267	0.7984
727	9.396				-0.0416	0.8050
728	9.378				-0.0436	0.8059
729	9.510				-0.0117	0.7918
730	9.569				0.0026	0.7855
731	9.612				0.0130	0.7809
732	9.614				0.0134	0.7807
<b>TUNNEL WEST WALL STATICS</b>						
760	9.631				0.0175	0.7789
761	9.530				-0.0069	0.7897
762	9.543				-0.0037	0.7883
763	9.404				-0.0373	0.8031
764	9.468				-0.0218	0.7963
765	9.558				-0.0001	0.7867
766	9.711				0.0369	0.7703
<b>TUNNEL EAST WALL STATICS</b>						
790	9.649				0.0219	0.7770

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 21-OCT-98 14:07:33  
 Job Number= 2212  
 Pt0= 14.379  
 Mach number= 0.787  
 Tunnel Rn= 3.995E+06

Run Number= 203.01  
 File Id= 06294140733  
 Bar. (Psia)= 14.417  
 Ptunnel (Psia)= 9.558  
 Tunnel Q= 4.1401

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
TUNNEL EAST WALL STATICS						
791	9.536				-0.0054	0.7890
792	9.453				-0.0255	0.7979
793	9.389				-0.0409	0.8047
794	9.534				-0.0059	0.7892
PT8 - RAKE @60 DEGREES						
1	22.833	1.0010				
2	22.847	1.0016				
3	22.823	1.0004				
4	22.792	0.9992				
5	22.752	0.9975				
6	22.698	0.9951				
AVERAGE=	22.791	Distortion .0065				
PS8 - STATICS						
25	21.534	0.9441				
29	21.387	0.9376				
AVERAGE=	21.460	Distortion .0068				
PT8 - RAKE @150 DEGREES						
7	22.825	1.0007				
8	22.780	0.9987				
9	22.785	0.9989				
10	22.808	0.9999				
11	22.843	1.0015				
12	22.794	0.9993				
AVERAGE=	22.806	Distortion .0028				
PS8 - STATICS						
26	21.409	0.9386				
30	21.372	0.9370				
AVERAGE=	21.390	Distortion .0017				
PT8 - RAKE @240 DEGREES						
Fixed 13	22.836	1.0012				
14	22.778	0.9986				
15	22.826	1.0007				
16	22.823	1.0006				
17	22.872	1.0027				
18	22.820	1.0005				
AVERAGE=	22.826	Distortion .0041				
PS8 - STATICS						
27	21.401	0.9382				
31	21.353	0.9361				
AVERAGE=	21.377	Distortion .0022				

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 21-OCT-98 14:07:33  
 Job Number= 2212  
 Pt0= 14.379  
 Mach number= 0.787  
 Tunnel Rn= 3.995E+06

Run Number= 203.01  
 File Id= 06294140733  
 Bar. (Psia)= 14.417  
 Ptunnel (Psia)= 9.558  
 Tunnel Q= 4.1401

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PT8 - RAKE @330 DEGREES						
19	22.851	1.0018				
20	22.826	1.0007				
Fixed 21	22.811	1.0001				
22	22.816	1.0003				
23	22.881	1.0031				
24	22.705	0.9954				
AVERAGE=	22.815	Distortion .0077				
PS8 - STATICS						
28	21.353	0.9361				
32	21.267	0.9324				
AVERAGE=	21.310	Distortion .0040				
PT7 - RAKE @0 DEGREES						
50	24.636		0.9987			
51	24.632		0.9985			
Fixed 52	24.634		0.9986			
53	24.637		0.9987			
54	24.635		0.9986			
55	24.635		0.9986			
56	24.665		0.9999			
57	24.687		1.0007			
58	24.723		1.0022			
59	24.730		1.0025			
60	24.671		1.0001			
61	24.547		0.9951			
AVERAGE=	24.652	Distortion .0074				
PS7 - STATICS @30 DEGREES						
98	23.982		0.9714			
102	24.039		0.9745			
AVERAGE=	24.000	Distortion .0032				
PT7 - RAKE @90 DEGREES						
62	24.623		0.9982			
63	24.719		1.0020			
64	24.738		1.0028			
65	24.735		1.0027			
66	24.732		1.0026			
67	24.708		1.0016			
68	24.666		0.9999			
69	24.664		0.9998			
70	24.641		0.9989			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 21-OCT-98 14:07:33  
 Job Number= 2212  
 Pt0= 14.379  
 Mach number= 0.787  
 Tunnel Rn= 3.995E+06

Run Number= 203.01  
 File Id= 06294140733  
 Bar. (Psia)= 14.417  
 Ptunnel (Psia)= 9.558  
 Tunnel Q= 4.1401

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PT7 - RAKE @90 DEGREES						
71	24.638		0.9988			
72	24.638		0.9988			
73	24.669		1.0000			
AVERAGE=	24.681	Distortion .0047				
PS7 - STATICS @120 DEGREES						
99	24.017		0.9736			
103	24.031		0.9742			
AVERAGE=	24.024	Distortion .0006				
PT7 - RAKE @180 DEGREES						
74	24.650		0.9992			
75	24.648		0.9992			
76	24.662		0.9997			
77	24.626		0.9983			
78	24.586		0.9967			
79	24.571		0.9960			
80	24.586		0.9967			
81	24.631		0.9985			
82	24.671		1.0001			
83	24.691		1.0009			
84	24.688		1.0008			
85	24.687		1.0007			
AVERAGE=	24.641	Distortion .0049				
PS7 - STATICS @210 DEGREES						
100	24.011		0.9733			
104	24.033		0.9742			
AVERAGE=	24.022	Distortion .0009				
PT7 - RAKE @270 DEGREES						
86	24.673		1.0004			
87	24.781		1.0046			
88	24.795		1.0051			
89	24.768		1.0040			
90	24.734		1.0027			
91	24.688		1.0008			
92	24.658		0.9996			
Fixed 93	24.660		0.9997			
94	24.651		0.9993			
95	24.644		0.9990			
96	24.649		0.9992			
97	24.643		0.9990			
AVERAGE=	24.696	Distortion .0062				

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 21-OCT-98 14:07:33  
 Job Number= 2212  
 Pt0= 14.379  
 Mach number= 0.787  
 Tunnel Rn= 3.995E+06

Run Number= 203.01  
 File Id= 06294140733  
 Bar. (Psia)= 14.417  
 Ptunnel (Psia)= 9.558  
 Tunnel Q= 4.1401

TAP	P(PSIA)	P/Pt0	P/Pt7	P/Pa	Cp	Mach #
PS7 - STATICS @300 DEGREES						
Fixed 101	23.996		0.9728			
105	24.034		0.9743			
AVERAGE=	24.015	Distortion .0016				
EXTERNAL FAN NACELLE						
111						
112						
115						
120						
B. L. PT RAKE						
122	12.269			1.2836		
125	13.007			1.3608		
PHASE 2 FAN INNER SURFACE PS @ 300 DEG						
151	11.034		0.4473			
152	9.510		0.3855			
153	8.737		0.3542			
154	9.837		0.3988			
155	10.276		0.4166			
156	10.628		0.4308			
157	11.914		0.4830			
158	11.105		0.4502			
159	10.202		0.4136			
160	9.383		0.3904			
PHASE 2 FAN INNER SURFACE PS @ 330 DEG						
161	10.992		0.4456			
162	9.503		0.3852			
163	8.747		0.3546			
164	9.917		0.4020			
165	10.201		0.4135			
166	10.416		0.4222			
167	11.673		0.4732			
168	11.189		0.4536			
169	10.244		0.4153			
170	9.264		0.3755			
PHASE 2 FAN INNER SURFACE PS @ 345 DEG						
171	11.069		0.4487			
172	9.585		0.3885			
173	8.826		0.3578			
174	9.826		0.3983			
175	10.269		0.4163			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 21-OCT-98 14:07:33  
 Job Number= 2212  
 Pt0= 14.379  
 Mach number= 0.787  
 Tunnel Rn= 3.995E+06

Run Number= 203.01  
 File Id= 06294140733  
 Bar. (Psia)= 14.417  
 Ptunnel (Psia)= 9.558  
 Tunnel Q= 4.1401

TAP	P(PSIA)	P/Pt0	P/Pt7	P/Pa	Cp	Mach #
PHASE 2 FAN INNER SURFACE	PS @ 345 DEG					
176	10.516		0.4263			
177	11.553		0.4683			
178	11.075		0.4489			
179	10.339		0.4191			
180	9.378		0.3802			

STA8	PT	PS	MACH
	22.791	21.449	0.2957
	22.806	21.388	0.3042
	22.826	21.373	0.3079
	22.915	21.304	0.3144
STA7			
	24.653	24.006	0.1953
	24.681	24.026	0.1965
	24.642	24.024	0.1908
	24.697	24.020	0.1997

	AVERAGE			Pt Dist	Ps Dist
STA8	22.809	21.378	0.3056	0.0080	0.0125
STA7	24.668	24.019	0.1955	0.0101	0.0032

USR1: [CH06, SET]PRCONF11, SET; 7

USR1: [CH06, SET]PZCONF12, SET; 2

USR1: [CH06, SET]PFCONF15, SET; 2

USR1: [CH06, SET]PBCONF12, SET; 1


DATA REDUCED WITH A DELTA FILE

PT7 PROFILE (PR22)

Job 2212 Phase 2


RUN = 223.01

<+> PT7 @ 3 deg 10' 05" (50-61)  
<X> PS7 @ 30 deg 51' 05" (53-8 & 102)  
<U> PT7 @ 58 deg 51' 05" (62-73)  
<Y> PS7 @ 128 deg 09' 05" (59 & 103)  
<\*> PT7 @ 188 deg 09' 05" (74-85)  
<#> PS7 @ 218 deg 09' 05" (100 & 104)  
<2> PT7 @ 278 deg 09' 05" (85-97)  
<\$> PS7 @ 308 deg 09' 05" (101 & 105)



PTS PROFILE (PL21)  
Job 2212 Phase 2  
RUN = 203.01

- (+) PTB @ 0 deg tdp5 (1-6)
- (X) PSB @ 15 deg tdp5 (25 & 29)
- (D) PTB @ 90 deg tdp5 (7-12)
- (Y) PSB @ 105 deg tdp5 (26 & 30)
- (\*) PTB @ 180 deg tdp5 (13-18)
- (#) PSB @ 150 deg tdp5 (27 & 31)
- (Z) PTB @ 270 deg tdp5 (19-24)
- (\\$) PSB @ 285 deg tdp5 (28 & 32)




## FAN STATIC PRESSURE DISTRIBUTION (PL24)

Job 2212 Phase 2

RUN = 203.01

- (+) PS/PT17 0300deg (taps 131-160)
- (X) PS/PT17 0330deg (taps 161-170)
- (O) PS/PT17 0345deg (taps 171-180)

3T24C'  $_{22.5^\circ}$ 



$3B'C_{22.5}^0$



Data Point = 204.01  
Nozzle Description = 3B'C22.5  
Pt7/Pa = 2.591  
Pt7/Pt8 = 1.085  
Mach Number = 0.789



## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 13:46:05  
 Job Number= 2212  
 Pt0= 14.385  
 Mach number= 0.789  
 Tunnel Rn= 3.746E+06

Run Number= 204.01  
 File Id= 06295134605  
 Bar. (Psia)= 14.423  
 Ptunnel (Psia)= 9.536  
 Tunnel Q= 4.1593

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
<b>TUNNEL FLOOR STATICS</b>						
701	9.540			0.0008	0.7890	
702	9.521			-0.0038	0.7910	
703	9.642			0.0253	0.7781	
704	9.501			-0.0086	0.7932	
705	9.478			-0.0141	0.7955	
706	9.477			-0.0144	0.7957	
707	9.531			-0.0014	0.7900	
708	9.417			-0.0288	0.8021	
709	9.358			-0.0430	0.8084	
710	9.273			-0.0634	0.8175	
711	9.386			-0.0362	0.8054	
712	9.491			-0.0110	0.7942	
713	9.512			-0.0060	0.7920	
714	9.547			0.0025	0.7883	
715	9.510			-0.0064	0.7922	
<b>TUNNEL CEILING STATICS</b>						
720	9.539			0.0005	0.7891	
721	9.511			-0.0062	0.7921	
722	9.504			-0.0079	0.7923	
723	9.535			-0.0004	0.7895	
724	9.462			-0.0180	0.7973	
725	9.427			-0.0264	0.8011	
726	9.421			-0.0278	0.8017	
727	9.345			-0.0461	0.8098	
728	9.344			-0.0463	0.8099	
729	9.478			-0.0141	0.7956	
730	9.544			0.0017	0.7886	
731	9.583			0.0111	0.7844	
732	9.588			0.0123	0.7839	
<b>TUNNEL WEST WALL STATICS</b>						
760	9.605			0.0164	0.7821	
761	9.493			-0.0105	0.7940	
762	9.519			-0.0045	0.7914	
763	9.382			-0.0372	0.8059	
764	9.448			-0.0213	0.7988	
765	9.539			0.0005	0.7891	
766	9.679			0.0342	0.7742	
<b>TUNNEL EAST WALL STATICS</b>						
790	9.620			0.0200	0.7805	

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 13:46:05	Run Number= 204.01
Job Number= 2212	File Id= 06295134605
Pt0= 14.385	Bar. (Psia)= 14.423
Mach number= 0.789	Ptunnel (Psia)= 9.536
Tunnel Rn= 3.746E+06	Tunnel Q= 4.1593

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
TUNNEL EAST WALL STATICS						
791	9.511				-0.0062	0.7921
792	9.422				-0.0276	0.8016
793	9.353				-0.0442	0.8090
794	9.504				-0.0079	0.7928
PT8 - RAKE @60 DEGREES						
1	22.803	1.0010				
2	22.817	1.0016				
3	22.797	1.0007				
4	22.764	0.9993				
5	22.721	0.9974				
6	22.667	0.9950				
AVERAGE=	22.761	Distortion .0066				
PS8 - STATICS						
25	21.455	0.9418				
29	21.315	0.9357				
AVERAGE=	21.385	Distortion .0065				
PT8 - RAKE @150 DEGREES						
7	22.799	1.0008				
8	22.748	0.9986				
9	22.755	0.9989				
10	22.777	0.9999				
11	22.820	1.0018				
12	22.768	0.9995				
AVERAGE=	22.777	Distortion .0032				
PS8 - STATICS						
26	21.331	0.9364				
30	21.297	0.9349				
AVERAGE=	21.314	Distortion .0016				
PT8 - RAKE @240 DEGREES						
Fixed 13	22.808	1.0012				
14	22.748	0.9986				
15	22.794	1.0006				
16	22.791	1.0005				
17	22.845	1.0029				
18	22.785	1.0002				
AVERAGE=	22.795	Distortion .0043				
PS8 - STATICS						
27	21.321	0.9360				
31	21.277	0.9340				
AVERAGE=	21.299	Distortion .0021				

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 13:46:05  
 Job Number= 2212  
 Pt0= 14.385  
 Mach number= 0.789  
 Tunnel Rn= 3.746E+06

Run Number= 204.01  
 File Id= 06295134605  
 Bar. (Psia)= 14.423  
 Ptunnel (Psia)= 9.536  
 Tunnel Q= 4.1593

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PT8 - RAKE @30 DEGREES						
19	22.823	1.0019				
20	22.795	1.0007				
Fixed 21	22.782	1.0001				
22	22.788	1.0004				
23	22.854	1.0032				
24	22.666	0.9950				
AVERAGE=	22.784	Distortion .0083				
PS8 - STATICS						
28	21.262	0.9334				
32	21.199	0.9306				
AVERAGE=	21.230	Distortion .0030				
PT7 - RAKE @0 DEGREES						
50	24.686		0.9989			
51	24.669		0.9982			
Fixed 52	24.674		0.9984			
53	24.680		0.9986			
54	24.674		0.9984			
55	24.680		0.9986			
56	24.707		0.9997			
57	24.732		1.0007			
58	24.762		1.0020			
59	24.780		1.0027			
60	24.711		0.9999			
61	24.587		0.9949			
AVERAGE=	24.695	Distortion .0078				
PS7 - STATICS @30 DEGREES						
98	24.009		0.9715			
102	24.084		0.9745			
AVERAGE=	24.046	Distortion .0031				
PT7 - RAKE @90 DEGREES						
62	24.673		0.9984			
63	24.770		1.0023			
64	24.782		1.0028			
65	24.782		1.0028			
66	24.773		1.0024			
67	24.759		1.0018			
68	24.707		0.9997			
69	24.708		0.9998			
70	24.693		0.9992			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 13:45:05  
 Job Number= 2212  
 Pt0= 14.385  
 Mach number= 0.789  
 Tunnel Rn= 3.746E+06

Run Number= 204.01  
 File Id= 06295134605  
 Bar. (Psia)= 14.423  
 Ptunnel (Psia)= 9.536  
 Tunnel Q= 4.1593

TAP	P(PSIA)	P/Pt0	P/Pt7	P/Pa	Cp	Mach #
PT7 - RAKE @90 DEGREES						
71	24.684		0.9988			
72	24.686		0.9989			
73	24.714		1.0000			
AVERAGE=	24.727	Distortion	.0044			
PS7 - STATICS @120 DEGREES						
99	24.045		0.9729			
103	24.082		0.9744			
AVERAGE=	24.063	Distortion	.0015			
PT7 - RAKE @180 DEGREES						
74	24.693		0.9992			
75	24.685		0.9988			
76	24.702		0.9995			
77	24.673		0.9984			
78	24.626		0.9965			
79	24.614		0.9960			
80	24.635		0.9968			
81	24.681		0.9987			
82	24.721		1.0003			
83	24.735		1.0009			
84	24.736		1.0009			
85	24.737		1.0009			
AVERAGE=	24.686	Distortion	.0050			
PS7 - STATICS @210 DEGREES						
100	24.115		0.9758			
104	24.080		0.9744			
AVERAGE=	24.097	Distortion	.0015			
PT7 - RAKE @270 DEGREES						
86	24.707		0.9997			
87	24.828		1.0046			
88	24.837		1.0050			
89	24.814		1.0041			
90	24.790		1.0031			
91	24.727		1.0005			
92	24.704		0.9996			
Fixed	93	24.707	0.9997			
	94	24.700	0.9994			
	95	24.695	0.9992			
	96	24.702	0.9995			
	97	24.691	0.9991			
AVERAGE=	24.741	Distortion	.0059			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 13:46:05  
 Job Number= 2212  
 Pt0= 14.385  
 Mach number= 0.789  
 Tunnel Rn= 3.746E+06

Run Number= 204.01  
 File Id= 06295134605  
 Bar. (Psia)= 14.423  
 Ptunnel (Psia)= 9.536  
 Tunnel Q= 4.1593

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PS7 - STATICS @300 DEGREES						
Fixed 101	24.056		0.9734			
105	24.084		0.9745			
AVERAGE=	24.070	Distortion .0011				
EXTERNAL FAN NACELLE						
111						
112						
115						
120						
B. L. PT RAKE						
122	12.327			1.2926		
125	13.113			1.3750		
PHASE 2 FAN INNER SURFACE PS @ 300 DEG						
151	11.049		0.4471			
152	9.505		0.3846			
153	8.576		0.3470			
154	9.807		0.3968			
155	10.207		0.4130			
156	10.438		0.4223			
157	11.772		0.4763			
158	11.235		0.4546			
159	10.377		0.4199			
160	9.234		0.3736			
PHASE 2 FAN INNER SURFACE PS @ 330 DEG						
161	11.003		0.4452			
162	9.505		0.3846			
163	8.605		0.3482			
164	9.879		0.3997			
165	10.154		0.4109			
166	10.226		0.4138			
167	11.501		0.4654			
168	11.304		0.4574			
169	10.404		0.4210			
170	9.190		0.3718			
PHASE 2 FAN INNER SURFACE PS @ 345 DEG						
171	11.078		0.4482			
172	9.580		0.3876			
173	8.679		0.3512			
174	9.892		0.3966			
175	10.176		0.4117			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 13:46:05	Run Number= 204.01
Job Number= 2212	File Id= 06295134605
Pt0= 14.395	Bar. (Psia)= 14.423
Mach number= 0.789	Ptunnel (Psia)= 9.536
Tunnel Rn= 3.746E+06	Tunnel Q= 4.1593

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PHASE 2 FAN INNER SURFACE PS @ 345 DEG						
176	10.318		0.4175			
177	11.415		0.4619			
178	11.209		0.4535			
179	10.496		0.4247			
180	9.365		0.3789			

STAB	PT	PS	MACH
22.761	21.374	0.3011	
22.778	21.311	0.3098	
22.795	21.296	0.3133	
22.783	21.226	0.3198	
STA7			
24.696	24.052	0.1946	
24.728	24.067	0.1972	
24.687	24.097	0.1862	
24.743	24.074	0.1982	

	AVERAGE		Pt Dist	Ps Dist
STAB	22.780	21.302	0.3110	0.0083
STA7	24.713	24.072	0.1940	0.0101

USR1: [CH06, SET]PRCONF11, SET; 7  
 USR1: [CH06, SET]PZCONF12, SET; 2  
 USR1: [CH06, SET]PFCONF15, SET; 2


USR1: [CH06, SET]PBCONF12, SET; 1  
 DATA REDUCED WITH A DELTA FILE

## FTT PROFILE (PR22)

Job 2212 Phase 2

RUN = 224.01

- (+) PTT 0 0 deg tps (30-51)
- (X) PTT 0 30 deg tps (98 & 102)
- (D) PTT 0 50 deg tps (62-73)
- (Y) PTT 0120 deg tps (95 & 103)
- (\*) PTT 0180 deg tps (74-85)
- (#) PTT 0210 deg tps (100 & 104)
- (2) PTT 0270 deg tps (85-97)
- (\*) PTT 0300 deg tps (101 & 105)




## PTS PROFILE (PL21)

Job 2212 Phase 2

RUN = 234.01

- (+) PTB @ 0 deg taps (1-6)
- (X) P5B @ 15 deg taps (25 & 29)
- (D) PTB @ 30 deg taps (7-12)
- (Y) P5B @ 165 deg taps (26 & 30)
- (\*) PTB @ 180 deg taps (13-18)
- (#) P5B @ 195 deg taps (27 & 31)
- (2) PTB @ 270 deg taps (19-24)
- (\\$) P5B @ 285 deg taps (28 & 32)




FAN STATIC PRESSURE DISTRIBUTION (PFL24)

Job 2212 Phase 2

RUN = 2214, 01

- (+) PS/P17 E300deg (11PS 151-160)
- (X) PS/P17 E350deg (11PS 161-170)
- (O) PS/P17 E345deg (11PS 171-180)

3 B' C<sub>22.5°</sub>





$$3B'C_0^0$$

$3B'C_0^0$



Data Point = 205.01  
Nozzle Description = 3B'C<sub>0</sub>  
Pt7/Pa = 2.626  
Pt7/Pt8 = 1.091  
Mach Number = 0.803



## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 15:39:11  
 Job Number= 2212  
 Pt0= 14.366  
 Mach number= 0.803  
 Tunnel Rn= 3.596E+06

Run Number= 205.01  
 File Id= 06295153911  
 Bar. (Psia)= 14.405  
 Ptunnel (Psia)= 9.393  
 Tunnel Q= 4.2435

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
<b>TUNNEL FLOOR STATICS</b>						
701	9.410				0.0041	0.8015
702	9.393				0.0000	0.8034
703	9.522				0.0304	0.7896
704	9.374				-0.0044	0.8054
705	9.347				-0.0108	0.8083
706	9.344				-0.0115	0.8086
707	9.410				0.0041	0.8015
708	9.276				-0.0275	0.8159
709	9.213				-0.0424	0.8226
710	9.107				-0.0674	0.8339
711	9.234				-0.0374	0.8204
712	9.340				-0.0124	0.8090
713	9.372				-0.0049	0.8056
714	9.410				0.0041	0.8015
715	9.373				-0.0047	0.8055
<b>TUNNEL CEILING STATICS</b>						
720	9.393				0.0000	0.8034
721	9.372				-0.0049	0.8056
722	9.367				-0.0061	0.8061
723	9.395				0.0005	0.8031
724	9.320				-0.0172	0.8112
725	9.280				-0.0266	0.8154
726	9.277				-0.0273	0.8158
727	9.193				-0.0471	0.8247
728	9.188				-0.0483	0.8253
729	9.334				-0.0139	0.8097
730	9.400				0.0017	0.8026
731	9.444				0.0121	0.7979
732	9.451				0.0137	0.7972
<b>TUNNEL WEST WALL STATICS</b>						
760	9.463				0.0165	0.7959
761	9.346				-0.0110	0.8084
762	9.374				-0.0044	0.8054
763	9.233				-0.0377	0.8205
764	9.303				-0.0212	0.8130
765	9.393				0.0000	0.8034
766	9.543				0.0354	0.7873
<b>TUNNEL EAST WALL STATICS</b>						
790	9.489				0.0227	0.7931

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 15:39:11  
 Job Number= 2212  
 Pt0= 14.366  
 Mach number= 0.803  
 Tunnel Rn= 3.596E+06

Run Number= 205.01  
 File Id= 06295153911  
 Bar. (Psia)= 14.405  
 Ptunnel (Psia)= 9.393  
 Tunnel Q= 4.2435

TAP	P(PSIA)	P/Pt0	P/Pt7	P/Pa	Cp	Mach #
TUNNEL EAST WALL STATICS						
791	9.375				-0.0042	0.8053
792	9.284				-0.0256	0.8150
793	9.205				-0.0443	0.8235
794	9.363				-0.0070	0.8066
PT8 - RAKE @60 DEGREES						
1	22.624	1.0011				
2	22.641	1.0018				
3	22.610	1.0004				
4	22.584	0.9993				
5	22.535	0.9971				
6	22.480	0.9947				
AVERAGE=	22.579	Distortion .0071				
PS8 - STATICS						
25	21.292	0.9421				
29	21.144	0.9356				
AVERAGE=	21.218	Distortion .0070				
PT8 - RAKE @150 DEGREES						
7	22.618	1.0008				
8	22.569	0.9986				
9	22.576	0.9989				
10	22.601	1.0000				
11	22.639	1.0017				
12	22.591	0.9996				
AVERAGE=	22.599	Distortion .0031				
PS8 - STATICS						
26	21.161	0.9363				
30	21.129	0.9349				
AVERAGE=	21.145	Distortion .0015				
PT8 - RAKE @240 DEGREES						
Fixed 13	22.627	1.0012				
14	22.570	0.9987				
15	22.617	1.0008				
16	22.615	1.0007				
17	22.665	1.0029				
18	22.604	1.0002				
AVERAGE=	22.616	Distortion .0042				
PS8 - STATICS						
27	21.154	0.9360				
31	21.114	0.9343				
AVERAGE=	21.134	Distortion .0019				

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 15:39:11  
 Job Number= 2212  
 Pt0= 14.366  
 Mach number= 0.803  
 Tunnel Rn= 3.596E+06

Run Number= 205.01  
 File Id= 06295153911  
 Bar. (Psia)= 14.405  
 Ptunnel (Psia)= 9.393  
 Tunnel Q= 4.2435

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PT8 - RAKE @30 DEGREES						
19	22.639	1.0017				
20	22.616	1.0007				
Fixed 21	22.601	1.0000				
22	22.607	1.0003				
23	22.673	1.0032				
24	22.491	0.9952				
AVERAGE=	22.604	Distortion .0081				
PS9 - STATICS						
28	21.089	0.9331				
32	21.026	0.9304				
AVERAGE=	21.057	Distortion .0030				
PT7 - RAKE @0 DEGREES						
50	24.640		0.9990			
51	24.628		0.9986			
Fixed 52	24.631		0.9987			
53	24.635		0.9988			
54	24.628		0.9986			
55	24.638		0.9990			
56	24.664		1.0000			
57	24.681		1.0007			
58	24.716		1.0021			
59	24.728		1.0026			
60	24.672		1.0003			
61	24.529		0.9945			
AVERAGE=	24.649	Distortion .0081				
PS7 - STATICS @30 DEGREES						
98	23.962		0.9715			
102	24.033		0.9744			
AVERAGE=	23.997	Distortion .0030				
PT7 - RAKE @90 DEGREES						
62	24.619		0.9982			
63	24.715		1.0021			
64	24.729		1.0026			
65	24.725		1.0025			
66	24.723		1.0024			
67	24.695		1.0013			
68	24.655		0.9996			
69	24.653		0.9996			
70	24.637		0.9989			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 15:39:11  
 Job Number= 2212  
 Pt0= 14.366  
 Mach number= 0.803  
 Tunnel Rn= 3.596E+06

Run Number= 205.01  
 File Id= 06295153911  
 Bar. (Psia)= 14.405  
 Ptunnel (Psia)= 9.393  
 Tunnel Q= 4.2435

TAP	P(PSIA)	P/Pt0	P/Pt7	P/Pa	Cp	Mach #
PT7 - RAKE @90 DEGREES						
71	24.631		0.9987			
72	24.636		0.9989			
73	24.667		1.0001			
AVERAGE=	24.674	Distortion	.0045			
PS7 - STATICS @120 DEGREES						
99	24.001		0.9731			
103	24.030		0.9743			
AVERAGE=	24.015	Distortion	.0012			
PT7 - RAKE @180 DEGREES						
74	24.645		0.9992			
75	24.638		0.9990			
76	24.648		0.9994			
77	24.617		0.9981			
78	24.573		0.9963			
79	24.564		0.9960			
80	24.581		0.9966			
81	24.630		0.9986			
82	24.664		1.0000			
83	24.683		1.0008			
84	24.686		1.0009			
85	24.681		1.0007			
AVERAGE=	24.634	Distortion	.0050			
PS7 - STATICS @210 DEGREES						
100	24.010		0.9735			
104	24.031		0.9743			
AVERAGE=	24.020	Distortion	.0009			
PT7 - RAKE @270 DEGREES						
86	24.680		1.0007			
87	24.781		1.0048			
88	24.785		1.0049			
89	24.767		1.0042			
90	24.732		1.0028			
91	24.686		1.0009			
92	24.656		0.9997			
Fixed 93	24.655		0.9996			
94	24.653		0.9996			
95	24.645		0.9992			
96	24.651		0.9995			
97	24.639		0.9990			
AVERAGE=	24.694	Distortion	.0059			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 15:39:11  
 Job Number= 2212  
 Pt0= 14.366  
 Mach number= 0.803  
 Tunnel Rn= 3.596E+06

Run Number= 205.01  
 File Id= 06295153911  
 Bar. (Psia)= 14.405  
 Ptunnel (Psia)= 9.393  
 Tunnel Q= 4.2435

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PS7 -	STATICS @300 DEGREES					
Fixed 101	23.991		0.9727			
105	24.030		0.9743			
AVERAGE=	24.010	Distortion .0016				
EXTERNAL FAN NACELLE						
111						
112						
115						
120						
B. L. PT RAKE						
122	12.198			1.2987		
125	12.976			1.3815		
PHASE 2 FAN INNER SURFACE PS @ 300 DEG						
151	10.999		0.4460			
152	9.418		0.3819			
153	8.550		0.3467			
154	9.882		0.4007			
155	9.692		0.3930			
156	10.357		0.4199			
157	11.387		0.4617			
158	11.351		0.4602			
159	10.509		0.4261			
160	9.187		0.3725			
PHASE 2 FAN INNER SURFACE PS @ 330 DEG						
161	10.964		0.4445			
162	9.418		0.3819			
163	8.477		0.3437			
164	10.003		0.4056			
165	9.699		0.3932			
166	10.234		0.4149			
167	11.149		0.4520			
168	11.385		0.4616			
169	10.564		0.4283			
170	9.206		0.3733			
PHASE 2 FAN INNER SURFACE PS @ 345 DEG						
171	11.025		0.4470			
172	9.497		0.3847			
173	8.680		0.3519			
174	9.969		0.4042			
175	9.650		0.3913			

PRESS. EXE

22-Oct-98 03:46 PM

Page 6

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 22-OCT-98 15:39:11	Run Number= 205.01
Job Number= 2212	File Id= 06295153911
Pt0= 14.366	Bar. (Psia)= 14.405
Mach number= 0.803	Ptunnel (Psia)= 9.393
Tunnel Rn= 3.596E+06	Tunnel Q= 4.2435

TAP	P(PSIA)	P/Pt0	P/Pt7	P/Pa	Cp	Mach #
PHASE 2 FAN INNER SURFACE			PS @ 345 DEG			
176	10.277		0.4167			
177	11.101		0.4501			
178	11.253		0.4563			
179	10.677		0.4329			
180	9.272		0.3759			

STAB	PT	PS	MACH
22.579	21.207	0.3006	
22.599	21.143	0.3100	
22.616	21.131	0.3130	
22.605	21.053	0.3203	
STA7			
24.650	24.003	0.1953	
24.674	24.018	0.1966	
24.635	24.023	0.1899	
24.695	24.015	0.2001	

	AVERAGE			Pt Dist	Ps Dist
STAB	22.600	21.133	0.3110	0.0085	0.0126
STA7	24.664	24.015	0.1955	0.0104	0.0030

USR1: [CH06, SET]PRCONF11, SET; 7

USR1: [CH06, SET]PBCONF12, SET; 1

USR1: [CH06, SET]PZCONF12, SET; 2

DATA REDUCED WITH A DELTA FILE


USR1: [CH06, SET]PFCONF15, SET; 2

PTB PROFILE (PL21)

Job 2212 Phase 2


RUN = 2335.31

- <+> PTB @ 0 deg 1dp5 (1-6)
- <X> PSB @ 15 deg 1dp5 (25 & 29)
- <D> PTB @ 90 deg 1dp5 (7-12)
- <Y> PSB @ 105 deg 1dp5 (26 & 30)
- <\*> PTB @ 180 deg 1dp5 (13-18)
- <#> PSB @ 150 deg 1dp5 (27 & 31)
- <2> PTB @ 270 deg 1dp5 (19-25)
- <\$> PSB @ 285 deg 1dp5 (28 & 32)



PT7 PROFILE (PR22)  
Job 2212 Phase 2  
RUN = 235.31

- (+) P117 E 0 deg TAPS (50-61)
- (X) P57 E 38 deg TAPS (98 & 102)
- (D) P117 E 90 deg TAPS (62-73)
- (Y) P57 E120 deg TAPS (59 & 103)
- (\*) P117 E180 deg TAPS (74-85)
- (#) P57 E210 deg TAPS (100 & 104)
- (2) P117 E270 deg TAPS (86-97)
- (\\$) P57 E300 deg TAPS (101 & 105)




## FH1 STATIC PRESSURE DISTRIBUTION (P124)

Job 2212 Phase 2

RUN = 205.01

- (+) PS/P17 0320168 (TAPS 151-160)
- (X) PS/P17 0330168 (TAPS 161-170)
- (O) PS/P17 0345168 (TAPS 171-180)

3 B' C°





3B'B



Data Point = 206.01  
Nozzle Description = 3B'B  
Pt7/Pa = 2.621  
Pt7/Pt8 = 1.080  
Mach Number = 0.801



## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 26-OCT-98 09:46:10  
 Job Number= 2212  
 Pt0= 14.243  
 Mach number= 0.801  
 Tunnel Rn= 3.557E+06

Run Number= 206.01  
 File Id= 06299084610  
 Bar. (Psia)= 14.281  
 Ptunnel (Psia)= 9.332  
 Tunnel Q= 4.1934

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
<b>TUNNEL FLOOR STATICS</b>						
701	9.339			0.0016	0.8005	
702	9.321			-0.0027	0.8024	
703	9.448			0.0276	0.7888	
704	9.299			-0.0080	0.8048	
705	9.277			-0.0132	0.8072	
706	9.272			-0.0144	0.8077	
707	9.337			0.0011	0.8007	
708	9.208			-0.0297	0.8146	
709	9.139			-0.0461	0.8221	
710	9.050			-0.0674	0.8317	
711	9.169			-0.0390	0.8188	
712	9.285			-0.0113	0.8063	
713	9.302			-0.0073	0.8045	
714	9.340			0.0018	0.8004	
715	9.305			-0.0065	0.8042	
<b>TUNNEL CEILING STATICS</b>						
720	9.327			-0.0013	0.8018	
721	9.300			-0.0077	0.8047	
722	9.298			-0.0082	0.8049	
723	9.324			-0.0020	0.8021	
724	9.249			-0.0199	0.8102	
725	9.213			-0.0285	0.8141	
726	9.203			-0.0309	0.8152	
727	9.125			-0.0495	0.8236	
728	9.125			-0.0495	0.8236	
729	9.264			-0.0163	0.8086	
730	9.331			-0.0003	0.8014	
731	9.366			0.0080	0.7976	
732	9.373			0.0097	0.7968	
<b>TUNNEL WEST WALL STATICS</b>						
760	9.396			0.0152	0.7944	
761	9.280			-0.0125	0.8069	
762	9.307			-0.0061	0.8040	
763	9.170			-0.0387	0.8187	
764	9.236			-0.0230	0.8116	
765	9.323			-0.0023	0.8022	
766	9.471			0.0330	0.7863	
<b>TUNNEL EAST WALL STATICS</b>						
790	9.415			0.0197	0.7923	

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 26-OCT-98 08:46:10  
 Job Number= 2212  
 Pt0= 14.243  
 Mach number= 0.801  
 Tunnel Rn= 3.557E+06

Run Number= 206.01  
 File Id= 06299084610  
 Bar. (Psia)= 14.281  
 Ptunnel (Psia)= 9.332  
 Tunnel Q= 4.1934

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
TUNNEL EAST WALL STATICS						
791	9.304				-0.0068	0.8043
792	9.212				-0.0287	0.8142
793	9.140				-0.0459	0.8220
794	9.297				-0.0085	0.8050
PT8 - RAKE @60 DEGREES						
1	22.687	1.0012				
2	22.699	1.0017				
3	22.675	1.0007				
4	22.643	0.9993				
5	22.600	0.9974				
6	22.551	0.9952				
AVERAGE=	22.642	Distortion .0065				
PSS - STATICS						
25	21.351	0.9422				
29	21.192	0.9352				
AVERAGE=	21.271	Distortion .0075				
PT8 - RAKE @150 DEGREES						
7	22.658	0.9999				
8	22.631	0.9987				
9	22.637	0.9990				
10	22.660	1.0000				
11	22.693	1.0015				
12	22.647	0.9994				
AVERAGE=	22.654	Distortion .0027				
PSS - STATICS						
26	21.216	0.9363				
30	21.176	0.9345				
AVERAGE=	21.196	Distortion .0019				
PT8 - RAKE @240 DEGREES						
Fixed 13	22.681	1.0009				
14	22.634	0.9989				
15	22.677	1.0008				
16	22.675	1.0007				
17	22.728	1.0030				
18	22.669	1.0004				
AVERAGE=	22.677	Distortion .0041				
PSS - STATICS						
27	21.207	0.9359				
31	21.171	0.9343				
AVERAGE=	21.189	Distortion .0017				

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 26-OCT-98 08:46:10  
 Job Number= 2212  
 Pt0= 14.243  
 Mach number= 0.901  
 Tunnel Rn= 3.557E+06

Run Number= 206.01  
 File Id= 06299084610  
 Bar. (Psia)= 14.281  
 Ptunnel (Psia)= 9.332  
 Tunnel Q= 4.1934

TAP	P(PSIA)	P/Pt0	P/Pt7	P/Pa	Cp	Mach #
<b>PTB - RAKE @330 DEGREES</b>						
19	22.698	1.0017				
20	22.681	1.0009				
Fixed 21	22.663	1.0001				
22	22.662	1.0001				
23	22.733	1.0032				
24	22.548	0.9951				
AVERAGE=	22.664	Distortion .0082				
<b>PS8 - STATICS</b>						
28	21.168	0.9342				
32	21.076	0.9301				
AVERAGE=	21.122	Distortion .0044				
<b>PT7 - RAKE @0 DEGREES</b>						
50	24.430		0.9987			
51	24.421		0.9983			
Fixed 52	24.424		0.9985			
53	24.428		0.9986			
54	24.427		0.9986			
55	24.433		0.9988			
56	24.457		0.9998			
57	24.481		1.0008			
58	24.511		1.0020			
59	24.518		1.0023			
60	24.455		0.9997			
61	24.325		0.9944			
AVERAGE=	24.442	Distortion .0079				
<b>PS7 - STATICS @30 DEGREES</b>						
98	23.768		0.9716			
102	23.845		0.9748			
AVERAGE=	23.806	Distortion .0032				
<b>PT7 - RAKE @90 DEGREES</b>						
62	24.424		0.9984			
63	24.512		1.0020			
64	24.529		1.0027			
65	24.527		1.0027			
66	24.522		1.0024			
67	24.504		1.0017			
68	24.462		1.0000			
69	24.451		0.9995			
70	24.439		0.9991			

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 26-OCT-98 08:46:10	Run Number= 206.01
Job Number= 2212	File Id= 06299084610
Pt0= 14.243	Bar. (Psia)= 14.281
Mach number= 0.801	Ptunnel (Psia)= 9.332
Tunnel Rn= 3.557E+06	Tunnel Q= 4.1934

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PT7 - RAKE @90 DEGREES						
71	24.430		0.9987			
72	24.438		0.9990			
73	24.475		1.0005			
AVERAGE=	24.476	Distortion .0043				
PS7 - STATICS @120 DEGREES						
99	23.927		0.9781			
103	23.847		0.9749			
AVERAGE=	23.887	Distortion .0033				
PT7 - RAKE @180 DEGREES						
74	24.449		0.9995			
75	24.435		0.9989			
76	24.451		0.9995			
77	24.424		0.9984			
78	24.384		0.9968			
79	24.375		0.9964			
80	24.383		0.9968			
81	24.432		0.9988			
82	24.466		1.0002			
83	24.482		1.0008			
84	24.481		1.0008			
85	24.484		1.0009			
AVERAGE=	24.437	Distortion .0045				
PS7 - STATICS @210 DEGREES						
100	23.807		0.9732			
104	23.847		0.9749			
AVERAGE=	23.827	Distortion .0017				
PT7 - RAKE @270 DEGREES						
86	24.493		1.0013			
87	24.576		1.0047			
88	24.579		1.0048			
89	24.556		1.0038			
90	24.522		1.0024			
91	24.481		1.0008			
92	24.456		0.9998			
Fixed 93	24.454		0.9997			
94	24.444		0.9993			
95	24.442		0.9992			
96	24.440		0.9991			
97	24.430		0.9987			
AVERAGE=	24.499	Distortion .0061				

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 26-OCT-98 08:46:10  
 Job Number= 2212  
 Pt0= 14.243  
 Mach number= 0.801  
 Tunnel Rn= 3.557E+06

Run Number= 206.01  
 File Id= 06299084610  
 Bar. (Psia)= 14.281  
 Ptunnel (Psia)= 9.332  
 Tunnel Q= 4.1934

TAP	P(PSIA)	P/Pt8	P/Pt7	P/Pa	Cp	Mach #
PS7 - STATICS @300 DEGREES						
Fixed 101	23.834		0.9743			
105	23.846		0.9748			
AVERAGE=	23.840	Distortion .0005				
EXTERNAL FAN NACELLE						
111	7.547			-0.4258		0.9974
112	5.732			-0.8586		1.2186
115	8.614			-0.1713		0.8790
120	9.737			0.0965		0.7576
B. L. PT RAKE						
122	12.155			1.3025		
125	12.930			1.3855		
PHASE 2 FAN INNER SURFACE PS @ 300 DEG						
151	12.509		0.5114			
152	9.612		0.3929			
153	8.663		0.3541			
154	8.698		0.3556			
155	8.885		0.3632			
156	9.143		0.3738			
157	10.069		0.4116			
158	12.216		0.4994			
159	11.566		0.4728			
160	9.732		0.3978			
PHASE 2 FAN INNER SURFACE PS @ 330 DEG						
161	12.562		0.5135			
162	9.567		0.3911			
163	8.663		0.3541			
164	8.733		0.3570			
165	8.822		0.3606			
166	8.926		0.3649			
167	9.891		0.4043			
168	12.277		0.5019			
169	11.642		0.4759			
170	9.799		0.4006			
PHASE 2 FAN INNER SURFACE PS @ 345 DEG						
171	12.701		0.5192			
172	9.712		0.3970			
173	8.739		0.3572			
174	8.684		0.3550			
175	8.826		0.3608			

PRESS. EXE

26-Oct-98 09:08 AM

Page 6

## FLUIDYNE AEROTEST LABORATORY

Run Day/Time= 26-OCT-98 09:46:10	Run Number= 206.01
Job Number= 2212	File Id= 06299084610
Pt0= 14.243	Bar. (Psia)= 14.291
Mach number= 0.801	Ptunnel (Psia)= 9.332
Tunnel Rn= 3.557E+06	Tunnel Q= 4.1934

TAP	P(PSIA)	P/Pt0	P/Pt7	P/Pa	Cp	Mach #
-----	---------	-------	-------	------	----	--------

PHASE 2 FAN INNER SURFACE PS @ 345 DEG

176	8.985	0.3673
177	9.933	0.4060
178	12.253	0.5009
179	11.710	0.4787
180	9.853	0.4028

STA8	PT	PS	MACH
------	----	----	------

22.642	21.259	0.3014
22.654	21.193	0.3101
22.677	21.186	0.3132
22.664	21.115	0.3196

STA7

24.443	23.812	0.1936
24.476	23.884	0.1875
24.437	23.830	0.1900
24.490	23.843	0.1960

## AVERAGE

STA8	22.659	21.188	0.3111	Pt Dist	Ps Dist
STA7	24.462	23.842	0.1918	0.0082	0.0130
				0.0104	0.0067

USR1:[CH06, SET]PRCONF11, SET; 7

USR1:[CH06, SET]PBCONF13, SET; 1

USR1:[CH06, SET]PZCONF12, SET; 2

DATA REDUCED WITH A DELTA FILE


USR1:[CH06, SET]PFCONF15, SET; 2

PTS PROFILE <PL21>

Job 2212 Phase 2

RUN = 255.01

- <+> PTB @ 0 deg taps (1-6)
- <X> PSB @ 15 deg taps (25 & 29)
- <D> PTB @ 30 deg taps (7-12)
- <Y> PSB @ 165 deg taps (26 & 30)
- <\*> PTB @ 180 deg taps (13-18)
- <#> PSB @ 195 deg taps (27 & 31)
- <2> PTB @ 270 deg taps (19-24)
- <3> PSB @ 285 deg taps (28 & 32)




PT7 PROFILE (PRTZ2)

Job 2212 Phase 2

RUN = Z65.01

- (+) PT7 @ 0 deg taps (50-61)
- (X) P57 @ 30 deg taps (33 & 102)
- (D) PT7 @ 50 deg taps (52-73)
- (Y) PT7 @120 deg taps (39 & 103)
- (\*) PT7 @160 deg taps (74-85)
- (#) P57 @210 deg taps (100 & 104)
- (2) PT7 @270 deg taps (86-97)
- (\\$) P57 @300 deg taps (101 & 105)



NACELLE EXTERNAL FS/Pt0 (PPL23)

Job 2212 Phase 2

RUN = 235.01


(+) TAP 111

(x) TAP 112

(o) TAP 115

(y) TAP 120

LINE - PHASE 1 RUN 61.01 3T24B (111-120)




## FAN STATIC PRESSURE DISTRIBUTION (PL24)

Job 2212 Phase 2

RUN = 235.01

- (+) PS/Pt7 030deg (taps 151-160)
- (X) PS/Pt7 033deg (taps 161-170)
- (D) PS/Pt7 0345deg (taps 171-180)



3 B' B








## PHOTOGRAPHS


























<b>REPORT DOCUMENTATION PAGE</b>				<i>Form Approved OMB No. 0704-0188</i>
<p>Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.</p>				
1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE	3. REPORT TYPE AND DATES COVERED	
		February 2001	Final Contractor Report	
4. TITLE AND SUBTITLE		5. FUNDING NUMBERS		
Static and Wind Tunnel Aero-Performance Tests of NASA AST Separate Flow Nozzle Noise Reduction Configurations		WU-781-30-12-00 NAS3-98021		
6. AUTHOR(S)				
Kevin L. Mikkelsen and Timothy J. McDonald				
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)		8. PERFORMING ORGANIZATION REPORT NUMBER		
Aero Systems Engineering, Inc. 358 East Fillmore Ave. St. Paul, Minnesota 55107		E-12658		
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES)		10. SPONSORING/MONITORING AGENCY REPORT NUMBER		
National Aeronautics and Space Administration Washington, DC 20546-0001		NASA CR—2001-210712		
11. SUPPLEMENTARY NOTES				
Aero Systems Engineering Inc. Proposal 975416, and FluidDyne Aerotest Group Report 2212. Project Manager, Naseem Saiyed, Structures and Acoustics Division, NASA Glenn Research Center, organization code 5940, 216-433-6736.				
12a. DISTRIBUTION/AVAILABILITY STATEMENT			12b. DISTRIBUTION CODE	
Unclassified - Unlimited Subject Category: 71  Available electronically at <a href="http://gltrs.grc.nasa.gov/GlTRS">http://gltrs.grc.nasa.gov/GlTRS</a> This publication is available from the NASA Center for AeroSpace Information, 301-621-0390.				
13. ABSTRACT (Maximum 200 words)				
<p>This report presents the results of cold flow model tests to determine the static and wind tunnel performance of several NASA AST separate flow nozzle noise reduction configurations. The tests were conducted by Aero Systems Engineering, Inc., for NASA Glenn Research Center. The tests were performed in the Channels 14 and 6 static thrust stands and the Channel 10 transonic wind tunnel at the FluiDyne Aerodynamics Laboratory in Plymouth, Minnesota. Facility checkout tests were made using standard ASME long-radius metering nozzles. These tests demonstrated facility data accuracy at flow conditions similar to the model tests. Channel 14 static tests reported here consisted of 21 ASME nozzle facility checkout tests and 57 static model performance tests (including 22 at no charge). Fan nozzle pressure ratio varied from 1.4 to 2.0, and fan to core total pressure ratio varied from 1.0 to 1.19. Core to fan total temperature ratio was 1.0. Channel 10 wind tunnel tests consisted of 15 tests at Mach number 0.28 and 31 tests at Mach 0.8. The sting was checked out statically in Channel 6 before the wind tunnel tests. In the Channel 6 facility, 12 ASME nozzle data points were taken and 7 model data points were taken. In the wind tunnel, fan nozzle pressure ratio varied from 1.73 to 2.8, and fan to core total pressure ratio varied from 1.0 to 1.19. Core to fan total temperature ratio was 1.0. Test results include thrust coefficients, thrust vector angle, core and fan nozzle discharge coefficients, total pressure and temperature charging station profiles, and boat-tail static pressure distributions in the wind tunnel (in Data Appendix).</p>				
14. SUBJECT TERMS				15. NUMBER OF PAGES
Acoustic nozzles; Discharge coefficient; Exhaust nozzles; Jet thrust; Mixers; Nozzle flow; Nozzle efficiency; Nozzle thrust coefficient; Power efficiency; Propulsive coefficient				303
				16. PRICE CODE
				A14
17. SECURITY CLASSIFICATION OF REPORT		18. SECURITY CLASSIFICATION OF THIS PAGE	19. SECURITY CLASSIFICATION OF ABSTRACT	20. LIMITATION OF ABSTRACT
Unclassified		Unclassified	Unclassified	